

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Piney Branch
	Elementary School
Date of Test Report	5/11/2022
Round of Testing	Initial
-	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	28
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.3 pCi/L

MCPS RADON TESTING – EXECUTIVE SUMMARY

Project Status: Initial testing completed; No further action needed



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

May 11, 2022

Brian T. Croyle, PG, CHMM Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re:	Radon Testing Services		
	KCI Job # 122108316		
Location:	Piney Branch Elementary School		
	7510 Maple Ave.		
	Takoma Park, MD 20912		

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Piney Branch Elementary School, located at 7510 Maple Ave. Takoma Park, MD 20912 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on March 15, 2022 and deployed thirty-one (31) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 18, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a

NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentration levels at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the low 20s and high temperatures ranged from the mid 70s to the high 50s Fahrenheit. Maximum sustained winds ranged from 0-32 miles per hour. Average humidity was around 61% with 0.1 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples			
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of		
less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that		
adequate laboratory measurement precision was achieved.			
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is		
	operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler McCleaf

Tyler P. McCleaf Radon Measurement Provider #111004 RT KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test LocationsB- Table 1-3, Radon Test Summary SpreadsheetsC- Laboratory Analytical Results

KCI TECHNOLOGIES, INC.

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal ACI- Air Check, Inc. D- Duplicate FB- Field Blank KCI- KCI Technologies, Inc. OB- Office Blank PM- Project Manager OC- Quality Control

Table 1- Radon Testing Results				
Piney Branch ES				
Test Period: 03/15/2022 - 03/18/2022				
Kit Number	Room / Area	Result		
11139715	202	< 0.3		
11139723	220	< 0.3		
11139721	407	< 0.3		
11139716	411	< 0.3		
11139374	AP	< 0.3		
11139747	BOILER ROOM OFFICE	< 0.3		
11139729	BSO2	< 0.3		
11139795	BUILDIMG SERVICE OFFICE	0.5		
11139781	CAFE	< 0.3		
11139794	CAFE	0.6		
11139736	COLLABORATIVE	< 0.3		
11139373	CONFERENCE ROOM	< 0.3		
11139731	COUNSELOR	< 0.3		
11139706	ESOL	< 0.3		
11139375	GYM	0.6		
11139793	GYM	0.6		
11139791	HEALTH	< 0.3		
11139796 HEALTH		< 0.3		
11139735	IMC	< 0.3		
11139734	JOHNSON	< 0.3		
11139800	KITCHEN OFFICE	< 0.3		
11139370	MAIN OFFICE	0.6		
11139730	ОТ	1.0		
11139792	ОТ	1.3		
11139790	PE OFFICE	< 0.3		
11139369	PRINCIPAL	< 0.3		
11139798	SDT	< 0.3		
11139799	STAFF LOUNGE	< 0.3		
11139708	STEM	0.6		
11139797	STEM	< 0.3		
11139722	WORK ROOM	< 0.3		

Table 2- Radon Testing Results				
	Piney B	ranch ES		
	Test Period: 03/15	/2022 - 03/18/2022		
Kit Number QC Type Room / Area Result				
11139796	D	Health	< 0.3	
11139797 FB Stem < 0.3				
11139792 D OT 1.3				
11138953	OB	OFFICE BLANK	< 0.3	
11138945 TB TRAVEL BLANK < 0.3				

Summary of Missed Locations			
Piney Branch ES			
Test Period: 03/15/22 - 03/18/22			
Kit Number	Room/Area	Result	
	NA		

Summary of Missing, Compromised and >/= 4 piC/L Tests			
Piney Branch ES			
Test Period: 03/15/22 - 03/18/22			
Kit Number	Room/Area	Result	
	NA		

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: PINEY BRANCH ES MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139715	202	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139723	220	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139721	407	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139716	411	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139374	AP	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139747	BOILER ROOM OFFICE	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139729	BSO2	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139795	BUILDIMG SERVICE OFFICE	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	0.5 ± 0.3	2022-03-21
11139781	CAFE	2022-03-15 @ 10:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139794	CAFE	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	0.6 ± 0.3	2022-03-21
11139736	COLLABORATIVE	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139373	CONFERENCE ROOM	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139731	COUNSELOR	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139706	ESOL	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139375	GYM	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	0.6 ± 0.3	2022-03-21
11139793	GYM	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	0.6 ± 0.3	2022-03-21
11139791	HEALTH	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139796	HEALTH	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139735	IMC	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139734	JOHNSON	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139800	KITCHEN OFFICE	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139370	MAIN OFFICE	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	0.6 ± 0.3	2022-03-21
11139792	OT	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	1.3 ± 0.3	2022-03-21
11139730	OT	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	1.0 ± 0.3	2022-03-21
11139790	PE OFFICE	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139369	PRINCIPAL	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139798	SDT	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139799	STAFF LOUNGE	2022-03-15 @ 10:00 an	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139708	STEM	2022-03-15 @ 11:00 an	n 2022-03-18 @ 12:00 pm	0.6 ± 0.3	2022-03-21
11139797	STEM	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21
11139722	WORK ROOM	2022-03-15 @ 11:00 ar	n 2022-03-18 @ 12:00 pm	< 0.3	2022-03-21

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, I	Job Nu	umber 204620
NOMINAL Conditions: Radon Conc 27.0 p	Ci/L Rel. Hum 50. 1	_% Temp. <u>70.0</u> F
Date Start: 3/18/22 Date Stop: 3/21/22	Date Start:	Date Stop:
Time Start: 0705 Time Stop: 0705	Time Start:	Time Stop:
Device No.'s: (5) Char Bags-	Device No.'s:	
11139367, 11139368, 11139371,		
11139710, 11139717		с.
E3 Right		10.1
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	
		Ω.
а — ", ц		~
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	42

1

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139367	SK1	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.9 ± 2.1	2022-03-30
11139368	SK2	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	23.9 ± 2.0	2022-03-30
11139371	SK3	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.7 ± 2.1	2022-03-30
11139710	SK4	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	26.4 ± 2.1	2022-03-30
11139717	SK5	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	24.6 ± 2.0	2022-03-30

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – March 2022 Schools

Name of Schools:

- 1. Singer, Flora M. ES
- 2. Sligo MS
- 3. Spring Mill Center
- 4. Fairland ES
- 5. Bel Pre ES
- 6. Shriver, Sargent ES
- 7. Strathmore ES
- 8. Viers Mill ES
- 9. Piney Branch ES

	Date	Initials
Radon Test Kits Deployed	03/15/2022	BMUN
Radon Test Kits Collected	03/18/2022	BUU
Radon Test Kits Shipped to Lab*	03/18/2022	BellI
Radon Test Kits Received by Lab*	03/20/2022	BIAL

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759