

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Bradley Hills Elementary School
Date of Report	3/5/2020
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	1
# Rooms ≥4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.0 pCi/L

Project Status

Current Project Status at this time: Retesting completed; no further action.



ENGINEERS . PLANNERS . SCIENTISTS . CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

3/5/2020

Mr. Richard Cox, MS
Team Leader
Montgomery County Public Schools
Division of Maintenance
Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #12146341.126

Location: Bradley Hills Elementary School 8701 Hartsdale Avenue Bethesda, Maryland 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Bradley Hills Elementary School, located at 8701 Hartsdale Avenue in Bethesda, Maryland 20817 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomer

KCI visited the site on 2/18/2020 and deployed two (2) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

1. Rooms with missing test kits from the December 2019 testing period (i.e. test kit was deployed but not recovered),

- 2. Rooms with invalidated test kits from the December 2019 testing period (e.g. an open window in the room or disturbed test kit),
- 3. Rooms which were locked/inaccessible during the December 2019 testing period,
- 4. Rooms with elevated December 2019 results (i.e. \geq 3.5 piC/L),
- 5. Rooms previously tested for radon but not tested in December 2019, and
- 6. Additional rooms that require testing (if applicable.)

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted nine (9) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on 2/21/2020 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the mid-20s to the lower-40s; and high temperatures ranged from the upper-30s to the upper-50s. Maximum sustained winds ranged from 13-21 miles per hour. Average humidity was approximately 50%. A total of .01 inches of rain were recorded during the testing period. The weather conditions during the testing period may have resulted in atypical radon test results for this facility.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Follow-up sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples		
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Mr. Tyler P. McCleaf Radon Measurement Provider KCI Technologies, Inc.

Attachments

A- Floor Plan with Test Locations

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

Floor Plan Legend

- X-Sample Location (in red)
- X- Previous Sample Location
- 1- Not Samled; No Ground Contact
- 2- Not Samled; Unoccupied (e.g. Storage, Mechanical)
- 3- Not Samled; High Humidity/Moisture
- 4- Not Samled; Bathroom/Hallway

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Table 1- Radon Testing Results		
Bradley Hills Elementary School		
Tes	t Period: 02/18/20-02/21	1/20
Kit Number	Room / Area	Result
9346906	127	1
9348571	OFFICE BLANK	< 0.3

Table 2- Radon Testing Results			
	Bradley Hills Elementary School		
Test Period: 02/18/20-02/21/20			
Kit Number	QC Type	Room / Area	Result
9348506	TRANSIT BLANK	NA	< 0.3

ATTACHMENT C

Laboratory Analytical Results

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9341725	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341730	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.1 ± 1.6	2020-02-26
9341728	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341726	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	25.8 ± 1.5	2020-02-26
9341731	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	25.1 ± 1.5	2020-02-26
9341729	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.2 ± 1.6	2020-02-26
9341727	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	27.2 ± 1.6	2020-02-26
9341732	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	27.3 ± 1.6	2020-02-26

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9341733		2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	26.4 ± 1.6	2020-02-26

** LABORATORY ANALYSIS REPORT **

Radon test result report for: S N/A

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9341729	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	26.2 ± 1.6	2020-02-26
9341727	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	27.2 ± 1.6	2020-02-26
9341732	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	27.3 ± 1.6	2020-02-26
9341725	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341730	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	26.1 ± 1.6	2020-02-26
9341728	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341726	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	25.8 ± 1.5	2020-02-26
9341731	N/A	2020-02-21 @ 8:00 am	2020-02-24 @ 8:00 am	25.1 ± 1.5	2020-02-26
75 11751	1,711	2020 02 21 € 0.00 4111	2020 02 21 C 0.00 um	20.1 = 1.0	2020 02 20

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technolog	gies, Inc.	Job Number 194523	_
NOMINAL Conditions: Radon Conc 45.8	,		F
Date Start: 2/21/20 Date Stop: 2/24/2	20 Date Start:	Date Stop:	
Time Start: Q745 Time Stop: Q743	Time Start:	Time Stop:	
Device No.'s: (9) Char Bags-	Device No.'s:_		
9341725 thru 9341733			
52 Ceft		1	
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:	'se	
22 25			
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:		
		φ.	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

February 26, 2020

** LABORATORY ANALYSIS REPORT **

Radon test result report for: BRADLEY HILLS MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9346906	127	2020-02-18 @ 1:00 pm	2020-02-21 @ 10:00 am	1.0 ± 0.4	2020-02-26
		•			

Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon 2019 Week 3

Name of Schools:

- 1. Bannockburn E.S.
- 2. Bradley Hills E.S.
- 3. East Silver Spring E.S.
- 4. Einstein H.S.
- 5. Flora M. Singer E.S.
- 6. Francis Scott Key M.S.

- 7. Jones Lane E.S.
- 8. Montgomery Blair H.S.
- 9. Oak View E.S.
- 10. Redland M.S.
- 11. Springbrook H.S.

	Date	Initials
Radon Test Kits Deployed	2/18/20	SM
Radon Test Kits Collected	2/21/20	M
Radon Test Kits Shipped to Lab*	2/21/20	\$\langle M\rangle
Radon Test Kits Received by Lab*	2/24/20	(M)

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Bradley Hills Elementary School
Date of Report	2/21/2020
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	50
# Rooms ≥4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.6 pCi/L

Project Status

Current Project Status at this time: Testing Complete; missing/compromised tests to be sampled.



936 RIDGEBROOK ROAD . SPARKS, MD 21152 . 410-316-7800 . (FAX) 410-316-7935

2/21/2020

Mr. Richard Cox, MS Environmental Team Leader Montgomery County Public Schools Division of Maintenance Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #12146341126

Location: Bradley Hills Elementary School 8701 Hartsdale Avenue Bethesda, Maryland 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Bradley Hills Elementary School, located at 8701 Hartsdale Avenue in Bethesda, Maryland 20817 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Provider (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.mont

KCI visited the site on 1/6/2020 and deployed sixty-two (62) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted sixty (60) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on 1/9/2020 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a National Radon Safety Board (NRSB) radon measurement provider and is a certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- · Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the upper-20s and high temperatures were in the mid-50s. Maximum sustained winds ranged from 10-23 miles per hour. Average humidity was around 64%. 0.32 inches of precipitation (rain) was recorded during the testing period.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples				
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.			
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.			

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Mr. Tyler P. McCleaf Radon Measurement Provider 111004 RT

KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test Locations

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Table 1- Radon Testing Results							
Bradley Hills Elementary School							
Test Period: 1/6/2020-1/9/2020							
Room / Area	Result						
113	< 0.3						
109	0.8						
109	0.7						
110	0.8						
107	< 0.3						
108	0.6						
105	0.6						
104	< 0.3						
103	< 0.3						
102	0.6						
116	0.7						
117	0.9						
117	0.7						
119	0.9						
118	0.9						
118	< 0.3						
121	< 0.3						
120	0.6						
122	0.6						
149	0.8						
148	1.1						
150	1.6						
150	1.3						
	Room / Area 113 109 109 110 107 108 105 104 103 102 116 117 117 119 118 118 121 120 122 149 148 150						

145A

1.2

0.6

< 0.3

< 0.3

< 0.3

0.5

0.6

< 0.3

< 0.3

< 0.3

< 0.3

< 0.3

0.5

0.7

1.2

< 0.3

< 0.3

9341281	156	< 0.3
9341282	157	< 0.3
9341283	158	< 0.3
9341284	160	< 0.3
9341285	159	< 0.3
9341286	01A	0.7
9341287	1	< 0.3
9341288	1	0.8
9341289	162	0.6
9341290	162	0.5
9341291	168	0.7
9341292	168	< 0.3
9341293	169	< 0.3
9341294	169	< 0.3
9341295	100E	0.5
9341296	100B	< 0.3
9341297	100A	< 0.3
9341298	100	< 0.3
9341299	101	0.7
9341300	101B	0.7
9348305	OFFICE BLANK	< 0.3
9341276	127	MISSING

Table 2- Radon Testing Results							
	Bradley Hills Elementary School						
	Test Period: 1/6	/2020-1/9/2020					
Kit Number	QC Type	Room / Area	Result				
9341240	D	109	0.7				
9341250	D	117	0.7				
9341253	FB	118	<0.3				
9341260	D	150	1.3				
9341270	D	131	<0.3				
9341272	FB	130	<0.3				
9341290	D	162	0.5				
9341292	FB	168	<0.3				
9348319	TRANSIT BLANK	NA	<0.3				
9348320	TRANSIT BLANK	NA	<0.3				
9348313	TRANSIT BLANK	NA	<0.3				

Summary of Missed Locations								
	Bradley Hills Elementary School							
Test Per	Test Period: 01/06/2020 - 01/09/2020							
Kit Number	Room/Area	Result						
-	N/A	-						
	_							

Summary of M	issing, Compromised and >/= 4 pi	C/L Tests
Br	adley Hills Elementary School	
	Period: 01/06/2020 - 01/09/2020	
Kit Number	Room/Area	Result
9341276	*127	MISSING

Table Note:

^{*} Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340067	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.4 \mathrm{D}$	2020-01-03
9340035	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$22.5 \pm 2.3 \mathrm{D}$	2020-01-03
9340003	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.2 \pm 2.4 \mathrm{D}$	2020-01-03
9340089	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$23.3 \pm 2.3 D$	2020-01-03
9340072	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$18.3 \pm 2.0 \mathrm{D}$	2020-01-03
9340040	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.3 \pm 2.6 \mathrm{D}$	2020-01-03
9340008	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.8 \pm 2.5 \mathrm{D}$	2020-01-03
9340094	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.7 \pm 2.5 \mathrm{D}$	2020-01-03
9340099	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$27.5 \pm 2.6 \mathrm{D}$	2020-01-03
9340077	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.2 \pm 2.5 \mathrm{D}$	2020-01-03
9340045	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.7 \pm 2.4 \mathrm{D}$	2020-01-03
9340013	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.9 \pm 2.6 \mathrm{D}$	2020-01-03
9340018	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$29.1 \pm 2.8 \mathrm{D}$	2020-01-03
9341704	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.4 D$	2020-01-03
9340050	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.2 \pm 2.6 \mathrm{D}$	2020-01-03
9340023	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.2 \pm 2.7 D$	2020-01-03
9341709	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.5 \pm 2.4 \mathrm{D}$	2020-01-03
9340055	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.8 \pm 2.6 \mathrm{D}$	2020-01-03
9340060	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.3 \pm 2.5 D$	2020-01-03
9340028	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.9 \pm 2.3 D$	2020-01-03
9341714	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$28.3 \pm 2.7 \mathrm{D}$	2020-01-03
9340082	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.4 \pm 2.6 \mathrm{D}$	2020-01-03
9340065	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.2 \pm 2.4 D$	2020-01-03
9340033	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.2 \pm 2.5 \mathrm{D}$	2020-01-03
9341719	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.7 \pm 2.5 \mathrm{D}$	2020-01-03
9340001	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.3 \pm 2.5 \mathrm{D}$	2020-01-03
9340087	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.8 \pm 2.4 \mathrm{D}$	2020-01-03
9340070	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$19.5 \pm 2.4 \mathrm{D}$	2020-01-03
9340038	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.7 \pm 2.3 \mathrm{D}$	2020-01-03
9340006	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.2 \pm 2.4 \mathrm{D}$	2020-01-03
9340092	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$31.4 \pm 2.8 D$	2020-01-03
9340097	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.7 \pm 2.5 \mathrm{D}$	2020-01-03
9340075	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$29.6 \pm 2.6 \mathrm{D}$	2020-01-03
9340043	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.1 \pm 2.6 \mathrm{D}$	2020-01-03
9340011	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.8 \pm 2.5 \mathrm{D}$	2020-01-03
9340016	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.2 \pm 2.4 \mathrm{D}$	2020-01-03
9341702	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.8 \pm 2.5 \mathrm{D}$	2020-01-03

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340048	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.5 \pm 2.4 \mathrm{D}$	2020-01-03
9340021	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.7 \pm 2.6 \mathrm{D}$	2020-01-03
9341707	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.8 \pm 2.4 \mathrm{D}$	2020-01-03
9340053	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.8 \pm 2.5 D$	2020-01-03
9340058	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.5 \pm 2.7 \mathrm{D}$	2020-01-03
9340026	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.9 \pm 2.4 D$	2020-01-03
9341712	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.3 \pm 2.4 D$	2020-01-03
9340080	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.4 D$	2020-01-03
9340063	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.8 \pm 2.5 D$	2020-01-03
9340031	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.9 \pm 2.4 D$	2020-01-03
9341717	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.7 \pm 2.4 \mathrm{D}$	2020-01-03
9340085	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.9 \pm 2.5 D$	2020-01-03
9340068	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.2 \pm 2.5 D$	2020-01-03
9340036	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.6 \pm 2.3 D$	2020-01-03
9340004	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.9 \pm 2.6 \mathrm{D}$	2020-01-03
9340090	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.3 \pm 2.5 D$	2020-01-03
9340073	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.8 \pm 2.5 D$	2020-01-03
9340041	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.6 \pm 2.4 D$	2020-01-03
9340009	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.1 \pm 2.4 D$	2020-01-03
9340095	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.2 \pm 2.5 D$	2020-01-03
9340100	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.5 \pm 2.4 \mathrm{D}$	2020-01-03
9340078	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.0 \pm 2.4 D$	2020-01-03
9340046	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.0 \pm 2.6 \mathrm{D}$	2020-01-03
9340014	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$21.8 \pm 2.8 D$	2020-01-03
9340019	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.0 \pm 2.5 D$	2020-01-03
9341705	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$27.8 \pm 2.6 \mathrm{D}$	2020-01-03
9340051	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.5 \pm 2.4 \mathrm{D}$	2020-01-03
9340056	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.7 \pm 2.6 \mathrm{D}$	2020-01-03
9340024	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.3 \pm 2.5 \mathrm{D}$	2020-01-03
9341710	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.2 \pm 2.3 D$	2020-01-03
9340061	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$28.9 \pm 2.6 \mathrm{D}$	2020-01-03
9340029	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.0 \pm 2.3 D$	2020-01-03
9341715	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$27.0 \pm 2.5 D$	2020-01-03
9340083	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.9 \pm 2.4 \mathrm{D}$	2020-01-03
9340066	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.4 \mathrm{D}$	2020-01-03
9340034	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.4 \pm 2.5 \mathrm{D}$	2020-01-03
9341720	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.3 \pm 2.5 D$	2020-01-03

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340002	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.7 ± 2.5 D	2020-01-03
9340088	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.4 \pm 2.5 \mathrm{D}$	2020-01-03
9340071	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.9 \pm 2.4 \mathrm{D}$	2020-01-03
9340039	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.9 \pm 2.5 \mathrm{D}$	2020-01-03
9340007	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.9 \pm 2.4 \mathrm{D}$	2020-01-03
9340093	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.5 D$	2020-01-03
9340098	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.8 \pm 2.5 \mathrm{D}$	2020-01-03
9340076	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.1 \pm 2.5 D$	2020-01-03
9340044	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.2 \pm 2.5 D$	2020-01-03
9340012	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$22.5 \pm 2.2 D$	2020-01-03
9340017	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.3 \pm 2.5 D$	2020-01-03
9341703	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.0 \pm 2.5 D$	2020-01-03
9340049	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.0 \pm 2.5 D$	2020-01-03
9340022	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.6 \pm 2.6 \mathrm{D}$	2020-01-03
9341708	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$28.8 \pm 2.8 D$	2020-01-03
9340054	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.8 \pm 2.5 \mathrm{D}$	2020-01-03
9340059	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.5 \pm 2.6 \mathrm{D}$	2020-01-03
9340027	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.6 \pm 2.5 \mathrm{D}$	2020-01-03
9341713	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.5 \pm 2.5 \mathrm{D}$	2020-01-03
9340081	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$18.4 \pm 2.1 D$	2020-01-03
9340064	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.5 \pm 2.5 \mathrm{D}$	2020-01-03
9340032	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.1 \pm 2.4 \mathrm{D}$	2020-01-03
9341718	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$23.7 \pm 2.4 \mathrm{D}$	2020-01-03
9340086	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.9 \pm 2.6 \mathrm{D}$	2020-01-03
9340069	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.6 \pm 2.5 D$	2020-01-03
9340037	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.4 \pm 2.6 \mathrm{D}$	2020-01-03
9340005	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	???? DIF1	2020-01-03
9340091	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.5 \pm 2.5 \mathrm{D}$	2020-01-03
9340096	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.2 \pm 2.5 D$	2020-01-03
9340074	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$27.7 \pm 2.5 D$	2020-01-03
9340042	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.6 \pm 2.5 \mathrm{D}$	2020-01-03
9340010	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.5 \pm 2.5 \mathrm{D}$	2020-01-03
9341701	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$22.9 \pm 2.3 D$	2020-01-03
9340047	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.7 \pm 2.5 \mathrm{D}$	2020-01-03
9340015	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.4 \pm 2.5 \mathrm{D}$	2020-01-03
9340020	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$24.1 \pm 2.4 \mathrm{D}$	2020-01-03
9341706	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$31.0 \pm 2.7 D$	2020-01-03

January 3, 2020

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within ± 25% of the chamber's reference value (25.7 pCi/L).

9340057 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 27.3 \pm 2.5 D 2020 9340025 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.1 \pm 2.4 D 2020 9341711 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 22.5 \pm 2.2 D 2020 9340079 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 26.9 \pm 2.5 D 2020 9340062 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25.6 \pm 2.5 D 2020 9340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 \pm 2.4 D 2020	Kit # R	Room Id	Started		Ended		pCi/L	Analyzed
9340025 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.1 \pm 2.4 D 2020 9341711 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 22.5 \pm 2.2 D 2020 9340079 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 26.9 \pm 2.5 D 2020 9340062 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25.6 \pm 2.5 D 2020 9340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 \pm 2.4 D 2020	9340052	N/A	2019-12-21 @	8:00 am	2019-12-23 @	8:00 am	$27.4 \pm 2.6 D$	2020-01-03
9341711 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 22.5 ± 2.2 D 2020 9340079 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 26.9 ± 2.5 D 2020 9340062 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25.6 ± 2.5 D 2020 9340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 ± 2.4 D 2020	9340057	N/A	2019-12-21 @	8:00 am	2019-12-23 @	8:00 am	$27.3 \pm 2.5 D$	2020-01-03
9340079 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 26.9 ± 2.5 D 2020 20340062 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25.6 ± 2.5 D 2020 20340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 ± 2.4 D 2020 2020 2020 2020 2020 2020 2020 2	9340025	N/A	2019-12-21 @	8:00 am	2019-12-23 @	8:00 am	$25.1 \pm 2.4 D$	2020-01-03
9340062 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25.6 ± 2.5 D 2020 20340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 ± 2.4 D 2020	9341711	N/A	2019-12-21 @	9:00 am	2019-12-23 @	9:00 am	$22.5 \pm 2.2 D$	2020-01-03
9340030 N/A 2019-12-21 @ 8:00 am 2019-12-23 @ 8:00 am 25.0 ± 2.4 D 2020	9340079	N/A	2019-12-21 @	9:00 am	2019-12-23 @	9:00 am	$26.9 \pm 2.5 D$	2020-01-03
	9340062	N/A	2019-12-21 @	9:00 am	2019-12-23 @	9:00 am	$25.6 \pm 2.5 D$	2020-01-03
9341716 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 25 1 + 2 4 D 2020	9340030	N/A	2019-12-21 @	8:00 am	2019-12-23 @	8:00 am	$25.0 \pm 2.4 D$	2020-01-03
2017 12 21 C 7.00 um 2017 12 23 C 7.00 um 2017 12 25 C 7.00 um	9341716	N/A	2019-12-21 @	9:00 am	2019-12-23 @	9:00 am	$25.1 \pm 2.4 D$	2020-01-03
9340084 N/A 2019-12-21 @ 9:00 am 2019-12-23 @ 9:00 am 24.5 ± 2.3 D 2020	9340084	N/A	2019-12-21 @	9:00 am	2019-12-23 @	9:00 am	$24.5 \pm 2.3 D$	2020-01-03

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT VCC		Technol	ggies	Ine Job	Number	1935	98			
NOMINAL Conditions:	Radon Conc		_pCi/L Re	el. Hum	%	Temp.		F	×	
			Date St	tart: 12/21/	19 Date	Stop: 12/2	23/19	Avg pCi/L	RH%_	Temp °F
			(Gan	tart: 0830						
			Device	No.'s: (20) Ch	an. Ba	195-	ري اي	50.	70
			9340	261 7	thno	93400	80	CI	-	0
				· · · · · · · · · · · · · · · · · · ·						
			52					i	1	!
			Date Sta	art: 12/2/1	9 Date S	Stop: 12/23	3/19	Avg	RU G	To B
			Time St	art: <u>0</u> 835	_ Time	Stop: 083	3	Avg pCi/L	ך ר,	o E
			CG roo Device	p 5) No.'s:(20)) Cha	r. Bag				
			;	081 4		V		25.5	50.1	70.0
			Q5					The state of the s		
			Date Sta	urt: 12/21/19	9 Date S	top: 12/2	3/19	Avg	ヱ :	Temp
			1	art: <u>0840</u>			2_	Avg pCi/L	, ,	o fi
			CG roop Device I	,6) No.'s:(20)	Char	Bougs	•		ļ	
			93417			93417	3 0	25.	50.	70
						, , , , , , , , , , , , , , , , , , ,	6	5		0
			R5					э: А	Æ	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

Radon test result report for: BRADLEY HILLS ES MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9341287	01	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341288	01	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.8 ± 0.4	2020-01-14
9341286	01A	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9341298	100	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341297	100A	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341296	100B	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341295	100E	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.5 ± 0.4	2020-01-14
9341299	101	2020-01-06 @ 3:00 pm	2020-01-09 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9341300	101B	2020-01-06 @ 3:00 pm	2020-01-09 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9341247	102	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	0.6 ± 0.4	2020-01-14
9341246	103	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341245	104	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341244	105	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.6 ± 0.4	2020-01-14
9341242	107	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14
9341243	108	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.6 ± 0.4	2020-01-14
9341239	109	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.8 ± 0.4	2020-01-14
9341240	109	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.7 ± 0.4	2020-01-14
9341241	110	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.8 ± 0.5	2020-01-14
9341238	113	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14
9341248	116	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.7 ± 0.4	2020-01-14
9341249	117	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.9 ± 0.4	2020-01-14
9341250	117	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.7 ± 0.4	2020-01-14
9341252	118	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	0.9 ± 0.5	2020-01-14
9341253	118	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341251	119	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	0.9 ± 0.4	2020-01-14
9341255	120	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	0.6 ± 0.4	2020-01-14
9341254	121	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14
9341256	122	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am	0.6 ± 0.4	2020-01-14
9341273	124	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341275	126	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	0.5 ± 0.4	2020-01-14
9341274	129	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	1.0 ± 0.5	2020-01-14
9341271	130	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14
9341272	130	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14
9341269	131	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341270	131	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341268	134	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	0.6 ± 0.5	2020-01-14
9341266	138	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	< 0.3	2020-01-14

Radon test result report for: BRADLEY HILLS ES MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9341267	142	2020-01-06 @ 2:00 pm	2020-01-09 @ 11:00 am	0.5 ± 0.4	2020-01-14
9341267	142	-	2020-01-09 @ 11:00 am	0.3 ± 0.4 < 0.3	2020-01-14
9341264	143 145	2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am 2020-01-09 @ 11:00 am	0.6 ± 0.4	2020-01-14
	143 145A	2020-01-06 @ 1:00 pm		0.6 ± 0.4 < 0.3	
9341265		2020-01-06 @ 1:00 pm	2020-01-09 @ 11:00 am		2020-01-14
9341261	146	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	1.2 ± 0.5	2020-01-14
9341258	148	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	1.1 ± 0.5	2020-01-14
9341257	149	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	0.8 ± 0.4	2020-01-14
9341259	150	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	1.6 ± 0.5	2020-01-14
9341260	150	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	1.3 ± 0.5	2020-01-14
9341262	151	2020-01-06 @ 1:00 pm	2020-01-09 @ 12:00 pm	1.0 ± 0.5	2020-01-14
9341279	153	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341280	153	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341281	156	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341282	157	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341283	158	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341285	159	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341284	160	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341289	162	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.6 ± 0.4	2020-01-14
9341290	162	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.5 ± 0.4	2020-01-14
9341292	168	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341291	168	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9341294	169	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341293	169	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	< 0.3	2020-01-14
9341277	205	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9341278	224	2020-01-06 @ 2:00 pm	2020-01-09 @ 12:00 pm	1.2 ± 0.4	2020-01-14
		·	1		

Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon 2019 Week 3

Name of Schools:

- 1. Bannockburn E.S.
- 2. Bethesda E.S.
- 3. Bethesda-Chevy Chase H.S.
- 4. Bradley Hill E.S.
- 5. Burning Tree E.S.
- 6. Burnt Mills E.S.
- 7. East Silver Springs E.S.
- 8. Einstein H.S.
- 9. Flora Singer E.S.
- 10. Key M.S.
- 11. Montgomery Blair H.S.

- 12. Montgomery Knolls E.S.
- 13. Newport Mills M.S.
- 14. Oak View E.S.
- 15. Rock View E.S.
- 16. Roscoe Nix E.S.
- 17. Sligo M.S.
- 18. Spring Mill Center
- 19. Springbrook H.S.
- 20. Westland M.S.
- 21. Woodlin M.S.

	Date	Initials
Radon Test Kits Deployed	1/6/20 to 1/7/20	M
Radon Test Kits Collected	1/9/20 to 1/10/20	M
Radon Test Kits Shipped to Lab*	1/10/20	M
Radon Test Kits Received by Lab*	1/13/202	M

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

RADON SCREENING SURVEY - FOLLOW-UP BRADELY HILLS ELEMENTARY SCHOOL

8701 Hartsdale Ave, Bethesda, Maryland 20817

EXECUTIVE SUMMARY

Date of Test Report:	3/10/16 (Follow-Up)
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested	3
# Rooms ≥ 4.0 pCi/L:	0
Low Value:	<0.3
High Value:	1.0
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0
Action Level	

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L)	Result (pCi/L)	Average Result
	3/10/16 (Rev. 2, Initial)	3/10/16 (Follow-Up)	(pCi/L)
126	0.8 (Open Window)	1.0	0.9
145A	(Missing)	<0.3	<0.3
Main Office	(Missing)	<0.3	<0.3



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Bradley Hills Elementary School

Date of Test Report:	3/10/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	3
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	1.0

Project Status:

Retesting completed; no further action at this time.

KCI Technologies, Inc. www.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 10, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.29

Location: Bradley Hills Elementary School

8701 Hartsdale Avenue Bethesda, MD 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Bradley Hills Elementary School, located at 8701 Hartsdale Avenue in Bethesda, Maryland 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 22, 2016 and deployed five (5) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 25, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

www.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. Note that strong storms and heavy rainfall were recorded during the test period. The unusual weather conditions may have resulted in atypical radon test results for this facility.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Mr. Richard Cox March 10, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makler

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank*

PM- Project Manager

QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 9 testing. Office blanks were not submitted under each school individually.

	Radon Testing Results				
	Bradley Hills Elementary School				
	Test Period: 02/22/16-02/25/16				
Kit Number	Kit Number Room / Area Result				
7732388	7732388 126 1.0				
7732392	145A	< 0.3			
7732399 MAIN OFFICE < 0.3					

	Radon Testing Results			
	Bradley Hills Elementary School			
	Test Period: 02/22/16-02/25/16			
Kit Number	Kit Number QC Type Result			
7732396	D (MAIN OFFICE)	< 0.3		
7732395	FB (MAIN OFFICE)	< 0.3		

ATTACHMENT C

Laboratory Analytical Results

March** LABORATORY ANALYSIS 8, 2016 REPORT **

Radon test result report for: BRADLEY HILLS ELEMENTARY SCHOOL MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7732388	126	2016-02-22 @ 9:00 am	2016-02-25 @ 7:00 am	1.0 ± 0.4	2016-02-29
7732392	145A	2016-02-22 @ 9:00 am	2016-02-25 @ 7:00 am	< 0.3	2016-02-29
7732395	MAIN OFFICE	2016-02-22 @ 9:00 am	2016-02-25 @ 7:00 am	< 0.3	2016-02-29
7732396	MAIN OFFICE	2016-02-22 @ 9:00 am	2016-02-25 @ 7:00 am	< 0.3	2016-02-29
7732399	MAIN OFFICE	2016-02-22 @ 9:00 am	2016-02-25 @ 7:00 am	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for: MCPS

Phase 9 Office Blanks

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7712568	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7712584	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719460	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719481	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719497	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719498	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for:

MCPS
Phase 9 Office Blanks

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7731626	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7731633	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7735204	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7733204		2010-02-23 @ 2.00 pm	2010-02-20 @ 3.00 pm	V 0.5	2010-03-0

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

Rit# Room Id Started Started PCi/L Analyzed						
7734946 10 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7734955 11 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 4 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 20	7734937	1	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 201	7734946	10	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734955	11	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734956	12	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734959	13	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734930	14	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734953	15	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734954	16	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734948 19 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734940	17	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734939 2 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734949	18	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734948	19	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734929 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734939	2	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734942	20	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734929	21	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734936 24 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734933	22	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734943 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734934	23	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734944 26 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734936	24	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734943	25	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734928 28 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734944	26	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734952 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734935	27	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734947 3 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734928	28	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734952	29	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734932 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734947	3	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718520 32 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734931	30	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718523 33 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734932	31	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718522 34 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718520	32	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718521 35 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718523	33	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734945 4 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7718522	34	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	
7734960 5 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718521	35	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734958 6 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734945	4	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23		5	1			2016-02-23
7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734958	6	•	2016-02-22 @ 11:00 am		2016-02-23
<u>.</u>	7734951	7	•			2016-02-23
7734938 9 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23			•			
	7734938	9	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologica	Inc. Job Number 173704
	pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: 1/30/16 Date Stop: 2/1/16	Date Start: Date Stop:
Time Start: 9986 Time Stop: 9986	Time Start: Time Stop:
Device No.'s: (6) Char. Bags-	Device No.'s:
7718281, 7718282, 7718291,	
7718288, 7718289, 7718273	
E3 Left	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	· · · · · · · · · · · · · · · · · · ·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

15. Briggs Chaney MS

Name of Schools:

1	Docking Horse Boad ES	16. Broad Acres ES	31. Rosa Parks MS
1.	Rocking Horse Road ES	10. Blodu Acres ES	31. ROSA PATKS IVIS
2.	Rockwell ES	17. Belmont ES	32. Rosemary Hills ES
3.	Oakland Terrace ES	18. Emory Grove Center	33. Sequoyah ES
4.	Rosemont ES	19. Forest Knolls ES	34. Damascus HS
5.	Beall ES	20. Baker MS	35. Einstein ES
6.	Cresthaven ES	21. MLK MS	36. Forest Oak MS
7.	Quince Orchard HS	22. Richard Montgomery HS	37. Hoover MS
8.	Smith Center	23. Sherwood HS	38. Julius West MS
9.	Ashburton ES	24. Walter Johnson HS	39. John F. Kennedy HS
10	. Bannockburn ES	25. Diamond ES	40. Travilah ES
11	. Bradley Hills ES	26. Newport Mill MS	41. Watkins Mill HS
12	. Cannon Road ES	27. Drew ES	42. Northwood HS
13	. Flora M. Singer ES	28. Monocacy ES	43. Lincoln Center
14	. Clarksburg HS	29. Potomac ES	

30. Rock Terrace School

	Date	Initials
Radon Test Kits Deployed	2/22/16	JM
Radon Test Kits Collected	2/25/16	JM
Radon Test Kits Shipped to Lab*	2/25/16	UM
Radon Test Kits Received by Lab*	2/29/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

Name of Schools:

- 1. Banneker MS
- 2. Bethesda-Chevy Chase HS
- 3. Burtonsville ES
- 4. Chevy Chase ES
- 5. Clopper Mill ES
- 6. Edison HS
- 7. Flower Hill ES
- 8. Flower Valley ES
- 9. Greencastle ES

- 10. Maryvale ES
- 11. Montgomery Blair HS
- 12. Poolesville HS
- 13. Rachel Carson ES
- 14. Stedwick ES
- 15. Watkins Mill ES
- 16. Laytonsville ES
- 17. Lincoln Center

	Date	Initials
Radon Test Kits Deployed	2/23/16	(/M
Radon Test Kits Collected	2/26/16	JM
Radon Test Kits Shipped to Lab*	2/26/16	JM
Radon Test Kits Received by Lab*	3/01/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Bradley Hills Elementary School

Date of Test Report:	3/10/2016 (Rev 2)
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	44
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	0.9

Project Status:

Initial testing completed; missing or compromised samples need re-test.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 10, 2016 (Rev 2)

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.20

Location: Bradley Hills Elementary School

8701 Hartsdale Avenue Bethesda, MD 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Bradley Hills Elementary School, located at 8701 Hartsdale Avenue in Bethesda, Maryland 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on December 21, 2015 and deployed fifty-eight (58) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 24, 2015 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

www.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
≥4.0 piC/L	none	n/a	
<4.0 piC/L	See Attachment B		

Notes:

D- Duplicate sample

The field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Mr. Richard Cox March 10, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makden

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

B- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Radon Testing Results									
Bradley Hills Es Test Period: 12/21/15-12/24/15									
100t 1 0110d. 12/2 1/10-12/24/10									
Kit Number	Kit Number Room / Area Resul								
7711846	101	< 0.3							
7711879	102	0.5							
7711823	103	< 0.3							
7711877	104	< 0.3							
7711826	105	0.5							
7711833	107	< 0.3							
7711900	108	< 0.3							
7711853	109	0.6							
7711816	110	< 0.3							
7711855	113	< 0.3							
7711851	116	< 0.3							
7711854	117	0.6							
7711849	118	< 0.3							
7711848	119	< 0.3							
7711845	120	< 0.3							
7711834	121	0.6							
7711844	122	< 0.3							
7711837	124	0.7							
7711843	127	0.5							
7711840	129	0.5							
7711882	130	0.6							
7711896	131	0.6							
7711878	134	0.6							
7711839	138	0.7							
7711870	142	0.7							
7711867	151	0.8							
7711883	156	< 0.3							
7711881	160	< 0.3							
7711861	162	< 0.3							
7711864	168	< 0.3							
7711817	215	< 0.3							
7711857	221	< 0.3							
7711822	100A	0.6							
7711819	100B	0.5							
7711825	100E	0.6							
7711821	100G	< 0.3							
7711842	101B	< 0.3							
7711841 *	126 (open windows)	0.8							
7711860 *	145A (missing)	-							
7711838	CAFE	< 0.3							
7711859	CAFE	< 0.3							
7711852	GYM	8.0							
7711884	GYM	0.8							
7711885	GYM	8.0							
7711863	LIBRARY	< 0.3							
7711871	LIBRARY	< 0.3							

Table Note:
* Missing or Compromised Sample

	Radon Testing Results						
	Bradley Hills Es						
	Test Period: 12/21/15-12/24/15						
Kit Number	Kit Number Room / Area Result						
7711818	* MAIN OFFICE (missing)	-					
7711856	7711856 STAFF LOUNGE						

Radon Testing Results Bradley Hills Es Test Period: 12/21/15-12/24/15							
Kit Number QC Type Result							
7711820	D (108)	0.7					
7711847	D (121)	< 0.3					
7711835	D (131)	< 0.3					
7711836	D (142)	0.6					
7711858	D (160)	0.9					
7711850	D (215)	< 0.3					
7711898	D (STAFF LOUNGE)	0.5					
7711893	FB (124)	< 0.3					
7711865	FB (151)	< 0.3					
7710416	OB (0)	< 0.3					

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: BRADLEY HILLS ES MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7710416	0	2015-12-21 @ 5:00 pm	2015-12-24 @ 1:00 pm	< 0.3	2015-12-28
7711822	100A	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.6 ± 0.3	2015-12-28
7711819	100B	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.5 ± 0.3	2015-12-28
7711825	100E	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.6 ± 0.3	2015-12-28
7711821	100G	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711846	101	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711842	101B	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711879	102	2015-12-21 @ 4:00 pm	2015-12-24 @ 11:00 am	0.5 ± 0.3	2015-12-28
7711823	103	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711877	104	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711826	105	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.5 ± 0.3	2015-12-28
7711833	107	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711820	108	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.7 ± 0.3	2015-12-28
7711900	108	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711853	109	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	0.6 ± 0.3	2015-12-28
7711816	110	2015-12-21 @ 4:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711855	113	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711851	116	2015-12-21 @ 4:00 pm	2015-12-24 @ 12:00 pm	< 0.3	2015-12-28
7711854	117	2015-12-21 @ 4:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28
7711849	118	2015-12-21 @ 4:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711848	119	2015-12-21 @ 4:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711845	120	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711834	121	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28
7711847	121	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711844	122	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711893	124	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711837	124	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.7 ± 0.3	2015-12-28
7711841	126	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.8 ± 0.3	2015-12-28
7711843	127	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.5 ± 0.3	2015-12-28
7711840	129	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.5 ± 0.3	2015-12-28
7711882	130	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28
7711896	131	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28
7711835	131	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	< 0.3	2015-12-28
7711878	134	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28
7711839	138	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.7 ± 0.3	2015-12-28
7711870	142	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.7 ± 0.3	2015-12-28
7711836	142	2015-12-21 @ 3:00 pm	2015-12-24 @ 11:00 am	0.6 ± 0.3	2015-12-28

Januar LABORATORY ANALYSIS 12, REPORT **

Radon test result report for: BRADLEY HILLS ES MAIN

Kit#	Room Id	Started		Ended		pCi/L	Analyzed
7711860	145A	@		@			
7711865	151	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am	< 0.3	2015-12-28
7711867	151	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.3	8 ± 0.3	2015-12-28
7711883	156	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am	< 0.3	2015-12-28
7711858	160	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.9	9 ± 0.3	2015-12-28
7711881	160	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am	< 0.3	2015-12-28
7711861	162	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711864	168	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711817	215	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711850	215	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711857	221	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711859	CAFE	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711838	CAFE	2015-12-21 @	4:00 pm	2015-12-24 @ 12	:00 pm	< 0.3	2015-12-28
7711884	GYM	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.3	8 ± 0.3	2015-12-28
7711885	GYM	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.3	8 ± 0.3	2015-12-28
7711852	GYM	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.3	8 ± 0.3	2015-12-28
7711863	LIBRARY	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am	< 0.3	2015-12-28
7711871	LIBRARY	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am	< 0.3	2015-12-28
7711818	MAIN OFFICE	@		@			
7711856	STAFF LOUNGE	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.0	6 ± 0.3	2015-12-28
7711898	STAFF LOUNGE	2015-12-21 @	3:00 pm	2015-12-24 @ 11	:00 am 0.:	5 ± 0.3	2015-12-28

December LABORATORY ANALYSIS 29, REPORT **

Radon test result report for:
TRANSIT DEC 14 2015
NONE

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
		2002000		-	•
7704395	TRANSIT 1	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706508	TRANSIT 10	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706510	TRANSIT 11	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706511	TRANSIT 12	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706505	TRANSIT 13	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704371	TRANSIT 14	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706506	TRANSIT 15	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704381	TRANSIT 16	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704399	TRANSIT 17	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704390	TRANSIT 18	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704396	TRANSIT 2	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704364	TRANSIT 3	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704370	TRANSIT 4	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704368	TRANSIT 5	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706524	TRANSIT 6	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706526	TRANSIT 7	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706518	TRANSIT 8	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706516	TRANSIT 9	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16

December LABORATORY ANALYSIS 23, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7706380	101	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	25.2	2015-12-23
7706381	102	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706208	103	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	27.7	2015-12-23
7705132	104	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	28.6	2015-12-23
7706366	105	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706211	106	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.1	2015-12-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies.	Inc. Job Number 173224
	pCi/L Rel. Hum <u>49.6</u> % Temp. <u>69.9</u>
Date Start: 12/18/15 Date Stop: 12/21/5	Date Start: Date Stop:
Time Start: <u>0929</u> Time Stop: <u>0929</u>	Time Start: Time Stop:
Device No.'s: 7705132,7766208	Device No.'s:
7706211,7706366,	
7706380, 7706381	
F3 Loft	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	-
1	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Chain of Custody

Project Name: MCPS Radon Phase II

School Names:

1.	Bannonckburn ES	11. Sherwood HS	21.	Fairland ES
2.	Walt Whitman HS	12. Hadley Farms	22.	Cannon Road ES
3.	Walter Johnson HS	13. S. Christa McAuliffe ES	23.	Richard Montgomery HS
4.	North Chevy Chase ES	14. Ronald A. McNair ES	24.	Brooke Grove ES
5.	Piney Branch ES	15. MLK MS	25.	Belmont ES
6.	Forest Knolls ES	16. Ashburton ES	26.	Emory Grove
7.	Newport Mill MS	17. Bradley Hills ES	27.	Clarksburg HS
8.	Broad Acres ES	18. Flora M. Singer ES	28.	Clarksburg ES
9.	Briggs Chaney MS	19. Woodlin ES	29.	John T. Baker MS
10.	Blair G. Ewing Center	20. Montgomery Knolls ES		

	Date	Initials
Radon Test Kits Deployed	12/21/2015	JM
Radon Test Kits Collected	12/24/2015	IM
Radon Test Kits Shipped to Lab*	12/24/2015	IM
Radon Test Kits Received by Lab*	12/28/2015	UM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Road, Mills River, NC 28758