



MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Weller Road Elementary School
Date of Test Report	4/29/2022
Round of Testing	Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility
# Rooms Tested	83
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.9 pCi/L

Project Status:
Initial testing completed; no further action needed



April 29, 2022

Brian T. Croyle, PG, CHMM
Environmental Specialist
Montgomery County Public Schools
Gaithersburg, MD 20879

Re: **Radon Testing Services**
KCI Job # 122108316

Location: Weller Road Elementary School
3301 Weller Rd.
Silver Spring, MD 20906

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Weller Road Elementary School Weller Road Elementary School, located at 3301 Weller Rd. Silver Spring, MD 20906 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <https://www.montgomeryschoolsmd.org> or www.epa.gov/radon.

KCI visited the site on March 8, 2022 and deployed ninety-five (95) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 11, 2022 to retrieve the radon sampling test kits. KCI shipped all radon

tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

- Follow-up to initial testing.

These tests were conducted to:

- Evaluate radon concentration levels at the facility

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility’s HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the mid 20s and high temperatures ranged from the high 70s to the low 50s Fahrenheit. Maximum sustained winds ranged from 0-32 miles per hour. Average humidity was around 65% with 1.09 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 pCi/L	None	N/A
<4.0 pCi/L	See Attachment B	

Quality Control Samples	
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is operating within statistical control limits.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,



Tyler P. McCleaf
Radon Measurement Provider
#111004 RT
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-3, Radon Test Summary Spreadsheets
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results		
Weller Road ES		
Test Period: 03/08/2022 - 03/11/2022		
Kit Number	Room / Area	Result
11132263	102	0.6
11132023	103	0.6
11132027	103	0.7
11132300	104	1.2
11132277	108	< 0.3
11132284	108	1.0
11132269	112	< 0.3
11132270	112	< 0.3
11132272	113	1.0
11132271	114	< 0.3
11132285	115	1.0
11132279	116	0.8
11132287	117	0.9
11132286	118	< 0.3
11132264	122	< 0.3
11132280	122	< 0.3
11133979	123	< 0.3
11133981	124	< 0.3
11133980	125	< 0.3
11133978	126	< 0.3
11133968	127	< 0.3
11133977	128	< 0.3
11133975	129	< 0.3
11133976	130	< 0.3
11133983	131	0.6
11132001	133	< 0.3
11132020	135	0.9
11132024	137	0.7
11132004	140	< 0.3
11132019	142	< 0.3
11132022	144	1.0
11132010	146	< 0.3
11132028	146	0.9
11133939	149	< 0.3
11133998	151	< 0.3
11133982	152	< 0.3
11133985	152	< 0.3
11133999	153	0.7
11133984	154	< 0.3
11133986	154	< 0.3
11134000	155	< 0.3
11133987	156	< 0.3

Table 1- Radon Testing Results		
Weller Road ES		
Test Period: 03/08/2022 - 03/11/2022		
Kit Number	Room / Area	Result
11133989	157	< 0.3
11133990	157	0.5
11133988	158	< 0.3
11133945	159	< 0.3
11133991	160	1.1
11133966	162	0.6
11133946	164	0.8
11132007	166	0.6
11133967	167	0.9
11132008	168	0.8
11133973	169	0.9
11133992	169	0.7
11132015	170	0.9
11133995	171	0.6
11132016	172	1.0
11133996	175	0.8
11133974	177	< 0.3
11133993	177	< 0.3
11133971	183	< 0.3
11132017	206	< 0.3
11132029	212	< 0.3
11132025	220	< 0.3
11132298	100 MAIN	1.2
11132295	100A	0.9
11132293	100B	1.3
11132294	100C	0.9
11132299	100D	0.9
11132292	100E	0.7
11132005	101 MEDIA	0.8
11132006	101 MEDIA	1.0
11132003	101C	0.9
11132297	104 WAITING	0.6
11132291	104E	0.6
11132281	104F	0.9
11132288	104G	1.9
11132289	104G	1.8
11132030	104H	1.1
11132276	104I	1.0
11132278	106F	1.0
11132275	106G	0.8
11132290	106H	0.7
11132296	106I	0.8

Table 1- Radon Testing Results		
Weller Road ES		
Test Period: 03/08/2022 - 03/11/2022		
Kit Number	Room / Area	Result
11132013	140D	0.7
11132021	140D	0.9
11133972	164 OFFICE	0.6
11133994	APR	< 0.3
11133997	APR	0.6
11132009	GYM	< 0.3
11132011	GYM	< 0.3
11132002	GYM OFFICE	1.3
11132014	GYM OFFICE	1.4
11133969	KITCHEN OFFICE	< 0.3
11132012	STAGE	0.7

Table 2- Radon Testing Results			
Weller Road ES			
Test Period: 03/08/2022 - 03/11/2022			
Kit Number	QC Type	Room / Area	Result
11132289	D	104G	1.8
11132277	D	108	< 0.3
11132270	FB	112	< 0.3
11132264	D	122	< 0.3
11133985	D	152	< 0.3
11133984	FB	154	< 0.3
11133973	D	169	0.9
11133993	FB	177	< 0.3
11132002	D	Gym Office	1.3
11132027	D	103	0.7
11132010	FB	146	< 0.3
11132021	D	140D	0.9
11131663	OB	OFFICE BLANK	< 0.3
11131669	TB	TRAVEL BLANK	< 0.3

Summary of Missed Locations		
Weller Road ES		
Test Period: 03/08/22 - 03/11/22		
Kit Number	Room/Area	Result
	NA	

Summary of Missing, Compromised and >= 4 piC/L Tests		
Weller Road ES		
Test Period: 03/08/22 - 03/11/22		
Kit Number	Room/Area	Result
	NA	

Table Note:
 * Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:**WELLER ROAD ES**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11132298	100 MAIN	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.2 ± 0.3	2022-03-14
11132295	100A	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.9 ± 0.3	2022-03-14
11132293	100B	2022-03-08 @ 10:00 am	2022-03-11 @ 11:00 am	1.3 ± 0.3	2022-03-14
11132294	100C	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.9 ± 0.3	2022-03-14
11132299	100D	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.9 ± 0.3	2022-03-14
11132292	100E	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.7 ± 0.3	2022-03-14
11132006	101 MEDIA	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	1.0 ± 0.3	2022-03-14
11132005	101 MEDIA	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.8 ± 0.3	2022-03-14
11132003	101C	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.9 ± 0.3	2022-03-14
11132263	102	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.6 ± 0.3	2022-03-14
11132023	103	2022-03-08 @ 12:00 pm	2022-03-11 @ 9:00 am	0.6 ± 0.3	2022-03-14
11132027	103	2022-03-08 @ 12:00 pm	2022-03-11 @ 9:00 am	0.7 ± 0.3	2022-03-14
11132300	104	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.2 ± 0.3	2022-03-14
11132297	104 WAITING	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.6 ± 0.3	2022-03-14
11132291	104E	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.6 ± 0.3	2022-03-14
11132281	104F	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.9 ± 0.3	2022-03-14
11132289	104G	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.8 ± 0.3	2022-03-14
11132288	104G	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.9 ± 0.3	2022-03-14
11132030	104H	2022-03-08 @ 12:00 pm	2022-03-11 @ 9:00 am	1.1 ± 0.3	2022-03-14
11132276	104I	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.0 ± 0.3	2022-03-14
11132278	106F	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.0 ± 0.3	2022-03-14
11132275	106G	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.8 ± 0.3	2022-03-14
11132290	106H	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.7 ± 0.3	2022-03-14
11132296	106I	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	0.8 ± 0.3	2022-03-14
11132284	108	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	1.0 ± 0.3	2022-03-14
11132277	108	2022-03-08 @ 10:00 am	2022-03-11 @ 9:00 am	< 0.3	2022-03-14
11132269	112	2022-03-08 @ 10:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132270	112	2022-03-08 @ 10:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132272	113	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	1.0 ± 0.3	2022-03-14
11132271	114	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132285	115	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	1.0 ± 0.3	2022-03-14
11132279	116	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.8 ± 0.3	2022-03-14
11132287	117	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.9 ± 0.3	2022-03-14
11132286	118	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132280	122	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132264	122	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132001	133	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	< 0.3	2022-03-14

March 15, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

WELLER ROAD ES

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11132020	135	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	0.9 ± 0.3	2022-03-14
11132024	137	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	0.7 ± 0.3	2022-03-14
11132004	140	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	< 0.3	2022-03-14
11132021	140D	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	0.9 ± 0.3	2022-03-14
11132013	140D	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	0.7 ± 0.3	2022-03-14
11132019	142	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	< 0.3	2022-03-14
11132022	144	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	1.0 ± 0.3	2022-03-14
11132010	146	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	< 0.3	2022-03-14
11132028	146	2022-03-08 @ 12:00 pm	2022-03-11 @ 11:00 am	0.9 ± 0.3	2022-03-14
11132007	166	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.6 ± 0.3	2022-03-14
11132008	168	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.8 ± 0.3	2022-03-14
11132015	170	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.9 ± 0.3	2022-03-14
11132016	172	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	1.0 ± 0.3	2022-03-14
11132017	206	2022-03-08 @ 1:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132029	212	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132025	220	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132011	GYM	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132009	GYM	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11132014	GYM OFFICE	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	1.4 ± 0.3	2022-03-14
11132002	GYM OFFICE	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	1.3 ± 0.3	2022-03-14
11132012	STAGE	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	0.7 ± 0.3	2022-03-14

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11133979	123	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133981	124	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133980	125	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133978	126	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133968	127	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133977	128	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133975	129	2022-03-08 @ 11:00 am	2022-03-11 @ 11:00 am	< 0.3	2022-03-14
11133976	130	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133983	131	2022-03-08 @ 11:00 am	2022-03-11 @ 11:00 am	0.6 ± 0.3	2022-03-14
11133939	149	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133998	151	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133982	152	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133985	152	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133999	153	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.7 ± 0.3	2022-03-14
11133984	154	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133986	154	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11134000	155	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133987	156	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133990	157	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.5 ± 0.3	2022-03-14
11133989	157	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133988	158	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133945	159	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133991	160	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	1.1 ± 0.3	2022-03-14
11133966	162	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.6 ± 0.3	2022-03-14
11133946	164	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.8 ± 0.3	2022-03-14
11133972	164 OFFICE	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.6 ± 0.3	2022-03-14
11133967	167	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.9 ± 0.3	2022-03-14
11133992	169	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.7 ± 0.3	2022-03-14
11133973	169	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.9 ± 0.3	2022-03-14
11133995	171	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.6 ± 0.3	2022-03-14
11133996	175	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.8 ± 0.3	2022-03-14
11133974	177	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133993	177	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133971	183	2022-03-08 @ 11:00 am	2022-03-11 @ 11:00 am	< 0.3	2022-03-14
11133994	APR	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	< 0.3	2022-03-14
11133997	APR	2022-03-08 @ 11:00 am	2022-03-11 @ 10:00 am	0.6 ± 0.3	2022-03-14
11133969	KITCHEN OFFICE	2022-03-08 @ 12:00 pm	2022-03-11 @ 10:00 am	< 0.3	2022-03-14

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, Inc. Job Number 204620

NOMINAL Conditions: Radon Conc 27.0 pCi/L Rel. Hum 50.1 % Temp. 70.0 F

Date Start: 3/18/22 Date Stop: 3/21/22 Date Start: _____ Date Stop: _____

Time Start: 0705 Time Stop: 0705 Time Start: _____ Time Stop: _____

Device No.'s: (5) Char Bags - Device No.'s: _____

11139367, 11139368, 11139371, _____

11139710, 11139717 _____

E3 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139367	SK1	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.9 \pm 2.1	2022-03-30
11139368	SK2	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	23.9 \pm 2.0	2022-03-30
11139371	SK3	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.7 \pm 2.1	2022-03-30
11139710	SK4	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	26.4 \pm 2.1	2022-03-30
11139717	SK5	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	24.6 \pm 2.0	2022-03-30

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



Radon Test Kit Chain of Custody

Project Name: MCPS Radon – March 2022 Schools

Name of Schools:

1. Fairland Center
2. Cloverly ES
3. Drew, Dr. Charles ES
4. Weller Road ES
5. Wheaton HS
6. East Silver Spring ES
7. Rosemary Hills ES

	Date	Initials
Radon Test Kits Deployed	03/08/2022	BMM
Radon Test Kits Collected	03/11/2022	BMM
Radon Test Kits Shipped to Lab*	03/11/2022	BMM
Radon Test Kits Received by Lab*	03/13/2022	BMM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759