

School / Facility Radon Testing Report Form

School Year: **24-25**

| | | | |
|-----------------------|---|--|--|
| Facility: | Wyngate Elementary School | | |
| Address: | 9300 Wadsworth Dr. | | |
| | Bethesda, MD 20817 | | |
| Reason for Testing: | Scheduled Re-Testing - <input type="checkbox"/> 2-year or <input checked="" type="checkbox"/> 5-year schedule <input type="checkbox"/> Clearance Testing (Post-Mitigation) <input checked="" type="checkbox"/> Building Envelope or HVAC Upgrades <input type="checkbox"/> New Construction – Addition or Facility | | |
| Current Radon Status: | <input type="checkbox"/> Active Mitigation (2-year regular schedule) <input checked="" type="checkbox"/> No Active Mitigation (5-year regular schedule) <input type="checkbox"/> Not Previously Tested (New Facility) | | |
| Round of Testing: | <input checked="" type="checkbox"/> Initial Testing -or- <input type="checkbox"/> Follow-up Testing | | |
| Testing Status: | <input checked="" type="checkbox"/> No Further Testing Needed -or- <input type="checkbox"/> Follow-Up Testing Required | | |

Conclusion (When Testing Status is - No Further Testing Needed)

| Mitigation - | Facility Radon Status: | | |
|--|--|-----------------------|------|
| <input checked="" type="checkbox"/> Not Required <input type="checkbox"/> Required (≥ 4.0 -pCi/L) Rooms: | <input checked="" type="checkbox"/> No Change in Status <input type="checkbox"/> Active Mitigation (2-year regular schedule) <input type="checkbox"/> No Active Mitigation (5-year regular schedule) | | |
| Number of Rooms Tested | 44 | Lowest Value (pCi/L) | <0.3 |
| Number of Rooms (≥ 4.0 -pCi/L) | 0 | Highest Value (pCi/L) | <0.3 |

Instructions: Submit one testing report form per-facility. Include the following as attachments:

Attachment 1- Summary Data Tables – containing the following: (see attached samples tables)

- Testing Results – lab/detector Identification, by room number/name (alpha-numeric order) as depicted on facility map/floor plan provided by the facility/school at the time of test device deployment;
- Summary Results – list of rooms by test result ≥ 2.0 -pCi/L; ≥ 2.7 -pCi/L; ≥ 4.0 -pCi/L; and ≥ 8.0 -pCi/L;
- QA/QC Results - (field blanks and duplicates) indicating location collected; trip and office blanks; and spike sample results;
- Invalid Measurement Locations – missed locations, missing and or damaged/compromised testing devices.

Attachment 2 – Laboratory Report(s)

Attachment 3 – Sampling Location Map(s) – indicating approximate location of samples, duplicates and blanks.

Detector and Deployment

| | | |
|---|---|---|
| Detector/Device Type: | <input checked="" type="checkbox"/> Passive | <input checked="" type="checkbox"/> Charcoal Absorption (CAD) <input type="checkbox"/> Alpha Track (ATD) <input type="checkbox"/> Other |
| | <input type="checkbox"/> Continuous | <input type="checkbox"/> Electret ion Chamber (EIC) <input type="checkbox"/> Electronic Integration (EID) |
| Other—Specify here: | | |
| Detector/Device Name: | Air Chek – Radon Test Kits | |
| Manufacturer: | Radon Labs | |
| Person(s) Deploying or Retrieving Test Devices and certification number | | Organization/Company |
| Brittany Maas | | KCI Technologies, Inc. |
| | | |
| | | |
| If noncertified individuals, the qualified measurement professional providing oversight - | | |
| Tyler McCleaf, CSP Cert. # 111004-RMP | | KCI Technologies, Inc. |

Testing

| | | | | |
|---|------------------------|---|--|---|
| <input checked="" type="checkbox"/> Short-Term | Length of Test (days): | 3 | Date of Deployment and Retrieval (mm/dd/yy): | 2/3/2025 |
| <input type="checkbox"/> Long-Term | | | | 2/6/2025 |
| Does the test period include weekends, school breaks or holidays? | | | | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| If “Yes” please explain/detail in the space below: | | | | |
| Was HVAC operating under occupied conditions? | | | | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| If “No” please explain/detail in the space below: | | | | |

Testing (continued)

| Round of Testing | Detectors Deployed | | | | |
|-----------------------------|--------------------|-----------|----------------|-----------|-------|
| | Ground-Contact | | Upper-Level(s) | | Total |
| | Initial | Follow-Up | Initial | Follow-Up | |
| Test Locations ¹ | 43 | 0 | 1 | 0 | 44 |
| Duplicates ² | 5 | 0 | 0 | 0 | 5 |
| Field Blanks ³ | 2 | 0 | 0 | 0 | 2 |
| Grand Total | | | | | 51 |

1 – include all detectors deployed (duplicates, field blanks); 1 detector per occupied (or intended to be occupied) ground-contact space ≤ 2,000-square feet; large spaces ≥ 2,000-square feet - 1 detector per 2,000-square feet or part thereof; and upper floors - 10% of all occupied or intended to be occupied rooms per floor (these are in addition to ground contact locations)

2 - 10% of all locations tested, per floor

3 – 5% of all locations tested, per floor

Quality Assurance / Quality Control (QA/QC)

A Quality Assurance plan that is consistent with ANSI/AARST MS-QA (Radon Measurement Systems Quality Assurance) was submitted under separate cover, and is available to review at the MCPS Radon Testing and Mitigation Program website. The following number of QA/QC samples are associated this facility.

| Round of Testing | QA/QC Samples | | Total |
|-------------------------------|----------------|-----------|-------|
| | Initial | Follow-Up | |
| Spikes ¹ | Not applicable | | 10 |
| Trip Blanks ² | 1 | 0 | 1 |
| Office Blanks ^{3, 4} | 1 | 0 | 1 |
| | | | 12 |

1 - 3% of EIC detectors; and 3% from each LOT of CAD and ATD detectors; a maximum of 6-spiked measurements per month for both EIC detectors and each LOT of CAD and ATD detectors.

2 – One per shipping container from start of detector deployment

3 – One per facility tested as devices are removed/allocated from the storage location for deployment;

4 - One additional blank, analyzed prior to deployment, for storage locations that have not been evaluated or monitored, for detectors that have been stored for more than 30-day durations.

Quality Assurance / Quality Control (continued)

| | |
|---|---|
| Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Quality Control measurements comply with QA/QC requirements in the submitted testing organization's/company's QA plan? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Round of Testing | Initial Follow-Up |
| All Field, Trip and Office Blanks are \leq (less than or equal to) to the Method Detection Limit? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No |
| For all Duplicate Samples ¹ , the higher value is $\leq 2x$ the lower value? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No |
| For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are less than the Warning Level ³ ? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No |
| For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are less than the Control Level ³ ? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No |

1 – Duplicate Control – a “NO” response constitute a control failure and the space/location represented by the duplicate sample becomes an invalid measurement location and should be listed in the “Invalid Measurement Locations” Table attached to this report.

2 - The objective of duplicate tests is to assess the precision error of the measurement method or, how well two side-by-side measurements agree or disagree. Precision involving duplicates is calculated by using Relative Percent Difference (RPD). RPD is equal to the difference between the higher test result minus the lower value test result divided by the average of the two duplicate test results, multiplied by 100. The RPD result is then compared to the warning and control limits.

3 - The Warning Level is set at the deviation from ideal performance that would be expected to occur by chance only 5% of the time, and Control Limits are set at that deviation from ideal performance that would be expected to occur by chance only 1% of the time. The Warning Level indicates a potential problem, which should be investigated. The Control Level indicates that the measurement system should be subject to corrective action.

The control and warning levels for duplicates, based on the averaged duplicate test result, are -

| Average concentration of the two duplicate test results | Warning Level | Control Level |
|---|---------------|----------------|
| < 2.0-pCi/L | 1-pCi/L | Not applicable |
| Between 2.0 and 3.9-pCi/L | 50% RPD | 67% RPD |
| ≥ 4.0 -pCi/L | 28% RPD | 36% RPD |

Summary of Test Results¹ and Determination of Valid Measurements²

| Round of Testing | Ground-Contact | | Upper-Level(s) | | Total |
|--|----------------|-----------|----------------|-----------|-------|
| | Initial | Follow-Up | Initial | Follow-Up | |
| Number of test locations: | 43 | 0 | 1 | 0 | 44 |
| Number of locations ≥ 8.0 -pCi/L: | 0 | 0 | 0 | 0 | 0 |
| Number of locations ≥ 4.0 and ≤ 8 -pCi/L: | 0 | 0 | 0 | 0 | 0 |
| Number of locations ≥ 2.7 and < 4 -pCi/L: | 0 | 0 | 0 | 0 | 0 |
| Number of locations ≥ 2.0 and < 2.7 -pCi/L: | 0 | 0 | 0 | 0 | 0 |
| Number of missing required test locations ³ : | 0 | 0 | 0 | 0 | 0 |
| Number of failed duplicate control locations: | 0 | 0 | 0 | 0 | 0 |
| Percentage of missing test locations for the facility ^{4,5} : | 0 | 0 | 0 | 0 | 0 |

1 – for locations with multiple test results, report consistent with Section 7.2(When Two Test Results Disagree) and 8.1.2 (Averaging) of ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings;

2 - the allowance is to be calculated individually for Ground-Contact and Upper-Level(s) Test Locations;

3 – includes missed or inaccessible locations upon deployment or retrieval, damaged (not able to analyze) and missing detectors upon retrieval;

4 – if all valid measurements are < 4.0 -pCi/L and the total number of test locations are ≥ 18 , there is an allowance of $\leq 33\%$. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023;

5 – if any valid measurements are ≥ 4.0 -pCi/L and the total number of test locations are ≥ 20 , there is an allowance of $\leq 25\%$ of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023.

Summary of Test Results¹ and Determination of Valid Measurements² (continued)

| Round of Testing | Initial | Follow-Up |
|---|---|---|
| Were test devices deployed in all occupied and intended to be occupied rooms in contact with the ground, and, if applicable, 10% of upper floor rooms? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| Were valid measurements obtained in all occupied and intended to be occupied rooms in contact with the ground, and, if applicable, 10% of upper floor rooms? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| <i>If Yes to both above – then Testing Status – ‘No Further Testing Needed’ mark ‘NA’ below and complete Conclusions section</i> | | |
| If No to either above, were all results obtained under 4.0-pCi/L and were sufficient valid measurements obtained?^{1,2} <i>If Yes, then - ‘No Further Testing Needed’ complete Conclusion section on first page.</i> <i>If No, then - ‘Follow-up Testing Required’ continue below.</i> | <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> NA | <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> NA |

1 – if all valid measurements are <4.0-pCi/L and the total number of test locations are ≥18, there is an allowance of ≤33%. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the allowance;
 2 – if any valid measurements are ≥4.0-pCi/L and the total number of test locations are ≥20, there is an allowance of ≤25% of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the number the allowance.

Follow-Up Testing

Required –

- If an insufficient number (greater than the allowance provided above) of valid measurements were obtained during the initial round of testing (the “missing required test locations” in the table above);
- Any location test results ≥ 4.0-pCi/L;
- Any location where duplicates fail QC checks; and or
- At the discretion of MCPS IAQ Staff

| Reason for Follow-Up Testing | Testing Procedure | Follow-up Result | Conclusion |
|-------------------------------------|--|------------------|-----------------------------------|
| Insufficient Number of Measurements | Follow same procedures as Initial Testing | Not Applicable | Follow Initial Testing procedures |
| Results ≥ 4.0-pCi/L | Deploy two Short-term follow-up tests and required blanks and duplicates; Average the results of the two tests | ≥4.0 | Mitigation Required |
| Failed QC checks | | ≥2.0 and <4.0 | Consider Mitigation |
| | | <2.0 | Mitigation Not Required |

- ***If follow-up testing identifies additional spaces requiring additional testing it will be performed as part of the ongoing follow-testing round.***

Attachment 1:

Summary Data Tables

| Table 1- Radon Testing Results | | |
|----------------------------------|--------------------------|--------|
| Wyngate Elementary School | | |
| Test Period: 2/3/2025 - 2/6/2025 | | |
| | | |
| Kit Number | Room / Area | Result |
| 11919950 | 1 | < 0.3 |
| 11919906 | 2 | < 0.3 |
| 11919938 | 2 | < 0.3 |
| 11919940 | 2 | < 0.3 |
| 11919945 | 3 | < 0.3 |
| 11919946 | 4 | < 0.3 |
| 11919953 | 5 | < 0.3 |
| 11919939 | 6 | < 0.3 |
| 11919903 | 9 | < 0.3 |
| 11919960 | 15 | < 0.3 |
| 11919959 | 18 | < 0.3 |
| 11919909 | 34 | < 0.3 |
| 11919919 | 35 | < 0.3 |
| 11919917 | 38 | < 0.3 |
| 11919918 | 38 | < 0.3 |
| 11919928 | 105 | < 0.3 |
| 11919927 | 108 | < 0.3 |
| 11919907 | 109 | < 0.3 |
| 11919932 | 115 | < 0.3 |
| 11919925 | 118 | < 0.3 |
| 11919933 | 119 | < 0.3 |
| 11919926 | 120 | < 0.3 |
| 11919934 | 120 | < 0.3 |
| 11919936 | 120 | < 0.3 |
| 11919941 | 121 | < 0.3 |
| 11919921 | 124 | < 0.3 |
| 11919942 | 126 | < 0.3 |
| 11919922 | 130 | < 0.3 |
| 11919935 | 209 | < 0.3 |
| 11919923 | APR | < 0.3 |
| 11919929 | APR | < 0.3 |
| 11919915 | ASSISTANT PRINCIPAL | < 0.3 |
| 11919910 | BUILDING SERVICES OFFICE | < 0.3 |
| 11919904 | CONFERENCE | < 0.3 |
| 11919905 | CONFERENCE | < 0.3 |
| 11919908 | ESOL | < 0.3 |
| 11919920 | ESOL 2 | < 0.3 |

| Table 1- Radon Testing Results | | |
|----------------------------------|--------------------|--------|
| Wyngate Elementary School | | |
| Test Period: 2/3/2025 - 2/6/2025 | | |
| | | |
| Kit Number | Room / Area | Result |
| 11919931 | GYM | < 0.3 |
| 11919937 | GYM | < 0.3 |
| 11919930 | GYM OFFICE | < 0.3 |
| 11919913 | HEALTH ROOM | < 0.3 |
| 11919914 | HEALTH ROOM OFFICE | < 0.3 |
| 11919911 | MAIN OFFICE | < 0.3 |
| 11919944 | MEDIA CENTER | < 0.3 |
| 11919949 | MEDIA CENTER | < 0.3 |
| 11919951 | MEDIA OFFICE | < 0.3 |
| 11919952 | MEDIA WORK ROOM | < 0.3 |
| 11919912 | PRINCIPAL | < 0.3 |
| 11919924 | STAGE | < 0.3 |
| 11919943 | STAGE | < 0.3 |
| 11919916 | WORK ROOM | < 0.3 |

[illegible]

| Table 3 - QC Radon Testing Results | | | |
|------------------------------------|---------|--------------|--------|
| Wyngate Elementary School | | | |
| Test Period: 2/3/2025 - 2/6/2025 | | | |
| | | | |
| Kit Number | QC Type | Room / Area | Result |
| 11919906 | D | 2 | < 0.3 |
| 11919938 | FB | 2 | < 0.3 |
| 11919918 | D | 38 | < 0.3 |
| 11919934 | FB | 120 | < 0.3 |
| 11919936 | D | 120 | < 0.3 |
| 11919905 | D | Conference | < 0.3 |
| 11919943 | D | Stage | < 0.3 |
| 11931691 | OB | OFFICE BLANK | < 0.3 |
| 11931692 | TB | TRAVEL BLANK | < 0.3 |

| Table 3a - Duplicate Worksheet / Data Validation | | | | | | | | | | | |
|--|----------|-------------|--|-------|-------------------------|-----------------|-------------------------|---------|--------------------------------------|---------------|--|
| Wyngate Elementary School | | | | | | | | | | | |
| Test Period: 2/3/2025 - 2/6/2025 | | | | | | | | | | | |
| Sample ID | | | Duplicate Concentrations (pCi/L) and OC Checks | | | | | | | | |
| Kit Numbers | | Room / Area | Higher | Lower | Check #1 (Pass/Fail) | 2x the Lower | Check #2 (Pass/Fail) | Average | Relative Percent Difference (RPD) | Check #3 | |
| 11919917 | 11919918 | 38 | 0.3 | 0.3 | ✓ | 0.6 | PASS | 0.3 | <1-pCi/L | ✓ | |
| 11919926 | 11919936 | 120 | 0.3 | 0.3 | ✓ | 0.6 | PASS | 0.3 | <1-pCi/L | ✓ | |
| 11919924 | 11919943 | Stage | 0.3 | 0.3 | ✓ | 0.6 | PASS | 0.3 | <1-pCi/L | ✓ | |
| 11919940 | 11919906 | 2 | 0.3 | 0.3 | ✓ | 0.6 | PASS | 0.3 | <1-pCi/L | ✓ | |
| 11919904 | 11919905 | Conference | 0.3 | 0.3 | ✓ | 0.6 | PASS | 0.3 | <1-pCi/L | ✓ | |
| NOTES: QC Check #1 - Data Entry QC Check #2 - Higher duplicate concentration is < or = to 2x the Lower QC Check #3 - Meets RPD Limits, by average duplicate concentration - enter 2 if RPD is BELOW warning and control levels, AND passes QC Check 1 and 2 - enter 1 if RPD is ABOVE warning and BELOW control levels, AND passes QC Check 1 and 2 - enter 0 if RPD is ABOVE control level, or 'FAILS' QC Check 1 or 2 | | | | | | | Average (pCi/L) | | Warning Level | Control Level | |
| | | | | | | | < 2.0 | | 1-pCi/L | NA | |
| | | | | | | | Between 2.0 and 3.9 | | 50% RPD | 67% RPD | |
| | | | | | | | ≥ 4.0 | | 28% RPD | 36% RPD | |

[illegible]

Attachment 2:

Laboratory Reports

Radon test result report for:**WYNGATE ES
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|--------------------------|-----------------------|-----------------------|-------|------------|
| 11919950 | 1 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919928 | 105 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919927 | 108 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919907 | 109 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919932 | 115 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919925 | 118 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919933 | 119 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919926 | 120 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919936 | 120 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919934 | 120 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919941 | 121 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919921 | 124 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919942 | 126 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919922 | 130 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919960 | 15 | 2025-02-03 @ 1:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919959 | 18 | 2025-02-03 @ 1:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919940 | 2 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919906 | 2 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919938 | 2 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919935 | 209 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919945 | 3 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919909 | 34 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919919 | 35 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919918 | 38 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919917 | 38 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919946 | 4 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919953 | 5 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919939 | 6 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919903 | 9 | 2025-02-03 @ 1:00 pm | 2025-02-06 @ 1:00 pm | < 0.3 | 2025-02-10 |
| 11919923 | APR | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919929 | APR | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919915 | ASSISTANT PRINCIPAL | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919910 | BUILDING SERVICES OFFICE | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919904 | CONFERENCE | 2025-02-03 @ 1:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919905 | CONFERENCE | 2025-02-03 @ 1:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919908 | ESOL | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919920 | ESOL 2 | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |

February 11, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**WYNGATE ES
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|--------------------|-----------------------|-----------------------|-------|------------|
| 11919937 | GYM | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919931 | GYM | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919930 | GYM OFFICE | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919913 | HEALTH ROOM | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919914 | HEALTH ROOM OFFICE | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919911 | MAIN OFFICE | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919949 | MEDIA CENTER | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919944 | MEDIA CENTER | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919951 | MEDIA OFFICE | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919952 | MEDIA WORK ROOM | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919912 | PRINCIPAL | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919943 | STAGE | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919924 | STAGE | 2025-02-03 @ 12:00 pm | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |
| 11919916 | WORK ROOM | 2025-02-03 @ 11:00 am | 2025-02-06 @ 12:00 pm | < 0.3 | 2025-02-10 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

February 11, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**OFFICE
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|---------|-----------------------|-----------------------|-------|------------|
| 11931691 | O | 2025-02-03 @ 11:00 am | 2025-02-06 @ 11:00 am | < 0.3 | 2025-02-10 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

February 11, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**TRAVEL
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|---------|-----------------------|-----------------------|-------|------------|
| 11931692 | T | 2025-02-03 @ 11:00 am | 2025-02-06 @ 11:00 am | < 0.3 | 2025-02-10 |

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGIES, INC Job Number 20001560

NOMINAL Conditions: Radon Conc 50.6 pCi/L Rel. Hum 50.6 % Temp. 70.8 F

Date Start: 12/14/24 Date Stop: 12/17/24 Date Start: _____ Date Stop: _____

Time Start: 0815 Time Stop: 0815 Time Start: _____ Time Stop: _____

Device No.'s: (3) CHAR BAGS Device No.'s: _____

11477880, 11477883, 11477896 _____

B4 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

December 23, 2024

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**SK
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|---------|----------------------|----------------------|------------|------------|
| 11477880 | SK1 | 2024-12-14 @ 8:00 am | 2024-12-17 @ 8:00 am | 52.0 ± 4.2 | 2024-12-23 |
| 11477883 | SK2 | 2024-12-14 @ 8:00 am | 2024-12-17 @ 8:00 am | 54.6 ± 4.4 | 2024-12-23 |
| 11477896 | SK3 | 2024-12-14 @ 8:00 am | 2024-12-17 @ 8:00 am | 45.5 ± 3.6 | 2024-12-23 |

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGIES, INC Job Number 20002919

NOMINAL Conditions: Radon Conc 7.0 pCi/L Rel. Hum 51.4 % Temp. 70.7 F

Date Start: 3/7/25 Date Stop: 3/10/25 Date Start: _____ Date Stop: _____

Time Start: 0832 Time Stop: 0832 Time Start: _____ Time Stop: _____

Device No.'s: (7) CHAR BAGS Device No.'s: _____

11886401 thru 11886406,

11886410

G3 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

March 19, 2025


**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

QC
MAIN

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|--------------|----------------|----------------------|----------------------|--------------|-----------------|
| 11886401 | SK1 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.8 ± 1.1 | 2025-03-19 |
| 11886405 | SK2 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.1 ± 1.1 | 2025-03-19 |
| 11886406 | SK3 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.7 ± 1.1 | 2025-03-19 |
| 11886403 | SK4 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.9 ± 1.2 | 2025-03-19 |
| 11886404 | SK5 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.6 ± 1.2 | 2025-03-19 |
| 11886410 | SK6 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 7.0 ± 1.1 | 2025-03-19 |
| 11886402 | SK7 | 2025-03-07 @ 9:00 am | 2025-03-10 @ 9:00 am | 8.6 ± 1.2 | 2025-03-19 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS
Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Testing February 3rd – February 6th, 2025

Name of Schools:

1. A. Mario Loiederman MS
2. Parkland MS
3. Rockville HS
4. Stone Mill ES
5. Wyngate ES

| | Date | Initials |
|----------------------------------|----------|----------|
| Radon Test Kits Deployed | 2/3/2025 | DM |
| Radon Test Kits Collected | 2/6/2025 | DM |
| Radon Test Kits Shipped to Lab* | 2/6/2025 | DM |
| Radon Test Kits Received by Lab* | 2/8/2025 | DM |

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835



MCPS RADON TESTING – EXECUTIVE SUMMARY

| | |
|--------------------------|--|
| Site Name | Wyngate Elementary School |
| Date of Test Report | 05/12/2022 |
| Round of Testing | Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility |
| # Rooms Tested | 4 |
| # Rooms \geq 4.0 pCi/L | 0 |
| Lowest Value | <0.3 pCi/L |
| Highest Value | 0.6 pCi/L |

Project Status

Current Project Status at this time: Testing completed; no further action needed



May 12, 2022

Mr. Brian Croyle, PG, CHMM
Environmental Specialist
Montgomery County Public Schools
Gaithersburg, MD 20879

Re: **Radon Testing Services**
KCI Job # 122108316

Location: Wyngate Elementary School
9300 Wadsworth Dr.
Bethesda, MD 20817

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Wyngate Elementary School, located at 9300 Wadsworth Dr. Bethesda, MD 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <https://www.montgomeryschoolsmd.org> or www.epa.gov/radon.

KCI visited the site on March 21, 2022 and deployed seven (7) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

1. Rooms with missing test kits from the Radon 2022 testing period (i.e. test kit was deployed but not recovered),
2. Rooms with invalidated test kits from the Radon 2022 testing period (e.g. an open window in the room or disturbed test kit),
3. Rooms which were locked/inaccessible during the Radon 2022 testing period,
4. Rooms with elevated radon results (i.e. ≥ 3.5 pCi/L),
5. Rooms previously tested for radon but not tested in Radon 2022, and
6. Additional rooms that require testing (if applicable.)

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 24, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

- Follow-up to initial testing.

These tests were conducted to:

- Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the low 40°Fs and high temperatures ranged from the low 50°Fs to the low 70°Fs. Maximum sustained winds ranged from 0-29 miles per hour. Average humidity was around 56% with 0.51 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

| Radon Concentration | Room | Result |
|---------------------|------------------|--------|
| ≥4.0 pCi/L | None | N/A |
| <4.0 pCi/L | See Attachment B | |

| Quality Control Samples | |
|--------------------------------|--|
| Results of Blank Canisters: | The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. |
| Adequate Laboratory Precision? | Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. |
| Spike Sample Analysis: | The Spike Sample analysis results indicate the laboratory is operating within statistical control limits. |

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,



Tyler P. McCleaf
Radon Measurement Provider
#111004 RT
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-3, Radon Test Summary Spreadsheets
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

| Table 1- Radon Testing Results | | |
|--------------------------------------|-------------|--------|
| Wyngate ES RT | | |
| Test Period: 03/21/2022 - 03/24/2022 | | |
| | | |
| Kit Number | Room / Area | Result |
| 11139185 | 14 | < 0.3 |
| 11139199 | APR | < 0.3 |
| 11139200 | APR | 0.6 |
| 11139191 | KITCHEN | < 0.3 |
| 11139186 | MAIN OFFICE | 0.5 |
| 11139195 | MAIN OFFICE | < 0.3 |
| 11139196 | MAIN OFFICE | < 0.3 |

| Table 2- Radon Testing Results | | | |
|--------------------------------------|---------|--------------|--------|
| Wyngate ES RT | | | |
| Test Period: 03/21/2022 - 03/24/2022 | | | |
| | | | |
| Kit Number | QC Type | Room / Area | Result |
| 11139196 | D | Main office | < 0.3 |
| 11139195 | FB | Main office | < 0.3 |
| 11139902 | OB | OFFICE BLANK | < 0.3 |
| 11139928 | TB | TRAVEL BLANK | < 0.3 |

ATTACHMENT C

Laboratory Analytical Results

March 28, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**WINGATE ES RT
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|--------------|----------------|-----------------------|-----------------------|--------------|-----------------|
| 11139185 | 14 | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | < 0.3 | 2022-03-28 |
| 11139199 | APR | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | < 0.3 | 2022-03-28 |
| 11139200 | APR | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | 0.6 ± 0.3 | 2022-03-28 |
| 11139191 | KITCHEN | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | < 0.3 | 2022-03-28 |
| 11139186 | MAIN OFFICE | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | 0.5 ± 0.3 | 2022-03-28 |
| 11139195 | MAIN OFFICE | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | < 0.3 | 2022-03-28 |
| 11139196 | MAIN OFFICE | 2022-03-21 @ 12:00 pm | 2022-03-24 @ 11:00 am | < 0.3 | 2022-03-28 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, Inc. Job Number 204620

NOMINAL Conditions: Radon Conc 27.0 pCi/L Rel. Hum 50.1 % Temp. 70.0 F

Date Start: 3/18/22 Date Stop: 3/21/22 Date Start: _____ Date Stop: _____

Time Start: 0705 Time Stop: 0705 Time Start: _____ Time Stop: _____

Device No.'s: (5) Char Bags - Device No.'s: _____

11139367, 11139368, 11139371, _____

11139710, 11139717 _____

E3 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (25.7 pCi/L).

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|---------|----------------------|----------------------|----------------|------------|
| 11139367 | SK1 | 2022-03-18 @ 7:00 am | 2022-03-21 @ 7:00 am | 25.9 \pm 2.1 | 2022-03-30 |
| 11139368 | SK2 | 2022-03-18 @ 7:00 am | 2022-03-21 @ 7:00 am | 23.9 \pm 2.0 | 2022-03-30 |
| 11139371 | SK3 | 2022-03-18 @ 7:00 am | 2022-03-21 @ 7:00 am | 25.7 \pm 2.1 | 2022-03-30 |
| 11139710 | SK4 | 2022-03-18 @ 7:00 am | 2022-03-21 @ 7:00 am | 26.4 \pm 2.1 | 2022-03-30 |
| 11139717 | SK5 | 2022-03-18 @ 7:00 am | 2022-03-21 @ 7:00 am | 24.6 \pm 2.0 | 2022-03-30 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS
Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – March 2022 Schools – Retesting

Name of Schools:

1. Rosa Parks MS
2. Poolesville ES
3. Wyngate ES
4. Seven Locks ES
5. Walt Whitman HS
6. Somerset ES
7. Rock Creek Forest ES
8. Walter Johnson HS
9. Westbrook ES
10. Westland MS
11. Farmland ES
12. College Gardens ES
13. Julius West MS
14. Robert Frost MS
15. Carl Sandburg Learning Center

| | Date | Initials |
|----------------------------------|------------|----------|
| Radon Test Kits Deployed | 03/21/2022 | BMM |
| Radon Test Kits Collected | 03/24/2022 | BMM |
| Radon Test Kits Shipped to Lab* | 03/25/2022 | BMM |
| Radon Test Kits Received by Lab* | 03/28/2022 | BMM |

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

MCPS RADON TESTING – EXECUTIVE SUMMARY

| | |
|--------------------------|--|
| Site Name | Wyngate Elementary School |
| Date of Test Report | 2/21/2022 |
| Round of Testing | Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility |
| # Rooms Tested | 38 |
| # Rooms \geq 4.0 pCi/L | 0 |
| Lowest Value | <0.3 pCi/L |
| Highest Value | 0.8 pCi/L |

Project Status:

Initial testing completed; Missing or compromised samples need re-sampling



February 21, 2022

Brian T. Croyle, PG, CHMM
Environmental Specialist
Montgomery County Public Schools
Gaithersburg, MD 20879

Re: **Radon Testing Services**
KCI Job # 122108316

Location: Wyngate Elementary School
9300 Wadsworth Dr.
Bethesda, MD 20817

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Wyngate Elementary School, located at 9300 Wadsworth Dr. Bethesda, MD 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <https://www.montgomeryschoolsmd.org> or www.epa.gov/radon.

KCI visited the site on January 18, 2022 and deployed forty four (44) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 21, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc.

is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

- Follow-up to initial testing.

These tests were conducted to:

- Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 30s and high temperatures ranged from the mid 30s to the mid 40s Fahrenheit. Maximum sustained winds ranged from 7-20 miles per hour. Average humidity was around 50% with .05 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

| Radon Concentration | Room | Result |
|---------------------|------------------|--------|
| ≥4.0 pCi/L | None | N/A |
| <4.0 pCi/L | See Attachment B | |

| Quality Control Samples | |
|--------------------------------|--|
| Results of Blank Canisters: | The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. |
| Adequate Laboratory Precision? | Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. |
| Spike Sample Analysis: | The Spike Sample analysis results indicate the laboratory is operating within statistical control limits. |

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,



Tyler P. McCleaf
Radon Measurement Provider
#111004 RT
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-3, Radon Test Summary Spreadsheets
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

| Table 1- Radon Testing Results | | |
|------------------------------------|-----------------------------|--------|
| Wyngate ES | | |
| Test Period: 01/18/2022-01/21/2022 | | |
| | | |
| Kit Number | Room / Area | Result |
| 11106387 | 105 | < 0.3 |
| 11106376 | 115 | < 0.3 |
| 11106375 | 118 | < 0.3 |
| 11106381 | 119 | 0.8 |
| 11106382 | 120 | < 0.3 |
| 11106384 | 121 | < 0.3 |
| 11106390 | 121 | 0.6 |
| 11106383 | 124 | < 0.3 |
| 11106391 | 126 | < 0.3 |
| 11106392 | 130 | < 0.3 |
| 11106369 | 208 | 0.6 |
| 11106377 | 211 | 0.6 |
| 11106398 | 219 | < 0.3 |
| 11106368 | 108 INSTRUMENTAL MUSIC | < 0.3 |
| 11106347 | 30 HEALTH ROOM | < 0.3 |
| 11106338 | 32 WORK ROOM | < 0.3 |
| 11106365 | 34 MAKER SPACE ROOM | < 0.3 |
| 11106354 | 35 FACULTY LOUNGE | < 0.3 |
| 11106361 | ALL PURPOSE ROOM | < 0.3 |
| 11106348 | ASSISTANT PRINCIPALS OFFICE | < 0.3 |
| 11106346 | BS TEAM OFFICE | < 0.3 |
| 11106340 | CONFERENCE ROOM | < 0.3 |
| 11106355 | GYM | < 0.3 |
| 11106356 | GYM | < 0.3 |
| 11106353 | GYM OFFICE | < 0.3 |
| 11106341 | KITCHEN OFFICE | NA |
| 11106332 | MAIN OFFICE | NA |
| 11106362 | MEDIA CENTER | < 0.3 |
| 11106374 | MEDIA CENTER | < 0.3 |
| 11106363 | MEDIA CENTER OFFICE | < 0.3 |
| 11106373 | MEDIA WORK ROOM | < 0.3 |
| 11106357 | MRS SMITH WORKSPACE | < 0.3 |
| 11106349 | PARAEDUCATOR OFFICE | 0.6 |
| 11106339 | PRINCIPALS OFFICE | < 0.3 |
| 11106372 | ROOM 1 | < 0.3 |
| 11106386 | ROOM 19 | < 0.3 |
| 11106371 | ROOM 2 | < 0.3 |
| 11106364 | ROOM 3 | < 0.3 |
| 11106379 | ROOM 4 | < 0.3 |
| 11106370 | ROOM 5 | < 0.3 |
| 11106380 | ROOM 5 | < 0.3 |
| 11106385 | ROOM 6 | < 0.3 |

| Table 1- Radon Testing Results | | |
|------------------------------------|-------------|--------|
| Wyngate ES | | |
| Test Period: 01/18/2022-01/21/2022 | | |
| | | |
| Kit Number | Room / Area | Result |
| 11106378 | ROOM 9 | < 0.3 |
| 11106331 | TRIAGE ROOM | < 0.3 |

| Table 2- Radon Testing Results | | | |
|--------------------------------|---------|--------------|--------|
| Wyngate ES | | | |
| Test Period: 01/18/22-01/21/22 | | | |
| | | | |
| Kit Number | QC Type | Room / Area | Result |
| 11106356 | D | Gym | < 0.3 |
| 11106374 | D | Media Center | < 0.3 |
| 11106362 | FB | Media Center | < 0.3 |
| 11106384 | D | 121 | < 0.3 |
| 11106380 | D | Room 5 | < 0.3 |
| 11106370 | FB | Room 5 | < 0.3 |
| 11106397 | OB | OFFICE BLANK | < 0.3 |
| 11106400 | FB | TRAVEL BLANK | < 0.3 |

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|-----------------------------|-----------------------|-----------------------|-----------|------------|
| 11106387 | 105 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106368 | 108 INSTRUMENTAL MUSIC | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106376 | 115 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106375 | 118 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106381 | 119 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | 0.8 ± 0.4 | 2022-01-26 |
| 11106382 | 120 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106384 | 121 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106390 | 121 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | 0.6 ± 0.4 | 2022-01-26 |
| 11106383 | 124 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106391 | 126 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106392 | 130 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106369 | 208 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | 0.6 ± 0.4 | 2022-01-26 |
| 11106377 | 211 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | 0.6 ± 0.4 | 2022-01-26 |
| 11106398 | 219 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106347 | 30 HEALTH ROOM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106338 | 32 WORK ROOM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106365 | 34 MAKER SPACE ROOM | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106354 | 35 FACULTY LOUNGE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106361 | ALL PURPOSE ROOM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106348 | ASSISTANT PRINCIPALS OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106346 | BS TEAM OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106340 | CONFERENCE ROOM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106356 | GYM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106355 | GYM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106353 | GYM OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106341 | KITCHEN OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | ???? IF1 | 2022-01-26 |
| 11106332 | MAIN OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | ???? IF1 | 2022-01-26 |
| 11106362 | MEDIA CENTER | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106374 | MEDIA CENTER | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106363 | MEDIA CENTER OFFICE | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106373 | MEDIA WORK ROOM | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106357 | MRS SMITH WORKSPACE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106349 | PARAEDUCATOR OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | 0.6 ± 0.4 | 2022-01-26 |
| 11106339 | PRINCIPALS OFFICE | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |
| 11106372 | ROOM 1 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106386 | ROOM 19 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106371 | ROOM 2 | 2022-01-18 @ 12:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |

January 27, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|----------|-------------|-----------------------|-----------------------|-------|------------|
| 11106364 | ROOM 3 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106379 | ROOM 4 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106370 | ROOM 5 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106380 | ROOM 5 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106385 | ROOM 6 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106378 | ROOM 9 | 2022-01-18 @ 1:00 pm | 2022-01-21 @ 10:00 am | < 0.3 | 2022-01-26 |
| 11106331 | TRIAGE ROOM | 2022-01-18 @ 11:00 am | 2022-01-21 @ 9:00 am | < 0.3 | 2022-01-26 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, Inc. Job Number 203404

NOMINAL Conditions: Radon Conc 16.2 pCi/L Rel. Hum 28.8 % Temp. 59.9 F

Date Start: 12/24/21 Date Stop: 12/27/21 Date Start: _____ Date Stop: _____

Time Start: 0809 Time Stop: 0809 Time Start: _____ Time Stop: _____

Device No.'s: (2) Char Bags- Device No.'s: _____

9341721, 9341722

G4 Left

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

December 31, 2021

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

SK
MA MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (16.2 pCi/L).

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|---------|---------|----------------------|----------------------|----------------|------------|
| 9341721 | 1 | 2021-12-24 @ 8:00 am | 2021-12-27 @ 8:00 am | 11.6 \pm 0.9 | 2021-12-31 |
| 9341722 | 1 | 2021-12-24 @ 8:00 am | 2021-12-27 @ 8:00 am | 15.4 \pm 1.2 | 2021-12-31 |

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS
Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – January 2022 Schools

Name of Schools:

1. Poolesville ES
2. Rosa Parks MS
3. Seven Locks ES
4. Somerset ES
5. Thomas Pyle MS
6. Walt Whitman HS
7. Walter Johnson HS
8. Westland MS
9. Wyngate ES

| | Date | Initials |
|----------------------------------|------------|----------|
| Radon Test Kits Deployed | 01/18/2022 | JM |
| Radon Test Kits Collected | 01/21/2022 | JM |
| Radon Test Kits Shipped to Lab* | 01/21/2022 | JM |
| Radon Test Kits Received by Lab* | 01/23/2022 | JM |

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

RADON SCREENING SURVEY – FOLLOW-UP WYNGATE ELEMENTARY SCHOOL

9300 Wadsworth Drive, Bethesda, Maryland 20817

EXECUTIVE SUMMARY

| | |
|--|--|
| Date of Test Report: | 4/15/16 Follow-Up |
| Round of Testing: | Initial Follow-up Post Remediation |
| # Rooms Tested | 1 |
| # Rooms \geq 4.0 pCi/L: | 0 |
| Low Value: | <0.4 |
| High Value: | <0.4 |
| Confirmed Rooms \geq 4.0 pCi/L US EPA Action Level | 0 |

Summary of Sampling Events \geq 4.0 pCi/L

| Room | Result (pCi/L) 3/2/16 Initial | Result (pCi/L) 4/15/16 Follow-Up | Average Result (pCi/L) |
|------|----------------------------------|-------------------------------------|---------------------------|
| 9 | --- Missing | <0.4 | <0.4 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |



MCPS RADON TESTING

Executive Summary: Wyngate Elementary School

| | |
|---------------------------|--|
| Date of Test Report: | 4/15/2016 |
| Round of Testing: | Initial Follow-up Post Remediation |
| | |
| # Rooms Tested: | 1 |
| # Rooms \geq 4.0 pCi/L: | 0 |
| | |
| Low Value: | < 0.4 |
| High Value: | < 0.4 |

Project Status:

Retesting completed; no further action at this time.



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

April 15, 2016

Mr. Richard Cox
Indoor Air Quality Team Leader
Montgomery County Public Schools
850 Hungerford Drive
Rockville, MD 20850

Re: **Radon Testing Services**
KCI Job # 12146341.32

Location: Wyngate Elementary School
9300 Wadsworth Drive
Bethesda, MD 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Wyngate Elementary School, located at 9300 Wadsworth Drive in Bethesda, Maryland 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on March 14, 2016 and deployed three (3) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to TCS Industries Inc. as spike samples. The spiked tests were exposed to a known radon concentration by TCS prior to being returned to the laboratory for analysis.

KCI returned to the site on March 17, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis (certification # ARL0007) located at 929 Mount

Zion Road, Lebanon, Pennsylvania.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}\text{F}$.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

| Radon Concentration | Room | Result |
|------------------------------------|------------------|---------------|
| ≥ 4.0 pCi/L | none | n/a |
| < 4.0 pCi/L | See Attachment B | |

Notes:

D- Duplicate sample

The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Sincerely,



James M. Moulds
Radon Measurement Specialist
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-Radon Test Summary Spreadsheet
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank*

PM- Project Manager

QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 12 testing. Office blanks were not submitted under each school individually.

| Radon Testing Results | | |
|--------------------------------|-------------|--------|
| Wyngate ES | | |
| Test Period: 03/14/16-03/17/16 | | |
| | | |
| Kit Number | Room / Area | Result |
| 3029046 | 9 | <0.4 |

Table Note:

* Missing or Compromised Sample

| Radon Testing Results | | |
|--------------------------------|---------|--------|
| Wyngate ES | | |
| Test Period: 03/14/16-03/17/16 | | |
| Kit Number | QC Type | Result |
| 3029044 | D (9) | <0.4 |
| 3029045 | FB (9) | <0.4 |

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

NRPP 10511AL
NRSB ARL0007

EPA Method #402-R-92-004
Charcoal Canister
NRPP Device Code 6048
NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 12146341

KCI Technologies
936 Ridgebrook Rd
Sparks MD 21152

Wyngate ES
9300 Wadsworth Drive
Bethesda MD 20817

| Log Number | Device Number | Test Exposure Duration: | | Area Tested | Result (pCi/L) |
|------------|---------------|-------------------------|--------------------|---------------------|----------------|
| 3017496 | 3029044 | 03/14/2016 12:51 pm | 03/17/2016 8:45 am | Unit 9 Second Floor | <0.4 |
| 3017497 | 3029045 | 03/14/2016 12:51 pm | 03/17/2016 8:44 am | Unit 9 Second Floor | <0.4 |
| 3017498 | 3029046 | 03/14/2016 12:51 pm | 03/17/2016 8:44 am | Unit 9 Second Floor | <0.4 |

Comment: A copy of this report was emailed to tehsin@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 03/21/2016 Date Logged: 03/21/2016 Date Analyzed: 03/21/2016 Date Reported: 03/22/2016

Report Reviewed By: Shane Leboucq


Report Approved By: Carolyn D. Koke

Carolyn D. Koke, President, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is $\pm 10\%$. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Contact Information:

| | |
|--------------|-----------------------|
| Contact | Tehsin Aurangabadwala |
| Telephone | 410-891-1726 |
| Technician | |
| Cert. Number | |
| Signature | |

1 of 1

NRPP 10511AL
NRSB ARL0007

EPA Method #402-R-92-004
Charcoal Canister
NRPP Device Code 6048
NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 12146341

KCI Technologies
936 Ridgebrook Rd
Sparks MD 21152

MCPS Radon Phase 12 Office Blank

| Log Number | Device Number | Test Exposure Duration: | Area Tested | Result (pCi/L) |
|------------|---------------|---------------------------------------|-----------------------------|----------------|
| 3017546 | 3029151 | 03/14/2016 9:30 am 03/17/2016 9:30 am | Unit # 0 Office First Floor | <0.4 |

Comment: A copy of this report was emailed to tehsin@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 03/21/2016 Date Logged: 03/21/2016 Date Analyzed: 03/21/2016 Date Reported: 03/22/2016

Report Reviewed By: Grace Heubling

Report Approved By: Carolyn D. Koke

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs

The uncertainty of this radon measurement is $\pm 10\%$. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

Radon Device Type Open Face Canister

Send Written Report To:

| | | | |
|----------------|-----------------------|----|-------|
| Name | KCI Technologies, Inc | | |
| Address | 936 Ridgebrook Road | | |
| Address | | | |
| City / Town | Sparks | | |
| State/Province | Postal Code | MD | 21152 |
| Report Country | Baltimore County | | |
| Email Address | tehsin@kci.com | | |

Site Tested:

| | |
|----------------|-------------------|
| Site Name | KCI OFFICE |
| Address | 936 RIDGEBROOK RD |
| Address | |
| City / Town | SPARKS |
| State/Province | MD |
| Test Country | 21152 |
| Project Number | Montgomery County |
| | 12146341 |

Contact Information:

| | |
|--------------|-----------------------|
| Contact | Tehsin Aurangabadwala |
| Telephone | 410-891-1726 |
| Technician | |
| Cert. Number | |
| Signature | |

[illegible]

NRPP 10511AL
NRSB ARL0007

EPA Method #402-R-92-004
Charcoal Canister
NRPP Device Code 6048
NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 12146341

KCI Technologies
936 Ridgebrook Rd
Sparks MD 21152

MCPS Radon Phase 12 Office Blank

| Log Number | Device Number | Test Exposure Duration: | Area Tested | Result (pCi/L) |
|------------|---------------|---------------------------------------|-----------------------------|----------------|
| 3017545 | 3029152 | 03/15/2016 9:30 am 03/18/2016 9:30 am | Unit # 0 Office First Floor | <0.4 |

Comment: A copy of this report was emailed to tehsin@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 03/21/2016 Date Logged: 03/21/2016 Date Analyzed: 03/21/2016 Date Reported: 03/22/2016

Report Reviewed By: Grace Heubling

Report Approved By: Carolyn D. Koke

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs

The uncertainty of this radon measurement is $\pm 10\%$. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

Radon Device Type Open Face Canister

Send Written Report To:

| | |
|----------------|-----------------------|
| Name | KCI Technologies, Inc |
| Address | 936 Ridgebrook Road |
| Address | |
| City / Town | Sparks |
| State/Province | MD |
| Postal Code | 21152 |
| Report Country | Baltimore County |
| Email Address | tehsin@kci.com |

Site Tested:

| | | |
|----------------|---------------------|-------|
| Site Name | KCI OFFICE | |
| Address | 936 RIDGE BROOK RD. | |
| Address | | |
| City / Town | SPARKS | |
| State/Province | MD | 21152 |
| Test Country | Montgomery County | |
| Project Number | 12146341 | |

Contact Information:

| | |
|--------------|-----------------------|
| Contact | Tehsin Aurangabadwala |
| Telephone | 410-891-1726 |
| Technician | |
| Cert. Number | |
| Signature | |

[illegible]

NRPP 10511AL
NRSB ARL0007

EPA Method #402-R-92-004
Charcoal Canister
NRPP Device Code 6048
NRSB Device Code 10317

Laboratory Report for:

Property Tested:

KCI Technologies
936 Ridgebrook Rd
Sparks MD 21152

MCPS
Transit Blanks

| Log Number | Device Number | Test Exposure Duration: | | Area Tested | Result (pCi/L) |
|------------|---------------|-------------------------|--------------------|-------------|----------------|
| 3010588 | 3028953 | 01/19/2016 1:00 pm | 01/22/2016 9:30 am | 1 | < 0.4 |
| 3010589 | 3028955 | 01/19/2016 1:00 pm | 01/22/2016 9:30 am | 2 | < 0.4 |
| 3010590 | 3028954 | 01/19/2016 1:00 pm | 01/22/2016 9:30 am | 3 | < 0.4 |
| 3010591 | 3028997 | 01/19/2016 1:00 pm | 01/22/2016 9:30 am | 4 | < 0.4 |

Comment: AMENDED REPORT for 3028953-8955, 3028997 on 2/22/16 to add all missing information from the blank datasheet. A copy of this report was emailed to james.moulds@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 01/27/2016 Date Logged: 01/27/2016 Date Analyzed: 01/28/2016 Date Reported: 01/28/2016

Report Reviewed By: Christie Bates

Report Approved By: Carolyn D. Koke

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs

The uncertainty of this radon measurement is $\pm 10\%$. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

**Instructions on back of form
Read instructions carefully
Discrepancies will invalidate tests**

Test Site Info

Name of Building/Project or Owner

Site Address: Transit

City: _____ State _____ Zip _____

Projects Contact Name: Simon Cooper Phone: _____

County

Email:

| Detector Serial# | ROOM NAME & NUMBER - LOCATION OF DETECTOR IN ROOM (indicate duplicates and blanks) | Floor | Start Date | Start Time Include AM/PM | Stop Date | Stop Time Include AM/PM |
|------------------|---|-------|------------|-----------------------------|-----------|----------------------------|
| 3028953 | Transit | 1 | 1/19/16 | 4:40:00pm | 1/22/16 | 9:30am |
| 8955 | Transit | 1 | 1/19/16 | | | |
| 8954 | Transit | 1 | 1/19/16 | | | |
| 8997 | Transit | 1 | 1/19/16 | | | |
| | | | | | | |
| | | | | | | |

1/27/2016

KCI Technologies, Inc.

3010588 3028953 ACPC275B EXP12/31/2018

Structure Type: (circle one or more) Basement - Crawlspace - Slab on Grade - Other

Both Placed by and Retrieved by signatures are required

| Test Purpose: | Initial Screening | Follow Up Test - |
|---------------|-------------------|------------------|
| | | |

Canisters placed by

| Building Type: | Residential | - Non Residential |
|---------------------------|-------------|-------------------|
| 1. Single-Family Detached | 1.00 | 1.00 |
| 2. Single-Family Attached | 1.00 | 1.00 |
| 3. Multi-Family Detached | 1.00 | 1.00 |
| 4. Multi-Family Attached | 1.00 | 1.00 |
| 5. Commercial | 1.00 | 1.00 |
| 6. Industrial | 1.00 | 1.00 |
| 7. Institutional | 1.00 | 1.00 |
| 8. Public Works | 1.00 | 1.00 |
| 9. Other | 1.00 | 1.00 |

Canisters retrieved by

(Circle One)

Private Day Care - Private School
Day Care in Public School - Public School

Send Results To:

Company Name: Mc:Tech
Address: 936 Ridgebrook

Attention:

James G. Thompson

Date _____

Were general operating conditions maintained?

Yes - No explain if No

Were closed building

conditions maintained?

Yes - No explain if NO

Normal Temp. Yes - No

[illegible]

| | Windy Y-N | Rainy Y-N |
|-----|-----------|-----------|
| 1 | 0.00 | 0.00 |
| 2 | 0.00 | 0.00 |
| 3 | 0.00 | 0.00 |
| 4 | 0.00 | 0.00 |
| 5 | 0.00 | 0.00 |
| 6 | 0.00 | 0.00 |
| 7 | 0.00 | 0.00 |
| 8 | 0.00 | 0.00 |
| 9 | 0.00 | 0.00 |
| 10 | 0.00 | 0.00 |
| 11 | 0.00 | 0.00 |
| 12 | 0.00 | 0.00 |
| 13 | 0.00 | 0.00 |
| 14 | 0.00 | 0.00 |
| 15 | 0.00 | 0.00 |
| 16 | 0.00 | 0.00 |
| 17 | 0.00 | 0.00 |
| 18 | 0.00 | 0.00 |
| 19 | 0.00 | 0.00 |
| 20 | 0.00 | 0.00 |
| 21 | 0.00 | 0.00 |
| 22 | 0.00 | 0.00 |
| 23 | 0.00 | 0.00 |
| 24 | 0.00 | 0.00 |
| 25 | 0.00 | 0.00 |
| 26 | 0.00 | 0.00 |
| 27 | 0.00 | 0.00 |
| 28 | 0.00 | 0.00 |
| 29 | 0.00 | 0.00 |
| 30 | 0.00 | 0.00 |
| 31 | 0.00 | 0.00 |
| 32 | 0.00 | 0.00 |
| 33 | 0.00 | 0.00 |
| 34 | 0.00 | 0.00 |
| 35 | 0.00 | 0.00 |
| 36 | 0.00 | 0.00 |
| 37 | 0.00 | 0.00 |
| 38 | 0.00 | 0.00 |
| 39 | 0.00 | 0.00 |
| 40 | 0.00 | 0.00 |
| 41 | 0.00 | 0.00 |
| 42 | 0.00 | 0.00 |
| 43 | 0.00 | 0.00 |
| 44 | 0.00 | 0.00 |
| 45 | 0.00 | 0.00 |
| 46 | 0.00 | 0.00 |
| 47 | 0.00 | 0.00 |
| 48 | 0.00 | 0.00 |
| 49 | 0.00 | 0.00 |
| 50 | 0.00 | 0.00 |
| 51 | 0.00 | 0.00 |
| 52 | 0.00 | 0.00 |
| 53 | 0.00 | 0.00 |
| 54 | 0.00 | 0.00 |
| 55 | 0.00 | 0.00 |
| 56 | 0.00 | 0.00 |
| 57 | 0.00 | 0.00 |
| 58 | 0.00 | 0.00 |
| 59 | 0.00 | 0.00 |
| 60 | 0.00 | 0.00 |
| 61 | 0.00 | 0.00 |
| 62 | 0.00 | 0.00 |
| 63 | 0.00 | 0.00 |
| 64 | 0.00 | 0.00 |
| 65 | 0.00 | 0.00 |
| 66 | 0.00 | 0.00 |
| 67 | 0.00 | 0.00 |
| 68 | 0.00 | 0.00 |
| 69 | 0.00 | 0.00 |
| 70 | 0.00 | 0.00 |
| 71 | 0.00 | 0.00 |
| 72 | 0.00 | 0.00 |
| 73 | 0.00 | 0.00 |
| 74 | 0.00 | 0.00 |
| 75 | 0.00 | 0.00 |
| 76 | 0.00 | 0.00 |
| 77 | 0.00 | 0.00 |
| 78 | 0.00 | 0.00 |
| 79 | 0.00 | 0.00 |
| 80 | 0.00 | 0.00 |
| 81 | 0.00 | 0.00 |
| 82 | 0.00 | 0.00 |
| 83 | 0.00 | 0.00 |
| 84 | 0.00 | 0.00 |
| 85 | 0.00 | 0.00 |
| 86 | 0.00 | 0.00 |
| 87 | 0.00 | 0.00 |
| 88 | 0.00 | 0.00 |
| 89 | 0.00 | 0.00 |
| 90 | 0.00 | 0.00 |
| 91 | 0.00 | 0.00 |
| 92 | 0.00 | 0.00 |
| 93 | 0.00 | 0.00 |
| 94 | 0.00 | 0.00 |
| 95 | 0.00 | 0.00 |
| 96 | 0.00 | 0.00 |
| 97 | 0.00 | 0.00 |
| 98 | 0.00 | 0.00 |
| 99 | 0.00 | 0.00 |
| 100 | 0.00 | 0.00 |

Make sure information is complete and correct.

If a recalculation is requested there is a \$10.00 recalc fee PER Canister.

Mailing: PO Box 990 Jonestown, PA 17038

Shipping: 929 Mt Zion Road, Lebanon, PA 17046

800-523-4964 fax 717-274-5662

NEHA 10511AL NRSB ARL 0007

Revision 5
4/2015

TCS INDUSTRIES, INC.

(717) 657-7032

RADON GAS DETECTION

www.radondetek.com

4326 Crestview Road, Harrisburg, PA 17112

James Mouldsdale
KCI
936 Ridgebrook Rd.
Sparks, MD 21152

April 04, 2016

Dear Mr. Mouldsdale:

The spike exposure data were:

Start 04/04/16 @ 1110 hrs EDT
End 04/06/16 @ 1113 hrs EDT

AC 3029218, 3029219, 3029220, 3029217, 3029214, 3029217, and 3029166

Average radon concentration was 10.6 pCi/L +/- 5%

Avg. Temp. was 71F
Avg. RH was 51%
Elevation was 490 feet above sea level

Sincerely,



Carl H. Distenfeld, CHP

TCS Radon Chamber NRSB CHM 0002

NRPP 10511AL
NRSB ARL0007

EPA Method #402-R-92-004
Charcoal Canister
NRPP Device Code 6048
NRSB Device Code 10317

Laboratory Report for:

Property Tested:

KCI Technologies
936 Ridgebrook Rd
Sparks MD 21152

MCPS
Radon Spike Sample Laboratory Results


| Log Number | Device Number | Test Exposure Duration: | | Area Tested | Result (pCi/L) |
|------------|---------------|-------------------------|---------------------|---------------|----------------|
| 3020102 | 3029166 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 11.9 |
| 3020103 | 3029214 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 11.5 |
| 3020104 | 3029217 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 10.7 |
| 3020105 | 3029218 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 11.3 |
| 3020106 | 3029219 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 11.0 |
| 3020107 | 3029220 | 04/04/2016 11:10 am | 04/06/2016 11:13 am | Not Indicated | 10.5 |


Comment: A copy of this report was emailed to james.mouldsdale@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 04/07/2016 Date Logged: 04/07/2016 Date Analyzed: 04/07/2016 Date Reported: 04/08/2016

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

Report Reviewed By: 

Report Approved By: 
Carolyn D. Koke, President, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is $\pm 10\%$. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



MCPS RADON TESTING

Executive Summary: Wyngate Elementary School

| | |
|---------------------------|--|
| Date of Test Report: | 3/2/2016 |
| Round of Testing: | Initial Follow-up Post Remediation |
| | |
| # Rooms Tested: | 48 |
| # Rooms \geq 4.0 pCi/L: | 0 |
| | |
| Low Value: | < 0.3 |
| High Value: | 1.5 |

Project Status:

Initial testing completed; missing or compromised samples need re-test.



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 2, 2016

Mr. Richard Cox
Indoor Air Quality Team Leader
Montgomery County Public Schools
850 Hungerford Drive
Rockville, MD 20850

Re: **Radon Testing Services**
KCI Job # 12146341.26

Location: Wyngate Elementary School
9300 Wadsworth Drive
Bethesda, MD 20817

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Wyngate Elementary School, located at 9300 Wadsworth Drive in Bethesda, Maryland 20817 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 1, 2016 and deployed fifty-eight (58) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 4, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}\text{F}$.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

| Radon Concentration | Room | Result |
|------------------------------------|------------------|---------------|
| ≥ 4.0 pCi/L | none | n/a |
| < 4.0 pCi/L | See Attachment B | |

Notes:

D- Duplicate sample

The field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Sincerely,



James M. Moulds
Radon Measurement Specialist
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-Radon Test Summary Spreadsheet
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

| Radon Testing Results | | |
|--------------------------------|---------------|--------|
| Wyngate Elementary School | | |
| Test Period: 02/01/16-02/04/16 | | |
| Kit Number | Room / Area | Result |
| 7730139 | 1 | 0.6 |
| 7730140 | 2 | < 0.3 |
| 7730141 | 3 | 0.9 |
| 7730143 | 4 | 0.7 |
| 7730144 | 5 | 0.6 |
| 7730145 | 6 | < 0.3 |
| 7730157 | 7 | 0.7 |
| 7730156 | 8 | 0.7 |
| 7730153 | 10 | < 0.3 |
| 7730154 | 11 | 0.6 |
| 7730152 | 12 | < 0.3 |
| 7730151 | 14 | 0.7 |
| 7730150 | 16 | 0.6 |
| 7730146 | 18 | 0.6 |
| 7730147 | 20 | < 0.3 |
| 7730148 | 22 | 0.6 |
| 7730149 | 23 | 0.6 |
| 7730101 | 28 | < 0.3 |
| 7730118 | 29 | < 0.3 |
| 7730113 | 30 | 0.7 |
| 7730116 | 31 | < 0.3 |
| 7730112 | 32 | 0.7 |
| 7730115 | 34 | < 0.3 |
| 7730110 | 35 | 0.6 |
| 7730121 | 38 | 0.5 |
| 7730125 | 101 | 0.7 |
| 7730126 | 101 | 0.8 |
| 7730127 | 105 | 0.9 |
| 7730130 | 108 | 0.8 |
| 7730129 | 109 | 1.0 |
| 7730131 | 115 | 1.1 |
| 7730132 | 118 | 0.9 |
| 7730134 | 119 | 0.9 |
| 7730133 | 120 | 1.0 |
| 7730135 | 121 | 1.0 |
| 7730136 | 124 | 1.4 |
| 7730137 | 126 | 1.3 |
| 7730138 | 130 | 1.5 |
| 7730104 | 28A | 0.6 |
| 7730107 | 28B | 0.5 |
| 7730108 | 28C | 0.7 |
| 7730109 | 28D | < 0.3 |
| 7730114 | 30A | 0.7 |
| 7730117 | 31A | < 0.3 |
| 7730155 | * 9 (Missing) | - |
| 7730122 | GYM | 0.7 |

Table Note:

* Missing or Compromised Sample

| Radon Testing Results | | |
|--------------------------------|-------------|--------|
| Wyngate Elementary School | | |
| Test Period: 02/01/16-02/04/16 | | |
| | | |
| Kit Number | Room / Area | Result |
| 7730123 | GYM | < 0.3 |
| 7730124 | GYM A | < 0.3 |
| 7730120 | TVA | 0.8 |
| 7730119 | TVB | 0.6 |

Table Note:

* Missing or Compromised Sample

| Radon Testing Results | | |
|--------------------------------|----------|--------|
| Wyngate Elementary School | | |
| Test Period: 02/01/16-02/04/16 | | |
| Kit Number | QC Type | Result |
| 7730128 | D (105) | 0.6 |
| 7730102 | D (28) | 0.6 |
| 7730105 | D (28A) | 0.9 |
| 7730142 | D (3) | 0.9 |
| 7730111 | D (35) | < 0.3 |
| 7730103 | FB (28) | < 0.3 |
| 7730106 | FB (28A) | < 0.3 |
| 7729850 | OB (0) | < 0.3 |

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:

**WYNGATE ELEMENTARY SCHOOL
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|---------|---------|-----------------------|-----------------------|-----------|------------|
| 7729850 | 0 | 2016-02-01 @ 3:00 pm | 2016-02-04 @ 11:00 am | < 0.3 | 2016-02-09 |
| 7730139 | 1 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730153 | 10 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730125 | 101 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730126 | 101 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.8 ± 0.3 | 2016-02-08 |
| 7730127 | 105 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |
| 7730128 | 105 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730130 | 108 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.8 ± 0.3 | 2016-02-08 |
| 7730129 | 109 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 1.0 ± 0.4 | 2016-02-08 |
| 7730154 | 11 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730131 | 115 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.1 ± 0.4 | 2016-02-08 |
| 7730132 | 118 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |
| 7730134 | 119 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |
| 7730152 | 12 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730133 | 120 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.0 ± 0.3 | 2016-02-08 |
| 7730135 | 121 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.0 ± 0.4 | 2016-02-08 |
| 7730136 | 124 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.4 ± 0.4 | 2016-02-08 |
| 7730137 | 126 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.3 ± 0.4 | 2016-02-08 |
| 7730138 | 130 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 1.5 ± 0.4 | 2016-02-08 |
| 7730151 | 14 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730150 | 16 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730146 | 18 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730140 | 2 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730147 | 20 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730148 | 22 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730149 | 23 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730101 | 28 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730102 | 28 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730103 | 28 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730104 | 28A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730105 | 28A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |
| 7730106 | 28A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730107 | 28B | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.5 ± 0.3 | 2016-02-08 |
| 7730108 | 28C | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730109 | 28D | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730118 | 29 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730141 | 3 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |

February 23, 2016
**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**WYNGATE ELEMENTARY SCHOOL
MAIN**

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|---------|---------|-----------------------|----------------------|-----------|------------|
| 7730142 | 3 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.9 ± 0.3 | 2016-02-08 |
| 7730113 | 30 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730114 | 30A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730116 | 31 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730117 | 31A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730112 | 32 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730115 | 34 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730110 | 35 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730111 | 35 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730121 | 38 | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.5 ± 0.3 | 2016-02-08 |
| 7730143 | 4 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730144 | 5 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |
| 7730145 | 6 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730157 | 7 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730156 | 8 | 2016-02-01 @ 10:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730155 | 9 | @ | @ | | |
| 7730122 | GYM | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.7 ± 0.3 | 2016-02-08 |
| 7730123 | GYM | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730124 | GYM A | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | < 0.3 | 2016-02-08 |
| 7730120 | TVA | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.8 ± 0.3 | 2016-02-08 |
| 7730119 | TVB | 2016-02-01 @ 9:00 am | 2016-02-04 @ 7:00 am | 0.6 ± 0.3 | 2016-02-08 |

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|---------|---------|----------------------|-----------------------|-------|------------|
| 7734937 | 1 | 2016-02-19 @ 3:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734946 | 10 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734955 | 11 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734956 | 12 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734959 | 13 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734930 | 14 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734953 | 15 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734954 | 16 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734940 | 17 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734949 | 18 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734948 | 19 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734939 | 2 | 2016-02-19 @ 3:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734942 | 20 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734929 | 21 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734933 | 22 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734934 | 23 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734936 | 24 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734943 | 25 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734944 | 26 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734935 | 27 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734928 | 28 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734952 | 29 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734947 | 3 | 2016-02-19 @ 3:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734931 | 30 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734932 | 31 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7718520 | 32 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7718523 | 33 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7718522 | 34 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7718521 | 35 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734945 | 4 | 2016-02-19 @ 3:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734960 | 5 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734958 | 6 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734951 | 7 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734957 | 8 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |
| 7734938 | 9 | 2016-02-19 @ 4:00 pm | 2016-02-22 @ 11:00 am | < 0.3 | 2016-02-23 |

February
15,
2016

**** LABORATORY ANALYSIS
REPORT ****

Spike Sample Laboratory Results

Radon test result report for:
MCPS

| Kit # | Room Id | Started | Ended | pCi/L | Analyzed |
|---------|---------|----------------------|----------------------|-----------|------------|
| 7718273 | 101A | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.5 ± 0.6 | 2016-02-04 |
| 7718281 | 102B | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.4 ± 0.6 | 2016-02-04 |
| 7718282 | 103C | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.3 ± 0.6 | 2016-02-04 |
| 7718288 | 104D | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.7 ± 0.6 | 2016-02-04 |
| 7718289 | 105E | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.6 ± 0.6 | 2016-02-04 |
| 7718291 | 106F | 2016-01-30 @ 9:00 am | 2016-02-01 @ 9:00 am | 6.5 ± 0.6 | 2016-02-04 |

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCF Technologies Inc. Job Number 173704

NOMINAL Conditions: Radon Conc 5.9 pCi/L Rel. Hum 45.9 % Temp. 79.0 F

Date Start: 11/30/16 Date Stop: 2/1/17

Date Start: _____ Date Stop: _____

Time Start: 0926 Time Stop: 0926

Time Start: _____ Time Stop: _____

Device No.'s: (6) Char. Bags -

Device No.'s: _____

7718281, 7718282, 7718291,

7718288, 7718289, 7718273

3 Left

Date Start: _____ Date Stop: _____

Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____

Time Start: _____ Time Stop: _____

Device No.'s: _____

Device No.'s: _____

Date Start: _____ Date Stop: _____

Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____

Time Start: _____ Time Stop: _____

Device No.'s: _____

Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft



Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 7 (2-1-2016)

Name of School/Facility:

- | | | |
|----------------------------|-----------------------------|----------------------------|
| 1. Wyngate E.S. | 10. Bethesda Depot | 18. Stone Mill E.S. |
| 2. Seven Locks E.S. | 11. Bethesda Trans Depot | 19. Strawberry Knoll E.S. |
| 3. Takoma Park M.S. | 12. Sligo M.S. | 20. Shady Grove M.S. |
| 4. Somerset E.S. | 13. Stonegate E.S. | 21. Washington Grove E.S. |
| 5. Silver Spring Int. M.S. | 14. Randolph Transportation | 22. Sherwood E.S. |
| 6. Sligo Creek E.S. | 15. Earl B. Wood M.S. | 23. Woodfield E.S. |
| 7. Tilden M.S. | 16. Sargent Shriver E.S. | 24. Taylor Learning Center |
| 8. Tilden Center | 17. Thomas Wooten H.S. | 25. Kingsley Wilderness |
| 9. Bethesda Annex | | |

| | Date | Initials |
|----------------------------------|--------|----------|
| Radon Test Kits Deployed | 2/1/16 | JM |
| Radon Test Kits Collected | 2/4/16 | JM |
| Radon Test Kits Shipped to Lab* | 2/4/16 | JM |
| Radon Test Kits Received by Lab* | 2/8/16 | JM |

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 7 (2-2-2016)

Name of School/Facility:

- | | |
|--------------------------------|--------------------------------|
| 1. Concord Center | 8. Food & Nutritional Services |
| 2. Lynnbrook Center | 9. Fairland Center |
| 3. Carver (CESC) | 10. Redland M.S. (retest) |
| 4. Spring Mill (area 1 Office) | 11. Clarksburg Trans Depot |
| 5. Wheaton H.S | 12. Clarksburg Main Depot |
| 6. Montrose Center | 13. Clarksburg E.S. |
| 7. West Farm Trans Depot | |

| | Date | Initials |
|----------------------------------|--------|----------|
| Radon Test Kits Deployed | 2/2/16 | JM |
| Radon Test Kits Collected | 2/5/16 | JM |
| Radon Test Kits Shipped to Lab* | 2/5/16 | JM |
| Radon Test Kits Received by Lab* | 2/9/16 | JM |

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759