

School / Facility Radon Testing Report Form

School Year: 24-25

Facility:	Westlar	Westland Middle School			
Address	5511 M	5511 Massachusetts Avenue			
Address:	Bethesd	Bethesda, MD 20816			
	·	Scheduled Re-Testing - 🛛 2-year or 🗌 5-year schedule			
Boscon for T	octing	Clearance Testing (Post-Mitigation)			
Reason for Testing:		Building Envelope or HVAC Upgrades			
		New Construction – Addition or Facility			
		Active Mitigation (2-year regular schedule)			
Current Rador	n Status:	No Active Mitigation (5-year regular schedule)			
		Not Previously Tested (New Facility)			
Round of Testing:		□ Initial Testing -or- ☑ Follow-up Testing			
Testing Status:		☑ No Further Testing Needed - or - □ Follow-Up Testing Required			

Conclusion (When Testing Status is - No Further Testing Needed)

Mitigation -	Facility Radon Status:		
□ Not Required	🛛 No Change in Status		
Required (≥4.0-pCi/L)	Active Mitigation (2-year regular schedule)		
Rooms: 100E; 100F	□ No Active Mitigation (5-year regular schedule)		
Number of Rooms Tested	59	Lowest Value (pCi/L)	< 0.3
Number of Rooms (≥4.0-pCi/L)	2	Highest Value (pCi/L)	11.9

Instructions: Submit one testing report form per-facility. Include the following as attachments:

Attachment 1- Summary Data Tables – containing the following: (see attached samples tables)

- Testing Results lab/detector Identification, by room number/name (alpha-numeric order) as depicted on facility map/floor plan provided by the facility/school at the time of test device deployment;
- Summary Results list of rooms by test result ≥2.0-pCi/L; ≥2.7-pCi/L; ≥4.0-pCi/L; and ≥8.0-pCi/L;
- QA/QC Results (field blanks and duplicates) indicating location collected; trip and office blanks; and spike sample results;
- Invalid Measurement Locations missed locations, missing and or damaged/compromised testing devices.

Attachment 2 – Laboratory Report(s)

Attachment 3 – Sampling Location Map(s) – indicating approximate location of samples, duplicates and blanks.



Detector and Deployment

Detector/Device Type:	 ☑ Passive ☑ Charcoal Absorption (CAD) ☑ Alpha Track (ATD) ☑ Other ☑ Continuous ☑ Electret ion Chamber (EIC) ☑ Electronic Integration (EID) <i>Other-Specify here:</i> 					
Detector/Device Name:	Air Chek – Radon T	Air Chek – Radon Test Kits				
Manufacturer:	Radon Lab					
Person(s) Deploying or Retrieving Test Devices a certification number		est Devices and	Organization/Company			
Shannon King			KCI Technologies, Inc.			
If noncertified individuals, the qualified measurement professional providing oversight -						
Tyler McCleaf, CSP – Cert. #111004 – RMP		MP	KCI Technologies, Inc.			

Testing

Short-Term	Length of	2	Date of Deployment and	02/04/25	03/24/25	
Long-Term	Test (days):	5	Retrieval (mm/dd/yy):	02/07/25	03/27/25	
Does the test pe	hool breaks or holidays?	🗆 Yes 🛛	🛛 No			
If " Yes " please explo	ain/detail in the s	pace below:				
Was HVAC opera	Was HVAC operating under occupied conditions?					
If " No " please explain/detail in the space below:						



Testing (continued)

	Detectors Deployed				
	Ground-Contact		Upper-Level(s)		Tabal
Round of Testing	Initial	Initial Follow-Up		Follow-Up	Iotal
Test Locations ¹	54	4	3	0	61
Duplicates ²	6	1	1	0	8
Field Blanks ³	3	1	0	0	4
Grand Total		73			

1 – include all detectors deployed (duplicates, field blanks); 1 detector per occupied (or intended to be occupied) ground-contact space \leq 2,000-square feet; large spaces \geq 2,000-square feet - 1 detector per 2,000-square feet or part thereof); and upper floors - 10% of all occupied or intended to be occupied rooms <u>per floor</u> (these are in addition to ground contact locations)

2 - 10% of all locations tested, per floor

3 – 5% of all locations tested, per floor

Quality Assurance / Quality Control (QA/QC)

A Quality Assurance plan that is consistent with ANSI/AARST MS-QA (Radon Measurement Systems Quality Assurance) was submitted under separate cover, and is available to review at the MCPS Radon Testing and Mitigation Program website. The following number of QA/QC samples are associated this facility.

	QA/QC Samples Initial Follow-Up		Total
Round of Testing			TOLAI
Spikes ¹	Not applicable		10
Trip Blanks ²	1	1	2
Office Blanks ^{3, 4}	1 1		2
			14

1 - 3% of EIC detectors; and 3% from <u>each LOT</u> of CAD and ATD detectors; a <u>maximum of 6-spiked</u> <u>measurements</u> per month for both EIC detectors and <u>each LOT</u> of CAD and ATD detectors.

2 - One per shipping container from start of detector deployment

3 – One per facility tested as devices are removed/allocated from the storage location for deployment;

4 - One additional blank, <u>analyzed prior to deployment</u>, for storage locations that have not been evaluated or monitored, for detectors that have been stored for more than 30-day durations.



Quality Assurance / Quality Control (continued)

Spike Sample Lab Results. Measured values are satisfactory, i.e., within ± 25% of the chamber's reference value?	🛛 Yes 🗌 No	
Quality Control measurements comply with QA/QC requirements in the submitted testing organization's/company's QA plan?		🗆 No
Round of Testing	Initial	Follow-Up
All Field, Trip and Office Blanks are ≤ (less than or equal to)	🛛 Yes	🛛 Yes
to the Method Detection Limit?	🗆 No	🗆 No
For all Duralizate Consults 1 the bighter value is $\mathbf{z} = \mathbf{z}$ with a larger value 2		🛛 Yes
For all Duplicate samples, the figher value is 2 2x the lower value?	🗌 No	🗌 No
For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are	🛛 Yes	🛛 Yes
less than the Warning Level ³ ?	🗆 No	🗆 No
For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are	🛛 Yes	🛛 Yes
less than the Control Level ³ ?	🗆 No	🗆 No

1 – Duplicate Control – a "NO" response constitute a control failure and the space/location represented by the duplicate sample becomes an invalid measurement location and should be listed in the "Invalid Measurement Locations" Table attached to this report.

2 - The objective of duplicate tests is to assess the precision error of the measurement method or, how well two side-by-side measurements agree or disagree. Precision involving duplicates is calculated by using Relative Percent Difference (RPD). RPD is equal to the difference between the higher test result minus the lower value test result divided by the average of the two duplicate test results, multiplied by 100. The RPD result is then compared to the warning and control limits.

3 - The Warning Level is set at the deviation from ideal performance that would be expected to occur by chance only 5% of the time, and Control Limits are set at that deviation from ideal performance that would be expected to occur by chance only 1% of the time. The Warning Level indicates a potential problem, which should be investigated. The Control Level indicates that the measurement system should be subject to corrective action.

The control and warning levels for duplicates, based on the averaged duplicate test result, are -

Average concentration of the two duplicate test results	Warning Level	Control Level
< 2.0-pCi/L	1-pCi/L	Not applicable
Between 2.0 and 3.9-pCi/L	50% RPD	67% RPD
≥ 4.0-pCi/L	28% RPD	36% RPD





	Ground-Contact		Upper-Level(s)		Total	
Round of Testing	Initial	Follow-Up	Initial	Follow-Up	lotai	
Number of test locations:	54	2	3	0	59	
Number of locations ≥8.0-pCi/L:	1	0	0	0	1	
Number of locations ≥4.0 and ≤8-pCi/L:	1	1	0	0	2	
Number of locations ≥2.7 and <4-pCi/L:	2	1	0	0	3	
Number of locations ≥2.0 and <2.7-pCi/L:	5	0	0	0	5	
Number of missing required test locations ³ :	1	0	0	0	1	
Number of failed duplicate control locations:	0	0	0	0	0	
Percentage of missing test locations for the facility ^{4,5} :	1.85%	0	0	0	1.69%	

Summary of Test Results¹ and Determination of Valid Measurements²

1 – for locations with multiple test results, report consistent with Section 7.2(When Two Test Results Disagree) and 8.1.2 (Averaging) of ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings;

2 - the allowance is to be calculated individually for Ground-Contact and Upper-Level(s) Test Locations;

3 – includes missed or inaccessible locations upon deployment or retrieval, damaged (not able to analyze) and missing detectors upon retrieval;

4 – if all valid measurements are <4.0-pCi/L and the total number of test locations are \geq 18, there is an allowance of \leq 33%. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023;

5 – if any valid measurements are \geq 4.0-pCi/L and the total number of test locations are \geq 20, there is an allowance of \leq 25% of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023.



Summary of Test Results¹ and Determination of Valid Measurements² (continued)

Round of Testing	Initial	Follow-Up
Were test devices deployed in all occupied and intended to be occupied rooms in	🛛 Yes	🛛 Yes
contact with the ground, and, if applicable, 10% of upper floor rooms?	🗆 No	🗆 No
Were valid measurements obtained in all occupied and intended to be occupied	🗌 Yes	🗌 Yes
rooms in contact with the ground, and, if applicable, 10% of upper floor rooms?	🛛 No	🛛 No
If Yes to both above – then Testing Status – 'No Further Testing Needed' mark 'NA' below and complete Conclusions section		
If No to either above, were all results obtained under 4.0-pCi/L and	🗆 Yes	🗆 Yes
were sufficient valid measurements obtained? ^{1,2}	🛛 No	🛛 No
If No, then - 'Follow-up Testing Required' continue below.	🗆 NA	🗆 NA

1 – if all valid measurements are <4.0-pCi/L and the total number of test locations are ≥18, there is an allowance of ≤33%. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the allowance; 2 – if any valid measurements are ≥4.0-pCi/L and the total number of test locations are ≥20, there is an allowance of ≤25% of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the allowance of ≤25% of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the allowance.

Follow-Up Testing

Required –

- If an insufficient number (greater than the allowance provided above) of valid measurements were obtained during the initial round of testing (the "missing required test locations" in the table above);
- Any location test results \geq 4.0-pCi/L;
- Any location where duplicates fail QC checks; and or
- At the discretion of MCPS IAQ Staff

Reason for Follow-Up Testing	Testing Procedure	Follow-up Result	Conclusion
Insufficient Number of	Follow same procedures as Initial	Not	Follow Initial Testing
Measurements	Testing	Applicable	procedures
Results ≥ 4.0-pCi/L	Deploy two Short-term follow-up	≥4.0	Mitigation Required
	tests and required blanks and	≥2.0 and <4.0	Consider Mitigation
Failed QC checks	duplicates; Average the results of the	<2.0	Mitigation Not
	two tests	<2.0	Required

If follow-up testing identifies additional spaces requiring additional testing it will be performed as part of the ongoing follow-testing round.

Attachment 1: Summary Data Tables

Table 1- Radon Testing Results					
	Westland Middle School				
1	Test Period: 2/4/2025 - 2/7/202	5			
Kit Number	Room / Area	Result			
11931429	101	2.6			
11931402	102	1.9			
11931481	108	< 0.3			
11931477	108	0.7			
11931462	109	0.7			
11931476	109	0.8			
11931473	110	0.6			
11931474	111	1.0			
11931471	112	< 0.3			
11931468	112	< 0.3			
11931461	113	1.1			
11931467	114	< 0.3			
11931472	115	< 0.3			
11931463	116	< 0.3			
11931466	117	< 0.3			
11931460	118	< 0.3			
11931464	119	< 0.3			
11931465	121	0.6			
11931458	125	1.3			
11931459	125	< 0.3			
11931456	127	0.7			
11931454	127	1.2			
11931479	128	< 0.3			
11931451	129	1.0			
11931452	130	1.2			
11931448	131	< 0.3			
11931447	133	1.5			
11931438	135	< 0.3			
11931443	137	< 0.3			
11931445	138	< 0.3			
11931446	138	< 0.3			
11931442	139	1.0			
11931450	140	< 0.3			
11931444	142	< 0.3			
11931439	148	0.5			
11931440	148	< 0.3			
11931430	149	1.3			

Table 1- Radon Testing Results								
Westland Middle School								
Test Period: 2/4/2025 - 2/7/2025								
Kit Number	Room / Area	Result						
11931436	11931436 149							
11931478	152	1.3						
11931482	205	1.0						
11931480	214	1.0						
11931483	225	0.6						
11931484	225	< 0.3						
11931421	100A	1.4						
11931417	100B	1.4						
11931422	100C	1.0						
11931418	100D	3.9						
11931423	100E	3.0						
11931424	100F	1.1						
11931426	100H	1.6						
11931427	101B	2.1						
11931428	101B	2.1						
11931431	101C	1.6						
11931432	101D	3.9						
11931433	101E	11.9						
11931435	101F	4.8						
11931453	130A	0.7						
11931457	130B	0.9						
11931449	130C	2.3						
11931455	130C	1.0						
11931441	BOYS LOCKER ROOM	1.0						
11931469	CAFETERIA	0.9						
11931470	CAFETERIA	< 0.3						
11931434	CALM ROOM	2.4						
11931437	GIRLS LOCKER ROOM	2.1						
11931416	MAIN OFFICE	1.0						
11931475	STAGE	< 0.3						

Table 2 - Summary Testing Results ≥2.0 pCi/L								
Westland Middle School								
		Test P	eriod: 2/4/2	025 - 2/7/2025				
≥2.0 and <2.7	pCi/L	≥2.7 and <4	.0 pCi/L	≥4.0 and <8	3.0 pCi/l	≥8.0 p0	Ci/L	
Room / Area	Result	Room / Area	Result	Room / Area	Result	Room / Area	Result	
101B	2.1	100E	3.0	101F	4.8	101E	11.9	
101B	2.1	100D	3.9					
Girls Locker Room	2.1	101D	3.9					
130C	2.3							
Calm Room	2.4							
101	2.6							

Table 3 - QC Radon Testing Results									
	Westland Middle School								
Т	est Period:	2/4/2025 - 2/7/2025							
Kit Number QC Type Room / Area Result									
11931477	FB	108	0.7						
11931476	D	109	0.8						
11931468	D	112	< 0.3						
11931459	FB	125	< 0.3						
11931454	D	127	1.2						
11931446	D	138	< 0.3						
11931440	FB	148	< 0.3						
11931436	D	149	1.7						
11931484	D	225	< 0.3						
11931428	D	101B	2.1						
11931544	OB	OFFICE BLANK	< 0.3						
11931543	TB	TRAVEL BLANK	< 0.3						

			Tab	ole 3a - Du	plicate Work	sheet / Dat	a Validation			
	Westland Middle School									
				Test	Period: 2/4/2	2025 - 2/7/2	025			
	Sample	D			Dup	licate Cond	centrations (p	oCi/L) and C	C Checks	
Kit Nı	umbers	Room / Area	Higher	Lower	Check #1 (Pass/Fail)	2x the Lower	Check #2 (Pass/Fail)	Average	Relative Percent Difference (RPD)	Check #3
11931427	11931428	101B	2.1	2.1	V	4.2	PASS	2.1	0.0%	V
11931430	11931436	149	1.7	1.3	V	2.6	PASS	1.5	<1-pCi/L	~
11931445	11931446	138	0.3	0.3	V	0.6	PASS	0.3	<1-pCi/L	~
11931456	11931454	127	1.2	0.7	V	1.4	PASS	1.0	<1-pCi/L	~
11931471	11931468	112	0.3	0.3	V	0.6	PASS	0.3	<1-pCi/L	~
11931462	11931476	109	0.8	0.7	V	1.4	PASS	0.8	<1-pCi/L	~
11931483	11931484	225	0.6	0.3	\checkmark	0.6	PASS	0.5	<1-pCi/L	>
NOTES:	OTES:						Average	(pCi/L)	Warning Level	Control Level
QC Check #	QC Check #1 - Data Entry					< 2.0 1-pCi/L N		NA		
QC Check #	2 - Higher dup	licate concentration	is < or = to	2x the Lo	wer		Between 2.0 and 3.9 50% RPD 67% RPD			67% RPD

≥ 4.0

28% RPD

36% RPD

QC Check #2 - Higher duplicate concentration is < or = to 2x the Lower

QC Check #3 - Meets RPD Limits, by average duplicate concentration

- enter 2 if RPD is BELOW warning and control levels, AND passes QC Check 1 and 2

- enter 1 if RPD is ABOVE warning and BELOW control levels, AND passes QC Check 1 and 2

- enter 0 if RPD is ABOVE control level, or 'FAILS' QC Check 1 or 2

Table 4 - Summary of Invalid Measurement Locations									
Westland Middle School									
Tes	t Period: 2/4/25	- 2/7/25							
Kit Number	Room/Area	Reason							
11931425	100G	Missing Kit							

Table 1- Radon Testing Results								
	Westland Middle School RT							
Te	Test Period: 3/24/2025 - 3/27/2025							
Kit Number Room / Area Result								
11887237	11887237 101F							
11887238	101E	3.9						
11887244	101E	3.9						
11887249	101F	7.6						
11887250	11887250 101F 7.4							
11887251	101F	7.3						

	Table 2 - Summary Testing Results ≥2.0 pCi/L								
	Westland Middle School RT								
		Tes	st Period: 3/24	4/2025 - 3/27/202	25				
≥2.0 and <	<2.7 pCi/L	≥2.7 and <	4.0 pCi/L	≥4.0 and <	<8.0 pCi/l	≥8.0	oCi/L		
Room / Area	Result	Room / Area	Result	Room / Area	Result	Room / Area	Result		
N/A	N/A	101E	3.9	101F	7.3	N/A	N/A		
		101E	3.9	101F	7.4				
				101F	7.6				

Table 3 - QC Radon Testing Results								
	Westlan	d Middle School RT						
	Test Period	d: 3/24/2025 - 3/27/2025						
Kit Number	Room / Area	Result						
11887251	D	101F	7.3					
11887237	FB	101F	< 0.3					
11886664	OB	OFFICE BLANK	< 0.3					
11886691	TB	TRAVEL BLANK	< 0.3					

	Table 3a - Duplicate Worksheet / Data Validation									
				Whea	aton High Sc	hool RT				
				Test Peri	od: 3/25/202	5 - 3/28/202	5			
	Samp	ile ID			Dup	licate Conc	entrations (p	Ci/L) and O	C Checks	
Kit Nı	umbers	Room / Area	Higher	Lower	Check #1 (Pass/Fail)	2x the Lower	Check #2 (Pass/Fail)	Average	Relative Percent Difference (RPD)	Check #3
11886561	11886669 11886670	1709	0.3	0.3	~	0.6	PASS	0.3	<1-pCi/L	v
NOTES:			_				Average	(pCi/L)	Warning Level	Control Level
QC Check #	QC Check #1 - Data Entry					< 2	< 2.0 1-pCi/L		NA	
QC Check #	2 - Higher dup	licate concentration is < or	r = to 2x the	Lower			Between 2	Between 2.0 and 3.9 50% RPD 67% RF		
QC Check #	3 - Meets RPD	Limits, by average duplic	ate concen	tration			≥ 4	≥ 4.0 28% RP		36% RPD

- enter 2 if RPD is BELOW warning and control levels, AND passes QC Check 1 and 2

- enter 1 if RPD is ABOVE warning and BELOW control levels, AND passes QC Check 1 and 2

- enter 0 if RPD is ABOVE control level, or 'FAILS' QC Check 1 or 2

Table 4 - Summary of Invalid Measurement Locations									
Westland Middle School RT									
Test Period: 3/25/25 - 3/28/25									
Kit Number	Room/Area	Reason							
N/A	N/A	N/A							

Attachment 2: Laboratory Reports

February 11, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11931421	100A	2025-02-04 @ 9:00 am	2025-02-07 @ 8:00 am	1.4 ± 0.4	2025-02-11
11931417	100B	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.4 ± 0.4	2025-02-11
11931422	100C	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11
11931418	100D	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	3.9 ± 0.4	2025-02-11
11931423	100E	2025-02-04 @ 9:00 am	2025-02-07 @ 10:00 am	3.0 ± 0.4	2025-02-11
11931424	100F	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.1 ± 0.3	2025-02-11
11931426	100H	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.6 ± 0.4	2025-02-11
11931429	101	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	2.6 ± 0.4	2025-02-11
11931427	101B	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	2.1 ± 0.4	2025-02-11
11931428	101B	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	2.1 ± 0.4	2025-02-11
11931431	101C	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.6 ± 0.4	2025-02-11
11931432	101D	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	3.9 ± 0.4	2025-02-11
11931433	101E	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	11.9 ± 1.0	2025-02-11
11931435	101F	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	4.8 ± 0.4	2025-02-11
11931402	102	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.9 ± 0.4	2025-02-11
11931481	108	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.7 ± 0.3	2025-02-11
11931477	108	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931476	109	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.8 ± 0.4	2025-02-11
11931462	109	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.7 ± 0.3	2025-02-11
11931473	110	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.6 ± 0.3	2025-02-11
11931474	111	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11
11931468	112	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931471	112	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931461	113	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.1 ± 0.4	2025-02-11
11931467	114	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931472	115	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931463	116	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931466	117	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931460	118	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931464	119	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931465	121	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.6 ± 0.3	2025-02-11
11931459	125	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931458	125	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.3 ± 0.3	2025-02-11
11931454	127	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.7 ± 0.3	2025-02-11
11931456	127	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.2 ± 0.4	2025-02-11
11931479	128	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931451	129	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11931452	130	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.2 ± 0.4	2025-02-11
11931453	130A	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.7 ± 0.3	2025-02-11
11931457	130B	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.9 ± 0.4	2025-02-11
11931449	130C	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	2.3 ± 0.4	2025-02-11
11931455	130C	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11
11931448	131	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931447	133	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.5 ± 0.3	2025-02-11
11931438	135	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931443	137	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931446	138	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931445	138	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931442	139	2025-02-04 @ 10:00 am	2025-02-07 @ 10:00 am	1.0 ± 0.3	2025-02-11
11931450	140	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931444	142	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931440	148	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931439	148	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	0.5 ± 0.3	2025-02-11
11931430	149	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.3 ± 0.4	2025-02-11
11931436	149	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.7 ± 0.4	2025-02-11
11931478	152	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	1.3 ± 0.4	2025-02-11
11931482	205	2025-02-04 @ 11:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.4	2025-02-11
11931480	214	2025-02-04 @ 11:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11
11931483	225	2025-02-04 @ 11:00 am	2025-02-07 @ 9:00 am	0.6 ± 0.3	2025-02-11
11931484	225	2025-02-04 @ 11:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931441	BLR	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	1.0 ± 0.3	2025-02-11
11931470	CAFETERIA	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11
11931469	CAFETERIA	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	0.9 ± 0.4	2025-02-11
11931434	CALM ROOM	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	2.4 ± 0.4	2025-02-11
11931437	GLR	2025-02-04 @ 9:00 am	2025-02-07 @ 9:00 am	2.1 ± 0.4	2025-02-11
11931416	MAIN OFFICE	2025-02-04 @ 9:00 am	2025-02-07 @ 8:00 am	1.0 ± 0.4	2025-02-11
11931475	STAGE	2025-02-04 @ 10:00 am	2025-02-07 @ 9:00 am	< 0.3	2025-02-11

Radon test result report for: OFFICE MAIN

	Perm	Anaryzeu
0 am 2025-02-07 @ 11:00 am	< 0.3	2025-02-11
() am 2025-02-07 @ 11:00 am) am 2025-02-07 @ 11:00 am < 0.3

Radon test result report for: TRAVEL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11931543	Т	2025-02-04 @ 11:00 am	2025-02-07 @ 11:00 am	< 0.3	2025-02-11

EM OSORE IN DOWSER-IN	IUNITER RADUN CHAMBER
CLIENT KCI TECHNOLOGIES	Job Number 2000 1560
NOMINAL Conditions: Radon Conc 50.6	pCi/L Rel. Hum <u>50.6</u> % Temp. <u>70.8</u>
Date Start: 12/14/24 Date Stop: 13/17/24	Date Start: Date Stop:
Time Start: 0815 Time Stop: 0815	Time Start: Time Stop:
Device No.'s 3 CHAR BAGS	Device No.'s:
11477880, 11477883, 11477896	
By Right	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

Radon test result report for: SK MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11477880	SK1	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	52.0 ± 4.2	2024-12-23
11477883	SK2	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	54.6 ± 4.4	2024-12-23
11477896	SK3	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	45.5 ± 3.6	2024-12-23



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Testing February 4th – February 7th, 2025

Name of Schools:

- 1. Candlewood ES
- 2. Viers Mill ES
- 3. Wayside ES
- 4. Julius West MS
- 5. Westland MS

	Date	Initials
Radon Test Kits Deployed	2/4/2025	GN
Radon Test Kits Collected	2/7/2025	m
Radon Test Kits Shipped to Lab*	2/7/2025	Em
Radon Test Kits Received by Lab*	2/10/2025	(M

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835

April 2, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11887238	101E	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	3.9 ± 0.7	2025-04-02
11887244	101E	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	3.9 ± 0.6	2025-04-02
11887237	101F	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	< 0.3	2025-04-02
11887249	101F	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	7.6 ± 0.9	2025-04-02
11887250	101F	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	7.4 ± 0.8	2025-04-02
11887251	101F	2025-03-24 @ 8:00 am	2025-03-27 @ 12:00 pm	7.3 ± 0.8	2025-04-02

Radon test result report for: OFFICE MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11886664	OB	2025-03-24 @ 11:00 am	2025-03-27 @ 11:00 am	< 0.3	2025-04-02
11886692	OB	2025-03-25 @ 11:00 am	2025-03-28 @ 11:00 am	< 0.3	2025-04-02
11951800	OB	2025-03-24 @ 11:00 am	2025-03-28 @ 11:00 am	< 0.3	2025-04-02
11951800	OB	2023-03-24 @ 11.00 alli	2025-05-20 @ 11.00 alli	< 0.5	2023-

Radon test result report for: TRAVEL MAIN

11886691 TB 2025-03-24 @ 11:00 am 2025-03-27 @ 1	1:00 am < 0.3 2025-04-02
11886693 TB 2025-03-25 @ 11:00 am 2025-03-28 @ 1	1:00 am < 0.3 2025-04-02
11892493 TB 2025-03-24 @ 11:00 am 2025-03-28 @ 1	1:00 am < 0.3 2025-04-02

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGIC	5. INC Job Number 2000 2919
NOMINAL Conditions: Radon Conc 7.0	pCi/L Rel. Hum 51.4 % Temp. 79.7 F
Date Start: 3/1/23 Date Stop: 3/10/2	Date Start: Date Stop:
Time Start: 0833 Time Stop: 0833	Time Start: Time Stop:
Device No.'s: (7) CHAR BAGS	Device No.'s:
11886401 thru 11886406,	
11886410	
G3 Right	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

Radon test result report for: QC MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11886401	SK1	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.8 ± 1.1	2025-03-19
11886405	SK2	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.1 ± 1.1	2025-03-19
11886406	SK3	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.7 ± 1.1	2025-03-19
11886403	SK4	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.9 ± 1.2	2025-03-19
11886404	SK5	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.6 ± 1.2	2025-03-19
11886410	SK6	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	7.0 ± 1.1	2025-03-19
11886402	SK7	2025-03-07 @ 9:00 am	2025-03-10 @ 9:00 am	8.6 ± 1.2	2025-03-19



 ENGINEERS
 PLANNERS
 SCIENTISTS
 CONSTRUCTION
 MANAGERS

 Corporate Office:
 936 Ridgebrook road
 • Sparks , Maryland
 21152
 • 410-316-7800
 • (Fax)
 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Testing March 24th – March 27th, 2025

Name of Schools:

- 1. Beverly Farms ES
- 2. Bradley Hills ES
- 3. Cabin John MS
- 4. Springbrook HS
- 5. Thomas Edison HS
- 6. Walter Johnson HS

- 7. Julius West MS
- 8. Parkland MS
- 9. Rockville HS
- **10.Westland MS**
- 11. Charles W. Woodward HS
- 12. Walt Whitman HS

	Date	Initials
Radon Test Kits Deployed	3/24/2025	BIHU
Radon Test Kits Collected	3/27/2025	BIHM
Radon Test Kits Shipped to Lab*	3/28/2025	BAHU
Radon Test Kits Received by Lab*	4/01/2025	YUNHU

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Westland Middle School Site Name Date of Test Report 05/12/2022 Round of Testing Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility # Rooms Tested 1 $\# \text{Rooms} \ge 4.0 \text{ pCi/L}$ 0 Lowest Value <0.3 pCi/L Highest Value 0.7 pCi/L

MCPS RADON TESTING – EXECUTIVE SUMMARY

Project Status

Current Project Status at this time: Testing completed; no further action needed



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

May 12, 2022

Mr. Brian Croyle, PG, CHMM Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re:	Radon Testing Services
	KCI Job # 122108316

Location: Westland Middle School 5511 Massachusetts Ave. Bethesda, MD 20816

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Westland Middle School, located at 5511 Massachusetts Ave. Bethesda, MD 20816 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on March 21, 2022 and deployed three (3) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

- 1. Rooms with missing test kits from the Radon 2022 testing period (i.e. test kit was deployed but not recovered),
- 2. Rooms with invalidated test kits from the Radon 2022 testing period (e.g. an open window in the room or disturbed test kit),
- 3. Rooms which were locked/inaccessible during the Radon 2022 testing period,
- 4. Rooms with elevated radon results (i.e. \geq 3.5 piC/L),
- 5. Rooms previously tested for radon but not tested in Radon 2022, and
- 6. Additional rooms that require testing (if applicable.)

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 24, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the low 40°Fs and high temperatures ranged from the low 50°Fs to the low 70°Fs. Maximum sustained winds ranged from 0-29 miles per hour. Average humidity was around 56% with 0.51 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples		
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of	
	less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
	adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is	
	operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler McCleaf

Tyler P. McCleaf Radon Measurement Provider #111004 RT KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations B- Table 1-3, Radon Test Summary Spreadsheets C- Laboratory Analytical Results
ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal ACI- Air Check, Inc. D- Duplicate FB- Field Blank KCI- KCI Technologies, Inc. OB- Office Blank PM- Project Manager OC- Quality Control

Table 1- Radon Testing Results			
	Westland MS RT		
Te	est Period: 03/21/2022 - 03/24/2022		
Kit Number	Room / Area	Result	
11139263	152	< 0.3	
11139264	152	< 0.3	
11139265	152	0.7	

Table 2- Radon Testing Results			
	Westlar	nd MS RT	
	Test Period: 03/21,	/2022 - 03/24/2022	
Kit Number	QC Type	Room / Area	Result
11139263	D	152	
11139264	FB	152	
11139902	OB	OFFICE BLANK	< 0.3
11139928	ТВ	TRAVEL BLANK	< 0.3

Summary of Missed Locations		
Westland MS RT		
Т	est Period: 03/21/22 - 03/24/22	
Kit Number	Room/Area	Result
	NA	

Summary of Missing, Compromised and >/= 4 piC/L Tests		
Westland MS RT		
Test Period: 03/21/22 - 03/24/22		
Kit Number	Room/Area	Result
	NA	

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: Westland MS RT

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139263	152	2022-03-21 @ 9:00 am	2022-03-24 @ 8:00 am	< 0.3	2022-03-28
11139264	152	2022-03-21 @ 9:00 am	2022-03-24 @ 8:00 am	< 0.3	2022-03-28
11139265	152	2022-03-21 @ 9:00 am	2022-03-24 @ 8:00 am	0.7	2022-03-28

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, I	Job N	umber 204620
NOMINAL Conditions: Radon Conc 27.0 p	Ci/L Rel. Hum 50, 1	_% Temp. <u>70.0</u> F
Date Start: 3/18/22 Date Stop: 3/21/22	Date Start:	Date Stop:
Time Start: 0705 Time Stop: 0705	Time Start:	Time Stop:
Device No.'s: (5) Char Bags-	Device No.'s:	
11139367, 11139368, 11139371,		
11139710, 11139717		е
E3 Right	· · · · · · · · · · · · · · · · · · ·	
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	
	·	fi .
8 4 2		, m
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	_ Time Stop:
Device No.'s:	Device No.'s:	
	2	

1

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139367	SK1	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.9 ± 2.1	2022-03-30
11139368	SK2	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	23.9 ± 2.0	2022-03-30
11139371	SK3	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.7 ± 2.1	2022-03-30
11139710	SK4	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	26.4 ± 2.1	2022-03-30
11139717	SK5	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	24.6 ± 2.0	2022-03-30



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – March 2022 Schools – Retesting

Name of Schools:

- 1. Rosa Parks MS
- 2. Poolesville ES
- 3. Wyngate ES
- 4. Seven Locks ES
- 5. Walt Whitman HS
- 6. Somerset ES
- 7. Rock Creek Forest ES
- 8. Walter Johnson HS
- 9. Westbrook ES
- **10.Westland MS**
- **11.Farmland ES**
- **12.College Gardens ES**
- 13.Julius West MS
- 14.Robert Frost MS
- **15.Carl Sandburg Learning Center**

	Date	Initials
Radon Test Kits Deployed	03/21/2022	13MM
Radon Test Kits Collected	03/24/2022	BMM
Radon Test Kits Shipped to Lab*	03/25/2022	BMM
Radon Test Kits Received by Lab*	03/28/2022	Bann

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Westland Middle
	School
Date of Test Report	2/21/2022
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	68
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	0.7 pCi/L

MCPS RADON TESTING – EXECUTIVE SUMMARY

Project Status: Initial testing completed; Missing or compromised samples need re-sampling



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 21, 2022

Brian T. Croyle, PG, CHMM Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re:	Radon Testing Services	
	KCI Job # 122108316	
Location:	Westland Middle School	
	5511 Massachusetts Ave.	
	Bethesda, MD 20816	

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Westland Middle School, located at 5511 Massachusetts Ave. Bethesda, MD 20816 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on January 18, 2022 and deployed seventy eight (78) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 21, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc.

Mr. Brian Croyle February 21, 2022 Page 3

is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

• Follow-up to post-mitigation biennial testing.

These tests were conducted to:

• Confirm the success of the mitigation system(s).

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 30s and high temperatures ranged from the mid 30s to the mid 40s Fahrenheit. Maximum sustained winds ranged from 7-20 miles per hour. Average humidity was around 50% with .05 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples		
Results of Blank Canisters: The office blanks, and lab transit blanks had test resu		
	less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
	adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory i	
	operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler McCleaf

Tyler P. McCleaf Radon Measurement Provider #111004 RT KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test LocationsB- Table 1-3, Radon Test Summary SpreadsheetsC- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal ACI- Air Check, Inc. D- Duplicate FB- Field Blank KCI- KCI Technologies, Inc. OB- Office Blank PM- Project Manager OC- Quality Control

Table 1- Radon Testing Results				
Westland MS				
1	est Period: 01/18/2022-01/21/2022			
Kit Number	Room / Area	Result		
11106627	101	< 0.3		
11106628	101	< 0.3		
11106630	102	< 0.3		
11106635	102	< 0.3		
11106675	108	< 0.3		
11106663	110	< 0.3		
11106672	111	< 0.3		
11106653	112	< 0.3		
11106664	113	< 0.3		
11106665	114	< 0.3		
11106654	115	< 0.3		
11106658	116	0.7		
11106666	117	< 0.3		
11106667	117	< 0.3		
11106660	118	< 0.3		
11106661	119	< 0.3		
11106662	119	< 0.3		
11106655	120	0.7		
11106656	120	< 0.3		
11106657	121	< 0.3		
11106646	125	< 0.3		
11106616	127	< 0.3		
11106648	128	< 0.3		
11106649	128	< 0.3		
11106608	129	< 0.3		
11106650	130	< 0.3		
11106652	130	< 0.3		
11106640	131	< 0.3		
11106647	133	< 0.3		
11106626	135	< 0.3		
11106632	136	< 0.3		
11106615	137	< 0.3		
11106623	137	< 0.3		
11106625	137	< 0.3		
11106633	138	< 0.3		
11106622	139	< 0.3		
11106637	139	< 0.3		
11106638	139	< 0.3		
11106634	140	< 0.3		
11106617	142	< 0.3		
11106643	148	< 0.3		
11106609	151	< 0.3		

Table 1- Radon Testing Results				
Westland MS				
7	Fest Period: 01/18/2022-01/21/2022			
Kit Number	Room / Area	Result		
11106677	203	< 0.3		
11106678	210	< 0.3		
11106670	214	0.7		
11106669	221	< 0.3		
11106676	229	< 0.3		
11106612	100 MAIN OFFICE	< 0.3		
11106619	100B	< 0.3		
11106611	100C	< 0.3		
11106604	100D	< 0.3		
11106605	100E	< 0.3		
11106620	100F	< 0.3		
11106618	100G	< 0.3		
11106613	100H	< 0.3		
11106603	101B	< 0.3		
11106606	101C	< 0.3		
11106610	101D	< 0.3		
11106636	101E	< 0.3		
11106629	101F	< 0.3		
11106659	118/116	0.6		
11106601	128A	< 0.3		
11106641	130 OFFICE	< 0.3		
11106642	130A	< 0.3		
11106602	130C	< 0.3		
11106607	130C	< 0.3		
11106631	130C	< 0.3		
11106624	130D	< 0.3		
11106639	131/133	< 0.3		
11106644	149 GYM	< 0.3		
11106645	149/GYM	< 0.3		
11106671	CAFETERIA	< 0.3		
11106673	CAFETERIA	< 0.3		
11106674	CAFETERIA	< 0.3		
11106668	CAFETERIA STAGE	< 0.3		
11106614	CALM ROOM	< 0.3		
11106621	EATING AREA OUTSIDE MAIN OFFICE	< 0.3		
11106682	KITCHEN	< 0.3		

Table 2- Radon Testing Results					
	Westland MS				
	Test Period: 01/1	18/22-01/21/22			
Kit Number	QC Type	Room / Area	Result		
11106628	D	101	< 0.3		
11106622	FB	130	< 0.3		
11106638	D	139	< 0.3		
11106615	D	137	< 0.3		
11106631	FB	130c	< 0.3		
11106602	D	130c	< 0.3		
11106649	D	128	< 0.3		
11106661	D	119	< 0.3		
11106667	FB	117	< 0.3		
11106673	D	Cafeteria	< 0.3		
11106397	OB	OFFICE BLANK	< 0.3		
11106400	FB	TRAVEL BLANK	< 0.3		

Summary of Missed Locations				
Westland MS				
Test Period: 01/18/22-01/21/22				
Kit Number	Room/Area	Result		
	NA			

Summary of Missing, Compromised and >/= 4 piC/L Tests			
Westland MS			
Test Period: 01/18/22-01/21/22			
Kit Number	Room/Area	Result	
11106651	152	Missing	

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: WESTLAND MS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11106612	100 MAIN OFFICE	2022-01-18 @ 12:00	pm 2022-01-21 @ 9:00 am	< 0.3	2022-01-26
11106619	100B	2022-01-18 @ 12:00	pm 2022-01-21 @ 9:00 am	< 0.3	2022-01-26
11106611	100C	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106604	100D	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106605	100E	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106620	100F	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106618	100G	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106613	100H	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106628	101	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106627	101	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106603	101B	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106606	101C	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106610	101D	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106636	101E	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106629	101F	2022-01-18 @ 12:00	pm 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106630	102	2022-01-18 @ 1:00 µ	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106635	102	2022-01-18 @ 1:00 µ	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106675	108	2022-01-18 @ 3:00 µ	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106663	110	2022-01-18 @ 3:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106672	111	2022-01-18 @ 3:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106653	112	2022-01-18 @ 3:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106664	113	2022-01-18 @ 3:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106665	114	2022-01-18 @ 2:00 p	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106654	115	2022-01-18 @ 2:00 p	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106658	116	2022-01-18 @ 2:00 g	om 2022-01-21 @ 10:00 am	0.7 ± 0.4	2022-01-26
11106667	117	2022-01-18 @ 2:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106666	117	2022-01-18 @ 2:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106660	118	2022-01-18 @ 2:00 g	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106659	118/116	2022-01-18 @ 2:00 g	om 2022-01-21 @ 10:00 am	0.6 ± 0.4	2022-01-26
11106662	119	2022-01-18 @ 2:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106661	119	2022-01-18 @ 2:00 g	om 2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106655	120	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	0.7 ± 0.4	2022-01-26
11106656	120	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106657	121	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106646	125	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106616	127	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106648	128	2022-01-18 @ 2:00 p	om 2022-01-21 @ 10:00 am	< 0.3	2022-01-26

Radon test result report for: WESTLAND MS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11106649	128	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106601	128A	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106608	129	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106652	130	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106650	130	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106641	130 OFFICE	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106642	130A	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106631	130C	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106602	130C	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106607	130C	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106624	130D	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106640	131	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106639	131/133	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106647	133	2022-01-18 @ 2:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106626	135	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106632	136	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106615	137	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106623	137	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106625	137	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106633	138	2022-01-18 @ 1:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106622	139	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106637	139	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106638	139	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106634	140	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106617	142	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106643	148	2022-01-18 @ 1:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106644	149 GYM	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106645	149/GYM	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106609	151	2022-01-18 @ 1:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106677	203	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106678	210	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106670	214	2022-01-18 @ 4:00 pm	2022-01-21 @ 11:00 am	0.7 ± 0.4	2022-01-26
11106669	221	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106676	229	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106671	CAFETERIA	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106673	CAFETERIA	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106674	CAFETERIA	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: WESTLAND MS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11106668	CAFETERIA STAGE	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106614	CALM ROOM	2022-01-18 @ 12:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106621	EATING AREA OUTSIDE MAIN OFFICE	2022-01-18 @ 12:00 pm	2022-01-21 @ 10:00 am	< 0.3	2022-01-26
11106682	KITCHEN	2022-01-18 @ 3:00 pm	2022-01-21 @ 11:00 am	< 0.3	2022-01-26
11106614 11106621 11106682	CALM ROOM EATING AREA OUTSIDE MAIN OFFICE KITCHEN	2022-01-18 @ 12:00 pm 2022-01-18 @ 12:00 pm 2022-01-18 @ 3:00 pm	2022-01-21 @ 10:00 am 2022-01-21 @ 10:00 am 2022-01-21 @ 11:00 am	< 0.3 < 0.3 < 0.3	2022-01-2 2022-01-2 2022-01-2

EXPOSURE IN BOWSER-	MORNER RADON CHAMBER
CLIENT KCI Technologie	5, Jnc. Job Number 203404
NOMINAL Conditions: Radon Conc. 16.2	_pCi/L Rel. Hum <u>28.8</u> % Temp. <u>59.9</u> F
Date Start: 12/24/21 Date Stop: 12/27/2	Date Start: Date Stop:
Time Start: 0809 Time Stop: 0809	_ Time Start: Time Stop:
Device No.'s: (2) Char Bags-	Device No.'s:
9341721,9341722	
р.	
syldt	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	·
=	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	2

1_

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

SK MA MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within ± 25% of the chamber's reference value (16.2 pCi/L).

	lu Starteu	Liueu	pCI/L	Analyzed
9341721 1	2021-12-24 (@ 8:00 am 2021-12-27 @ 8:	:00 am 11.6 ± 0.9	2021-12-31
9341722 1	2021-12-24 (@ 8:00 am 2021-12-27 @ 8:	:00 am 15.4 ± 1.2	2021-12-31



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – January 2022 Schools

Name of Schools:

- 1. Poolesville ES
- 2. Rosa Parks MS
- 3. Seven Locks ES
- 4. Somerset ES
- 5. Thomas Pyle MS
- 6. Walt Whitman HS
- 7. Walter Johnson HS
- 8. Westland MS
- 9. Wyngate ES

	Date	Initials
Radon Test Kits Deployed	01/18/2022	M
Radon Test Kits Collected	01/21/2022	M
Radon Test Kits Shipped to Lab*	01/21/2022	TM
Radon Test Kits Received by Lab*	01/23/2022	M

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Westland Middle School
Date of Report	2/21/2020
Round of Testing	Initial Follow-up Post Remediation 2 year testing 5 year testing HVAC Upgrade Window Replacement New Addition New Facility
# of Rooms Tested	65
# Rooms ≥4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.8 pCi/L

MCPS RADON TESTING - EXECUTIVE SUMMARY

Project Status

Current Project Status at this time: Testing Complete; no further action.



2/21/2020

Mr. Richard Cox, MS Environmental Team Leader Montgomery County Public Schools Division of Maintenance Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #12146341126

Location: Westland Middle School 5511 Massachusetts Avenue Bethesda, Maryland 20816

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Westland Middle School, located at 5511 Massachusetts Avenue in Bethesda, Maryland 20816 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Provider (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on 2/7/2020 and deployed eighty-one (81) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted sixty (60) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on 2/10/2020 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a National Radon Safety Board (NRSB) radon measurement provider and is a certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the upper-20s and high temperatures were in the mid-50s. Maximum sustained winds ranged from 10-23 miles per hour. Average humidity was around 64%. 0.32 inches of precipitation (rain) was recorded during the testing period.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples	
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Mr. Tyler P. McCleaf Radon Measurement Provider 111004 RT

KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test Locations

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank**
- PM- Project Manager
- QC- Quality Control
| Tak | Table 1- Radon Testing Results | | | | |
|------------|--------------------------------|--------|--|--|--|
| | Westland Middle School | | | | |
| Test | Period: 1/7/2020-1/10-2 | 2020 | | | |
| | | | | | |
| Kit Number | Room / Area | Result | | | |
| 9346701 | 100 | 0.5 | | | |
| 9346702 | 100A | < 0.3 | | | |
| 9346703 | 100A | 0.7 | | | |
| 9346704 | 100F | < 0.3 | | | |
| 9346705 | 100B | < 0.3 | | | |
| 9346706 | 100C | 1 | | | |
| 9346707 | 100D | 0.5 | | | |
| 9346708 | 100E | < 0.3 | | | |
| 9346709 | 100G | 0.7 | | | |
| 9346710 | 101 | < 0.3 | | | |
| 9346711 | 136 | < 0.3 | | | |
| 9346712 | 136A | < 0.3 | | | |
| 9346713 | 136A | < 0.3 | | | |
| 9346714 | 136B | < 0.3 | | | |
| 9346715 | 136B | < 0.3 | | | |
| 9346716 | 136C | < 0.3 | | | |
| 9346717 | 136D | < 0.3 | | | |
| 9346718 | 136E | < 0.3 | | | |
| 9346719 | 136F | < 0.3 | | | |
| 9346720 | 135 | < 0.3 | | | |
| 9346721 | 135A | < 0.3 | | | |
| 9346722 | 142 | < 0.3 | | | |
| 9346723 | 142 | < 0.3 | | | |
| 9346724 | 143 | 1.5 | | | |
| 9346725 | 143 | 1 | | | |
| 9346726 | 139 | 0.9 | | | |
| 9346727 | 137 | < 0.3 | | | |
| 9346728 | 134 | < 0.3 | | | |
| 9346729 | 133 | < 0.3 | | | |
| 9346730 | 133A | < 0.3 | | | |
| 9346731 | 132 | < 0.3 | | | |
| 9346732 | 131 | < 0.3 | | | |
| 9346733 | 131 | 0.5 | | | |
| 9346734 | 130 | < 0.3 | | | |
| 9346735 | 130 | < 0.3 | | | |
| 9346736 | 129 | < 0.3 | | | |
| 9346737 | 128 | < 0.3 | | | |
| 9346738 | 126 | 1 | | | |
| 9346739 | 126A | 1.7 | | | |
| 9346740 | 126B | 1.4 | | | |
| 9346741 | 152 | 1 | | | |
| 9346742 | 151 | < 0.3 | | | |

9346743	151	< 0.3
9346744	125	0.7
9346745	125	0.7
9346746	125A	0.6
9346747	125B	0.5
9346748	125C	< 0.3
9346749	150	< 0.3
9346750	127B	1.2
9346751	127A	< 0.3
9346752	127C	< 0.3
9346753	127C	0.5
9346754	122	< 0.3
9346755	122	< 0.3
9346756	122A	< 0.3
9346757	119	1.2
9346758	120	1.7
9346759	118	0.7
9346760	117	< 0.3
9346761	116	0.8
9346762	115	< 0.3
9346763	115	< 0.3
9346764	113	0.6
9346765	114	0.6
9346766	112	0.8
9346767	111	0.6
9346768	110	< 0.3
9346769	109	0.9
9346770	107	1.8
9346771	106	1.4
9346772	105	1
9346773	105	0.5
9346774	CAFETERIA	< 0.3
9346775	CAFETERIA	< 0.3
9346776	CAFETERIA	0.6
9346777	228	< 0.3
9346778	221	< 0.3
9346779	251	0.5
9346780	204	< 0.3
9346781	204	< 0.3
9348311	OFFICE BLANK	<0.3

Table 2- Radon Testing Results			
	Westland M	iddle School	
	Test Period: 1/7/	/2020-1/10-2020	
Kit Number	QC Type	Room / Area	Result
9346703	D	100A	0.7
9346713	D	136A	0.5
9346723	D	142	<0.3
9346733 D 131 0.5			
9346735 FB 130 <0.3			
9346743 D 151 <0.3			
9346753	D	127C	0.5
9346755	FB	122	<0.3
9346763	D	115	<0.3
9346773	D	105	0.5
9346775	FB	CAFETERIA	<0.3
9346781	D	204	<0.3
9348319	TRANSIT BLANK	NA	<0.3
9348320	TRANSIT BLANK	NA	<0.3
9348313	TRANSIT BLANK	NA	<0.3

Summary of Missed Locations					
Westland Middle School					
Test Period: 01/07/2020 - 01/10/2020					
Kit Number	Room/Area	Result			
-	N/A	-			

Summary of Missing, Compromised and >/= 4 piC/L Tests				
	Westland Middle School			
Tes	t Period: 01/07/2020 - 01/10/2020			
Kit Number	Room/Area	Result		
-	N/A	-		

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340067	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.4 D	2020-01-03
9340035	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	22.5 ± 2.3 D	2020-01-03
9340003	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.2 \pm 2.4 \text{ D}$	2020-01-03
9340089	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	23.3 ± 2.3 D	2020-01-03
9340072	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	18.3 ± 2.0 D	2020-01-03
9340040	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.3 ± 2.6 D	2020-01-03
9340008	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.8 ± 2.5 D	2020-01-03
9340094	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	24.7 ± 2.5 D	2020-01-03
9340099	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	27.5 ± 2.6 D	2020-01-03
9340077	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.2 ± 2.5 D	2020-01-03
9340045	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.7 ± 2.4 D	2020-01-03
9340013	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.9 ± 2.6 D	2020-01-03
9340018	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	29.1 ± 2.8 D	2020-01-03
9341704	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.4 D	2020-01-03
9340050	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.2 ± 2.6 D	2020-01-03
9340023	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.2 ± 2.7 D	2020-01-03
9341709	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.5 ± 2.4 D	2020-01-03
9340055	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.8 ± 2.6 D	2020-01-03
9340060	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.3 ± 2.5 D	2020-01-03
9340028	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	23.9 ± 2.3 D	2020-01-03
9341714	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	28.3 ± 2.7 D	2020-01-03
9340082	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.4 ± 2.6 D	2020-01-03
9340065	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.2 \pm 2.4 \text{ D}$	2020-01-03
9340033	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.2 \pm 2.5 \text{ D}$	2020-01-03
9341719	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.7 ± 2.5 D	2020-01-03
9340001	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.3 ± 2.5 D	2020-01-03
9340087	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.8 \pm 2.4 \text{ D}$	2020-01-03
9340070	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	19.5 ± 2.4 D	2020-01-03
9340038	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.7 ± 2.3 D	2020-01-03
9340006	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.2 \pm 2.4 \text{ D}$	2020-01-03
9340092	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	31.4 ± 2.8 D	2020-01-03
9340097	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.7 ± 2.5 D	2020-01-03
9340075	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	29.6 ± 2.6 D	2020-01-03
9340043	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.1 ± 2.6 D	2020-01-03
9340011	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.8 ± 2.5 D	2020-01-03
9340016	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.2 \pm 2.4 \text{ D}$	2020-01-03
9341702	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.8 ± 2.5 D	2020-01-03

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340048	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.5 ± 2.4 D	2020-01-03
9340021	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.7 ± 2.6 D	2020-01-03
9341707	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.8 \pm 2.4 \text{ D}$	2020-01-03
9340053	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.8 ± 2.5 D	2020-01-03
9340058	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.5 ± 2.7 D	2020-01-03
9340026	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.9 ± 2.4 D	2020-01-03
9341712	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	24.3 ± 2.4 D	2020-01-03
9340080	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.4 D	2020-01-03
9340063	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.8 ± 2.5 D	2020-01-03
9340031	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.9 ± 2.4 D	2020-01-03
9341717	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.7 ± 2.4 D	2020-01-03
9340085	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.9 ± 2.5 D	2020-01-03
9340068	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.2 \pm 2.5 \text{ D}$	2020-01-03
9340036	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	23.6 ± 2.3 D	2020-01-03
9340004	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.9 ± 2.6 D	2020-01-03
9340090	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.3 ± 2.5 D	2020-01-03
9340073	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.8 ± 2.5 D	2020-01-03
9340041	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.6 ± 2.4 D	2020-01-03
9340009	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.1 ± 2.4 D	2020-01-03
9340095	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.2 ± 2.5 D	2020-01-03
9340100	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.5 \pm 2.4 \text{ D}$	2020-01-03
9340078	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$25.0 \pm 2.4 \text{ D}$	2020-01-03
9340046	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$28.0 \pm 2.6 \text{ D}$	2020-01-03
9340014	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	21.8 ± 2.8 D	2020-01-03
9340019	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.0 \pm 2.5 \text{ D}$	2020-01-03
9341705	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	27.8 ± 2.6 D	2020-01-03
9340051	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.5 \pm 2.4 \text{ D}$	2020-01-03
9340056	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.7 ± 2.6 D	2020-01-03
9340024	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.3 ± 2.5 D	2020-01-03
9341710	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.2 \pm 2.3 \text{ D}$	2020-01-03
9340061	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$28.9 \pm 2.6 \text{ D}$	2020-01-03
9340029	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$23.0 \pm 2.3 \text{ D}$	2020-01-03
9341715	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$27.0 \pm 2.5 \text{ D}$	2020-01-03
9340083	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$24.9 \pm 2.4 \text{ D}$	2020-01-03
9340066	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.4 D	2020-01-03
9340034	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$26.4 \pm 2.5 \text{ D}$	2020-01-03
9341720	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.3 ± 2.5 D	2020-01-03

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340002	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.7 ± 2.5 D	2020-01-03
9340088	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.4 ± 2.5 D	2020-01-03
9340071	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	24.9 ± 2.4 D	2020-01-03
9340039	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.9 ± 2.5 D	2020-01-03
9340007	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.9 ± 2.4 D	2020-01-03
9340093	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.5 D	2020-01-03
9340098	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.8 ± 2.5 D	2020-01-03
9340076	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.5 D	2020-01-03
9340044	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.2 ± 2.5 D	2020-01-03
9340012	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	22.5 ± 2.2 D	2020-01-03
9340017	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.3 ± 2.5 D	2020-01-03
9341703	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.0 ± 2.5 D	2020-01-03
9340049	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.0 ± 2.5 D	2020-01-03
9340022	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.6 ± 2.6 D	2020-01-03
9341708	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	28.8 ± 2.8 D	2020-01-03
9340054	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.8 ± 2.5 D	2020-01-03
9340059	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.5 ± 2.6 D	2020-01-03
9340027	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.6 ± 2.5 D	2020-01-03
9341713	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.5 ± 2.5 D	2020-01-03
9340081	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	18.4 ± 2.1 D	2020-01-03
9340064	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.5 ± 2.5 D	2020-01-03
9340032	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.1 ± 2.4 D	2020-01-03
9341718	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	23.7 ± 2.4 D	2020-01-03
9340086	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.9 ± 2.6 D	2020-01-03
9340069	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.6 ± 2.5 D	2020-01-03
9340037	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	28.4 ± 2.6 D	2020-01-03
9340005	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	???? DIF1	2020-01-03
9340091	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.5 \pm 2.5 \text{ D}$	2020-01-03
9340096	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$26.2 \pm 2.5 \text{ D}$	2020-01-03
9340074	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	27.7 ± 2.5 D	2020-01-03
9340042	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.6 ± 2.5 D	2020-01-03
9340010	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.5 ± 2.5 D	2020-01-03
9341701	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	22.9 ± 2.3 D	2020-01-03
9340047	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	26.7 ± 2.5 D	2020-01-03
9340015	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.4 ± 2.5 D	2020-01-03
9340020	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	24.1 ± 2.4 D	2020-01-03
9341706	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	31.0 ± 2.7 D	2020-01-03

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9340052	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$27.4 \pm 2.6 \text{ D}$	2020-01-03
9340057	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	27.3 ± 2.5 D	2020-01-03
9340025	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	25.1 ± 2.4 D	2020-01-03
9341711	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	$22.5 \pm 2.2 \text{ D}$	2020-01-03
9340079	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	26.9 ± 2.5 D	2020-01-03
9340062	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.6 ± 2.5 D	2020-01-03
9340030	N/A	2019-12-21 @ 8:00 am	2019-12-23 @ 8:00 am	$25.0 \pm 2.4 \text{ D}$	2020-01-03
9341716	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	25.1 ± 2.4 D	2020-01-03
9340084	N/A	2019-12-21 @ 9:00 am	2019-12-23 @ 9:00 am	24.5 ± 2.3 D	2020-01-03

EXPOSURE IN BOWSER- M	MORNER RADON CHAMBER	
CLIENT KCI TEchnol	ggies Inc Job Number 193598	
NOMINAL Conditions: Radon Conc	_pCi/L Rel. Hum% Temp	F
	Date Start: $(2/2)/(9)$ Date Stop: $(12/23)/(9)$ Time Start: (2830) Time Stop: (2830)	Temp °F RH % Avg pCi/L
	(Gradop 4) Device No.'s: (20) Chan. Bags- 9340061 thno 9340089	70.0 35.5
	52	
	Date Start: $(2)_{11}_{19}$ Date Stop: $(2)_{23}_{19}_{19}$ Time Start: (0835) Time Stop: (0835)	Temp °F RH % Avg pCi/L
	Device No.'s: (20) Chan. Bags- 9340081 thnu 9340100	70.0 50.1 25.5
	Q 5	
	Date Start: $12 21 19$ Date Stop: $12 23 19$ Time Start: <u>0849</u> Time Stop: <u>0849</u> (Group 6) Device No.'s: <u>(20) Char. Bags -</u>	Temp °F RH % Avg pCi/L
	9341701 thau 9341720	70.9 50.1 25.5
	RS	

100

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

Radon test result report for: WESTLAND MS MAIN

9346701 100 2020-01-07 0 2020-01-10 0 12:00 pm 0.5 ± 0.3 2020-01-14 9346702 100A 2020-01-07 11:00 am 2020-01-10 12:00 pm 0.3 2020-01-14 9346703 100B 2020-01-07 11:00 am 2020-01-10 12:00 pm 0.7 ± 0.4 2020-01-14 9346704 100C 2020-01-07 11:00 am 2020-01-10 12:00 pm 0.5 ± 0.3 2020-01-14 9346704 100F 2020-01-07 11:00 am 2020-01-10 12:00 pm < 0.3 2020-01-14 9346704 100F 2020-01-07 11:00 am 2020-01-10 12:00 pm < 0.3 2020-01-14 9346701 101 2020-01-07 11:00 am 2020-01-10 12:00 pm < 0.3 2020-01-14 9346771 105 2020-01-07 2:00 pm 2020-01-10 12:00 pm < 0.5 ± 0.3 2020-01-14 9346770 107 2020-01-07 2:00 pm 2020-01-10 12:00 pm < 0.5 ± 0.3 2020-01-14	Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9346702 100A 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm < 0.3	9346701	100	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	0.5 ± 0.3	2020-01-14
9346703 100A 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-14 9346705 100B 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm 1.0 ± 0.3 2020-01-14 9346706 100C 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm 0.5 ± 0.4 2020-01-14 9346707 100D 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm < 0.3	9346702	100A	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346705 100B 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm < 0.3 2020-01-14 9346706 100C 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm 0.5 ± 0.4 2020-01-14 9346707 100D 2020-01-07 @ 11:00 am 2020-01-10 @ 12:00 pm < 0.3	9346703	100A	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9346706100C2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 1.0 ± 0.3 2020-01-149346707100D2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.5 ± 0.4 2020-01-149346708100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.3 2020-01-149346704100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.3 2020-01-1493467041012020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467661102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467611132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 2020-01-149346754<	9346705	100B	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346707100D2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.5 ± 0.4 2020-01-149346708100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm < 0.3 2020-01-149346704100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467011012020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm $< 0.5 \pm 0.3$ 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.8 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467661102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467671112020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm $< 6 \pm 0.3$ 2020-01-1493467641132020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm $< 6 \pm 0.3$ 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm $< 6 \pm 0.3$ 2020-01-1493467611152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm $< 6 \pm 0.3$ 2020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm $< 6 \pm 0.3$ 2020-01-1493467631162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346759 <td< td=""><td>9346706</td><td>100C</td><td>2020-01-07 @ 11:00 am</td><td>2020-01-10 @ 12:00 pm</td><td>1.0 ± 0.3</td><td>2020-01-14</td></td<>	9346706	100C	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	1.0 ± 0.3	2020-01-14
9346708100E2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm< 0.32020-01-149346704100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm< 0.3	9346707	100D	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	0.5 ± 0.4	2020-01-14
9346704100F2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm<0.32020-01-149346709100G2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.7 ± 0.3 2020-01-1493467101012020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467701072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.8 ± 0.4 2020-01-1493467661102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467671112020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm <0.3 2020-01-1493467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm <0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm <0.3 2020-01-1493467661172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm <0.3 2020-01-149346757118 <td< td=""><td>9346708</td><td>100E</td><td>2020-01-07 @ 11:00 am</td><td>2020-01-10 @ 12:00 pm</td><td>< 0.3</td><td>2020-01-14</td></td<>	9346708	100E	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346709100G2020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.7 ± 0.3 2020-01-1493467101012020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467701072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467681092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467681102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467561172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 2020-01-1493467571182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346755	9346704	100F	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467101012020-01-07 @ 11:00 am2020-01-10 @ 12:00 pm< 0.32020-01-1493467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467641072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467651102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 ± 0.4 2020-01-1493467551182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346756 </td <td>9346709</td> <td>100G</td> <td>2020-01-07 @ 11:00 am</td> <td>2020-01-10 @ 12:00 pm</td> <td>0.7 ± 0.3</td> <td>2020-01-14</td>	9346709	100G	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	0.7 ± 0.3	2020-01-14
93467731052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-1493467721052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467681102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 ± 0.4 2020-01-1493467531162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.3 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467551182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346	9346710	101	2020-01-07 @ 11:00 am	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467721052020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-1493467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467701072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.8 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467671112020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467511152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122	9346773	105	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.5 ± 0.3	2020-01-14
93467711062020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.4 ± 0.4 2020-01-1493467701072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467681102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020	9346772	105	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	1.0 ± 0.4	2020-01-14
93467701072020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 1.8 ± 0.4 2020-01-1493467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467681102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467661112020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467441252020-01-07 @ 1:	9346771	106	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	1.4 ± 0.4	2020-01-14
93467691092020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.9 ± 0.4 2020-01-1493467681102020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467501182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467561222020-01-07 @ 1:00 pm	9346770	107	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	1.8 ± 0.4	2020-01-14
9346768110 $2020-01-07 @ 2:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346767111 $2020-01-07 @ 2:00 pm$ $2020-01-10 @ 12:00 pm$ 0.6 ± 0.3 $2020-01-14$ 9346766112 $2020-01-07 @ 2:00 pm$ $2020-01-10 @ 12:00 pm$ 0.8 ± 0.4 $2020-01-14$ 9346764113 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ 0.6 ± 0.3 $2020-01-14$ 9346765114 $2020-01-07 @ 2:00 pm$ $2020-01-10 @ 12:00 pm$ 0.6 ± 0.3 $2020-01-14$ 9346763115 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346761116 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346760117 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346759118 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346757119 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ $< 1.2 \pm 0.4$ $2020-01-14$ 9346758120 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ $< 1.2 \pm 0.4$ $2020-01-14$ 9346755122 $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346756122A $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346756122A $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 pm$ < 0.3 $2020-01-14$ 9346756122A $2020-01-07 @ 1:00 pm$ $2020-01-10 @ 12:00 p$	9346769	109	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.9 ± 0.4	2020-01-14
93467671112020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.8 ± 0.4 2020-01-1493467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467591182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm $< 0.5 \pm 0.3$ 2020-01-1493467451252020-01-07 @ 1	9346768	110	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467661122020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.8 ± 0.4 2020-01-1493467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467571182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346746125A2020-01-07 @ 1:00	9346767	111	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.6 ± 0.3	2020-01-14
93467641132020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467651142020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467591182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346746125A2020-01-07 @ 1:00 pm<	9346766	112	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.8 ± 0.4	2020-01-14
93467651142020-01-07 @ 2:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.3 2020-01-1493467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm<0.3	9346764	113	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.6 ± 0.3	2020-01-14
93467631152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-1493467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346765	114	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.6 ± 0.3	2020-01-14
93467621152020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-1493467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.8 ± 0.4 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346763	115	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467611162020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.8 ± 0.4 2020-01-1493467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467591182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.2 ± 0.4 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346747125B2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346748125C2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467381262020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-149346738126A <t< td=""><td>9346762</td><td>115</td><td>2020-01-07 @ 1:00 pm</td><td>2020-01-10 @ 12:00 pm</td><td>< 0.3</td><td>2020-01-14</td></t<>	9346762	115	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467601172020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-1493467591182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.2 ± 0.4 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346761	116	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.8 ± 0.4	2020-01-14
93467591182020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.2 ± 0.4 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm<0.3	9346760	117	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467571192020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.2 ± 0.4 2020-01-1493467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346759	118	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.7 ± 0.4	2020-01-14
93467581202020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-1493467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346757	119	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.2 ± 0.4	2020-01-14
93467541222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-1493467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346758	120	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.7 ± 0.4	2020-01-14
93467551222020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-149346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.3	9346754	122	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346756122A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm< 0.32020-01-1493467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.4 2020-01-149346747125B2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346748125C2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467381262020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-149346739126A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346755	122	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467441252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-1493467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.4 2020-01-149346747125B2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346748125C2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467381262020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-149346739126A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346756	122A	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
93467451252020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.7 ± 0.4 2020-01-149346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.4 2020-01-149346747125B2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346748125C2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467381262020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-149346739126A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346744	125	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9346746125A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.6 ± 0.4 2020-01-149346747125B2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-149346748125C2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm < 0.3 2020-01-1493467381262020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-149346739126A2020-01-07 @ 1:00 pm2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346745	125	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.7 ± 0.4	2020-01-14
9346747 125B 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 0.5 ± 0.3 2020-01-14 9346748 125C 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm <0.3	9346746	125A	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.6 ± 0.4	2020-01-14
9346748 125C 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm < 0.3 2020-01-14 9346738 126 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-14 9346739 126A 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346747	125B	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	0.5 ± 0.3	2020-01-14
9346738 126 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 1.0 ± 0.4 2020-01-14 9346739 126A 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346748	125C	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346739 126A 2020-01-07 @ 1:00 pm 2020-01-10 @ 12:00 pm 1.7 ± 0.4 2020-01-14	9346738	126	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.0 ± 0.4	2020-01-14
1	9346739	126A	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.7 ± 0.4	2020-01-14

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9346740	126B	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.4 ± 0.4	2020-01-14
9346751	127A	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346750	127B	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.2 ± 0.4	2020-01-14
9346753	127C	2020-01-07 @ 1:00 pm	2020-01-10 @ 11:00 am	0.5 ± 0.4	2020-01-14
9346752	127C	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346737	128	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346736	129	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346734	130	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346735	130	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346733	131	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	0.5 ± 0.3	2020-01-14
9346732	131	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346731	132	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346729	133	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346730	133A	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346728	134	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346720	135	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346721	135A	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346711	136	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346712	136A	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346713	136A	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346714	136B	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346715	136B	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346716	136C	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346717	136D	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346718	136E	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346719	136F	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346727	137	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346726	139	2020-01-07 @ 12:00 pm	2020-01-10 @ 12:00 pm	0.9 ± 0.4	2020-01-14
9346722	142	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346723	142	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	< 0.3	2020-01-14
9346724	143	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	1.5 ± 0.4	2020-01-14
9346725	143	2020-01-07 @ 12:00 pm	2020-01-10 @ 11:00 am	1.0 ± 0.4	2020-01-14
9346749	150	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346743	151	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346742	151	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346741	152	2020-01-07 @ 1:00 pm	2020-01-10 @ 12:00 pm	1.0 ± 0.4	2020-01-14
9346780	204	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9346781	204	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346778	221	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346777	228	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346779	251	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.5 ± 0.3	2020-01-14
9346775	CAFETERIA	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14
9346776	CAFETERIA	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	0.6 ± 0.3	2020-01-14
9346774	CAFETERIA	2020-01-07 @ 2:00 pm	2020-01-10 @ 12:00 pm	< 0.3	2020-01-14



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon 2019 Week 3

Name of Schools:

- 1. Bannockburn E.S.
- 2. Bethesda E.S.
- 3. Bethesda-Chevy Chase H.S.
- 4. Bradley Hill E.S.
- 5. Burning Tree E.S.
- 6. Burnt Mills E.S.
- 7. East Silver Springs E.S.
- 8. Einstein H.S.
- 9. Flora Singer E.S.
- 10. Key M.S.
- 11. Montgomery Blair H.S.

- 12. Montgomery Knolls E.S.
- 13. Newport Mills M.S.
- 14. Oak View E.S.
- 15. Rock View E.S.
- 16. Roscoe Nix E.S.
- 17. Sligo M.S.
- 18. Spring Mill Center
- 19. Springbrook H.S.
- 20. Westland M.S.
- 21. Woodlin M.S.

	Date	Initials
Radon Test Kits Deployed	1/6/20 to 1/7/20	TM
Radon Test Kits Collected	1/9/20 to 1/10/20	M
Radon Test Kits Shipped to Lab*	1/10/20	TM
Radon Test Kits Received by Lab*	1/13/202	SM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Westland Middle School		
Date of Report	March 14, 2018		
Round of Testing	Initial		
	Follow-up		
	Post Remediation		
	2 year testing		
	5 year testing		
	HVAC Upgrade		
	Window Replacement		
	New Addition		
	New Facility		
# of Rooms Tested	14		
# Rooms ≥4.0 pCi/L	0		
Lowest Value	<0.3 pCi/L		
Highest Value	3.6 pCi/L		

MCPS RADON TESTING - EXECUTIVE SUMMARY

Project Status

Current Project Status at this time: Retesting completed; no further action at this time.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 14, 2018

Mr. Richard Cox, MS Team Leader Montgomery County Public Schools Division of Maintenance Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #1214634188

Location: Westland Middle School 5511 Massachusetts Ave. Bethesda, Maryland 20816

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Westland Middle School, located at 5511 Massachusetts Ave. in Bethesda, Maryland 20816 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 13, 2018 and deployed sixteen (16) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

- 1. Rooms not successfully tested,
- 2. Rooms with elevated November 2017 results (i.e. \geq 3.5 piC/L).

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on February 16, 2018 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to post-mitigation biennial testing.

These tests were conducted to:

• Confirm the success of the mitigation system(s).

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures ranged from the mid-20s to upper 40s and high temperatures ranged from the high-30s to the high-60s. Maximum sustained winds ranged from 10-18 miles per hour. Average humidity was around 73%. 0.30 Inches of precipitation was recorded during the testing period.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples			
Results of Blank Canisters:	The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.		
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Juns Makler

Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

C- Laboratory Analytical Results

B - Radon Test Summary Spreadsheets

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank**
- PM- Project Manager
- QC- Quality Control

	Table 1 - Radon Testing Results Westland Middle School						
	Test Period: 02/13/18-02/16/18						
Kit Number Room / Area Result							
7975475	105	0.7					
7975476	106	0.6					
7975463	136	0.7					
7975464	139	1.3					
7975495	100F	< 0.3					
7975473	118 OFFICE	< 0.3					
7975460	125B	0.9					
7975468	125C	1.1					
7975474	BLR	3.6					
7975466	GLR	1.4					
7975478	KITCHEN	< 0.3					
7975462	KITCHEN OFFICE	< 0.3					
7975465	MED CENTER	0.6					
7975461	STAGE	< 0.3					

	Table 2 - Radon Testing Results	
	Westland Middle School	
	Test Period: 02/13/18-02/16/18	
Kit Number	QC Type	Result
7975477	D (106)	0.7
7975467	FB (MED CENTER)	< 0.3

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: WESTLAND MIDDLE SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7975495	100F	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20
7975475	105	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.7 ± 0.3	2018-02-20
7975477	106	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.7 ± 0.3	2018-02-20
7975476	106	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.6 ± 0.3	2018-02-20
7975473	118 OFFICE	2018-02-13 @ 11:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20
7975460	125B	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.9 ± 0.3	2018-02-20
7975468	125C	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	1.1 ± 0.4	2018-02-20
7975463	136	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.7 ± 0.3	2018-02-20
7975464	139	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	1.3 ± 0.4	2018-02-20
7975474	BLR	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	3.6 ± 0.5	2018-02-20
7975466	GLR	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	1.4 ± 0.3	2018-02-20
7975478	KITCHEN	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20
7975462	KITCHEN OFFICE	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20
7975465	MED CENTER	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	0.6 ± 0.3	2018-02-20
7975467	MED CENTER	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20
7975461	STAGE	2018-02-13 @ 10:00 am	2018-02-16 @ 9:00 am	< 0.3	2018-02-20



 ENGINEERS
 PLANNERS
 SCIENTISTS
 CONSTRUCTION
 MANAGERS

 Corporate Office:
 936 Ridgebrook Road
 • Sparks , Maryland
 21152
 • 410-316-7800
 • (Fax)
 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase

Names of Schools:

- 1. Westbrook Elementary School
- 2. Westland Middle School
- 3. Walt Whitman High School
- 4. Cloverly Elementary School
- 5. Sligo Middle School
- 6. Flora Singer Elementary School
- 7. Albert Einstein High School
- 8. Roscoe Nix Elementary School
- 9. Mario Loiederman Middle School
- 10. Sargent Shriver Elementary School
- 11. Whetstone Elementary School
- 12. Brooke Grove Elementary School
- 13. Clearspring Elementary School
- 14. Beall Elementary School
- 15. Maryvale Elementary School
- 16. Lathrop E. Smith Center
- 17. Laytonsville Elementary School
- 18. Germantown Elementary School
- 19. Spring Mill Center
- 20. Northwood High School

- 21. E. Silver Spring Elementary School
- 22. Silver Spring Int. Middle School
- 23. Clarksburg High School
- 24. Rosa Parks Middle School
- 25. Greenwood Elementary School
- 26. Montgomery Knolls Elem. School
- 27. Watkins Mill Elementary School
- 28. Gaithersburg Elementary School
- 29. Viers Mill Elementary School
- 30. Rock View Elementary School

	1	
	Date	Initials
Radon Test Kits Deployed	2/13/18	UM
Radon Test Kits Collected	2/16/18	ŮM
Radon Test Kits Shipped to Lab*	2/16/18	JM
Radon Test Kits Received by Lab*	2/20/18	ĴM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

Radon test result report for: OFFICE BLANKS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7979482	1	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986991	10	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985684	11	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986987	12	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986993	13	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986990	14	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7979485	2	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985686	3	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986995	4	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986989	5	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986998	6	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986986	7	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986985	8	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986997	9	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20

Radon test result report for: TRANSIT BLANKS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7984188	1	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7984044	10	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986582	11	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986999	12	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7987000	13	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7984196	14	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986996	2	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986994	3	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986992	4	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985680	5	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985698	6	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985699	7	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985700	8	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985872	9	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20

Radon test result report for:

MCPS - Spike Sample Laboratory Results. Measured values are satisfactory, i.e. within ±25% of the chamber's reference value (20.9 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7984181	1	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.7 ± 0.8	2018-02-21
7986621	2	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.4 ± 0.8	2018-02-21
7985683	3	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.5 ± 0.8	2018-02-21
7984168	4	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	20.5 ± 0.8	2018-02-21
7986618	5	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.9 ± 0.8	2018-02-21
7984169	6	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	20.4 ± 0.8	2018-02-21

EXPOSURE IN BOWSER-MORNER RADON CHAMBER		
CLIENT KCI Technologics	Inc.	Job Number 183530
NOMINAL Conditions: Radon Conc 20.9	pCi/L Rel. Hum	<u>49.8</u> % Temp. <u>79.1</u>
Date Start: 2/16/18 Date Stop: 2/19/18	Date Start:	Date Stop:
Time Start: <u>1052</u> Time Stop: <u>1053</u>	Time Start:	Time Stop:
Device No.'s: (6) Char. Bags.	Device No.'s:	
7984181, 7986621, 7985683	F	
7984168, 7986618, 7984169		
G3 Middle		
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	~ę .
		· · · ·
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:_	
	х.* С	
-	·	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Westland Middle School
Date of Report	January 30, 2018
Round of Testing	Initial
	Follow-up
	Post Remediation
(2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	67
# Rooms \geq 4.0 pCi/L	0
Lowest Value	< 0.3 pCi/L
Highest Value	1.9 pCi/L

MCPS RADON TESTING - EXECUTIVE SUMMARY

Project Status

Current Project Status at this time: Results satisfactory to date; missed locations and missing/ compromised tests to be sampled.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

January 30, 2018

Mr. Richard Cox, MS Team Leader Montgomery County Public Schools Division of Maintenance Rockville, Maryland 20855

Re: Radon Testing Services

KCI Job #1214694182

Location: Westland Middle School 5511 Massachusetts Ave. Bethesda, Maryland 20816

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Westland Middle School, located at 5511 Massachusetts Ave. in Bethesda, Maryland 20816 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on November 27, 2017 and deployed eighty-two (82) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to

Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on November 30, 2017 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• 2 year testing.

These tests were conducted to:

• Confirm the success of the mitigation system(s).

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 30s and high temperatures ranged from the low-50s to mid-60s. Maximum sustained winds ranged from 8-15 miles per hour. Average humidity was around 65%. 0.02 Inches of precipitation was recorded during the testing period.

A magnitude 4.1 earthquake was reported on Thursday, November 30 near Dover, Delaware approximately 95 miles east of Gaithersburg, Maryland. The earthquake occurred during or just after the radon testing period for this facility. In general, enhanced radon emissions have been observed prior to earthquakes and this has been recorded all over the world, according to the research article entitled *Radon-222: A Potential Short-Term Earthquake Precursor*, published June 30, 2015 in the Journal of Earth Science and Climate

Change. The nearby earthquake, which occurred during or prior to the testing period, may have resulted in higher-than-normal radon test results for this facility.

<u>RESULTS</u>

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Missing/ compromised tests, missed rooms, and locked rooms are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples		
Results of Blank Canisters:	The field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Jams Makle

James Moulsdale, CHMM Radon Measurement Specialist KCI Technologies, Inc.

Mr. Richard Cox, MS January 30, 2018 Page 5

Attachments:

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank**
- PM- Project Manager
- QC- Quality Control
| | Radon Testing Results | | | | | |
|------------|--------------------------------|--------|--|--|--|--|
| | Westland Middle School | | | | | |
| | Test Period: 11/27/17-11/30/17 | | | | | |
| Kit Number | Room / Area | Result | | | | |
| 7976416 | 102 | < 0.3 | | | | |
| 7975782 | 106 | 0.5 | | | | |
| 7975776 | 107 | 0.7 | | | | |
| 7975775 | 109 | 0.7 | | | | |
| 7975768 | 110 | < 0.3 | | | | |
| 7975767 | 111 | 0.7 | | | | |
| 7975756 | 112 | 0.9 | | | | |
| 7975755 | 113 | 0.6 | | | | |
| 7975764 | 114 | < 0.3 | | | | |
| 7975765 | 115 | < 0.3 | | | | |
| 7975766 | 116 | < 0.3 | | | | |
| 7975771 | 117 | 0.6 | | | | |
| 7975772 | 118 | 0.6 | | | | |
| 7975773 | 121 | < 0.3 | | | | |
| 7975774 | 122 | 0.9 | | | | |
| 7975758 | 124 | 0.7 | | | | |
| 7975750 | 125 | 1.1 | | | | |
| 7975751 | 125 | 1.1 | | | | |
| 7975744 | 126 | 1.7 | | | | |
| 7975740 | 128 | < 0.3 | | | | |
| 7975739 | 129 | < 0.3 | | | | |
| 7975729 | 130 | < 0.3 | | | | |
| 7976414 | 131 | < 0.3 | | | | |
| 7976410 | 132 | 0.8 | | | | |
| 7976413 | 133 | 0.7 | | | | |
| 7975799 | 134 | 0.6 | | | | |
| 7975748 | 135 | < 0.3 | | | | |
| 7975784 | 137 | 0.6 | | | | |
| 7975789 | 142 | 0.6 | | | | |
| 7975753 | 143 | 0.7 | | | | |
| 7975754 | 143 | 1.0 | | | | |
| 7975790 | 145 | 1.4 | | | | |
| 7975760 | 150 | 0.8 | | | | |
| 7975759 | 151 | 1.0 | | | | |
| 7975749 | 152 | 1.1 | | | | |
| 7975746 | 212 | 1.1 | | | | |
| 7975791 | 214 | 1.3 | | | | |
| 7975792 | 222 | < 0.3 | | | | |
| 7975796 | 226 | < 0.3 | | | | |
| 7975795 | 228 | 0.6 | | | | |
| 7975788 | 230 | 0.5 | | | | |
| 7975793 | 100A | < 0.3 | | | | |
| 7975785 | 100B | 0.6 | | | | |
| 7975786 | 100C | < 0.3 | | | | |
| 7975797 | 100D | 0.8 | | | | |
| 7975798 | 100E | < 0.3 | | | | |

	Radon Testing Results					
	Westland Middle School					
	Test Period: 11/27/17-11/30/17					
		-				
Kit Number	Room / Area	Result				
7975800	* 100F (Tampered)	< 0.3				
7976406	100G	< 0.3				
7976415	100H	0.5				
7975783	105 OFFICE	< 0.3				
7975757	125A	0.8				
7975741	126A	1.9				
7975742	126B	1.7				
7975743	126C	1.6				
7976404	127A	< 0.3				
7976405	127B	0.9				
7976407	127C	0.8				
7976408	127D	0.6				
7976409	131B	0.7				
7975747	* 135A (Missing)	-				
7975745	136A	< 0.3				
7975777	136B	< 0.3				
7975778	136C	0.6				
7975779	136D	< 0.3				
7975780	136E	0.8				
7975787	136F	0.7				
7975794	136G	0.5				
7975769	143-2	0.7				
7975770	143-2	0.6				
7976401	CAF	0.5				
7976402	CAF	0.8				

	Radon Testing Results					
	Westland Middle School					
	Test Period: 11/27/17-11/30/17					
Kit Numbor	Kit Number OC Type Pecult					
	QC Type	Result				
7976417	D (102)	< 0.3				
7975781	D (107)	0.6				
7975763	D (114)	0.6				
7975752	D (125)	0.8				
7975738	D (130)	< 0.3				
7976411	D (132)	< 0.3				
7976403	D (CAF)	< 0.3				
7975762	FB (114)	< 0.3				
7976412	FB (132)	< 0.3				
7975761	FB (150)	< 0.3				
7977284	OB (OB)	< 0.3				

	Summary of Missed Locations			
	Westland Middle School			
Test Period: 11/27/17-11/30/17				
Kit Number	Room / Area	Result		
-	105 (Missed location)	-		
-	106 (Missed location)	-		
-	136 (Missed location)	-		
-	139 (Missed location)	-		
-	125B (Missed location)	-		
-	125C (Missed location)	-		
-	Stage (Missed location)	-		
-	Kitchen (Missed location)	-		

Summary of Missing, Compromised and ≥4 piC/L Tests						
Westland Middle School Test Period: 11/27/17-11/30/17						
	Test Period: 11/27/17-11/30/17					
		_				
Kit Number	Room / Area	Result				
7975800	* 100F (Tampered)	< 0.3				
7975747	* MED CENTER (Missing)	-				

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7975793	100A	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975785	100B	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.3	2017-12-04
7975786	100C	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975797	100D	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.4	2017-12-04
7975798	100E	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975800	100F	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976406	100G	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976415	100H	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.5 ± 0.4	2017-12-04
7976416	102	2017-11-27 @ 6:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976417	102	2017-11-27 @ 6:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975783	105 OFFICE	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975782	106	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.5 ± 0.4	2017-12-04
7975781	107	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.3	2017-12-04
7975776	107	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.7 ± 0.4	2017-12-04
7975775	109	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.7 ± 0.3	2017-12-04
7975768	110	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975767	111	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.7 ± 0.3	2017-12-04
7975756	112	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.9 ± 0.3	2017-12-04
7975755	113	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.3	2017-12-04
7975762	114	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975763	114	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.3	2017-12-04
7975764	114	2017-11-27 @ 3:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975765	115	2017-11-27 @ 2:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975766	116	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975771	117	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.3	2017-12-04
7975772	118	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.3	2017-12-04
7975773	121	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975774	122	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.9 ± 0.3	2017-12-04
7975758	124	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.7 ± 0.3	2017-12-04
7975750	125	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	1.1 ± 0.3	2017-12-04
7975751	125	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	1.1 ± 0.3	2017-12-04
7975752	125	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.3	2017-12-04
7975757	125A	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.3	2017-12-04
7975744	126	2017-11-27 @ 2:00 pm	2017-11-30 @ 12:00 pm	1.7 ± 0.4	2017-12-04
7975741	126A	2017-11-27 @ 1:00 pm	2017-11-30 @ 12:00 pm	1.9 ± 0.3	2017-12-04
7975742	126B	2017-11-27 @ 1:00 pm	2017-11-30 @ 12:00 pm	1.7 ± 0.4	2017-12-04
7975743	126C	2017-11-27 @ 1:00 pm	2017-11-30 @ 12:00 pm	1.6 ± 0.4	2017-12-04

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7976404	127A	2017-11-27 @ 3:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976405	127B	2017-11-27 @ 3:00 pm	2017-11-30 @ 11:00 am	0.9 ± 0.4	2017-12-04
7976407	127C	2017-11-27 @ 3:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.3	2017-12-04
7976408	127D	2017-11-27 @ 3:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.4	2017-12-04
7975740	128	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975739	129	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975738	130	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975729	130	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976414	131	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976409	131B	2017-11-27 @ 4:00 pm	2017-11-30 @ 11:00 am	0.7 ± 0.4	2017-12-04
7976410	132	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.3	2017-12-04
7976411	132	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976412	132	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7976413	133	2017-11-27 @ 1:00 pm	2017-11-30 @ 11:00 am	0.7 ± 0.3	2017-12-04
7975799	134	2017-11-27 @ 4:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.4	2017-12-04
7975748	135	2017-11-27 @ 4:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975745	136A	2017-11-27 @ 5:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975777	136B	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975778	136C	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.6 ± 0.4	2017-12-04
7975779	136D	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975780	136E	2017-11-27 @ 5:00 pm	2017-11-30 @ 12:00 pm	0.8 ± 0.4	2017-12-04
7975787	136F	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.7 ± 0.3	2017-12-04
7975794	136G	2017-11-27 @ 5:00 pm	2017-11-30 @ 11:00 am	0.5 ± 0.4	2017-12-04
7975784	137	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.4	2017-12-04
7975789	142	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.4	2017-12-04
7975753	143	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	0.7 ± 0.3	2017-12-04
7975754	143	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	1.0 ± 0.4	2017-12-04
7975769	143-2	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	0.7 ± 0.3	2017-12-04
7975770	143-2	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	0.6 ± 0.4	2017-12-04
7975790	145	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	1.4 ± 0.4	2017-12-04
7975761	150	2017-11-27 @ 6:00 pm	2017-11-30 @ 11:00 am	< 0.3	2017-12-04
7975760	150	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	0.8 ± 0.3	2017-12-04
7975759	151	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	1.0 ± 0.3	2017-12-04
7975749	152	2017-11-27 @ 2:00 pm	2017-11-30 @ 11:00 am	1.1 ± 0.3	2017-12-04
7975746	212	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	1.1 ± 0.4	2017-12-04
7975791	214	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	1.3 ± 0.4	2017-12-04
7975792	222	2017-11-27 @ 4:00 pm	2017-11-30 @ 12:00 pm	< 0.3	2017-12-04

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7975796	226	2017-11-27 @ 5:00 pr	m 2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7975795	228	2017-11-27 @ 5:00 pr	m 2017-11-30 @ 12:00 pm	0.6 ± 0.4	2017-12-04
7975788	230	2017-11-27 @ 5:00 pr	m 2017-11-30 @ 12:00 pm	0.5 ± 0.4	2017-12-04
7976403	CAF	2017-11-27 @ 3:00 pr	m 2017-11-30 @ 12:00 pm	< 0.3	2017-12-04
7976401	CAF	2017-11-27 @ 3:00 pr	m 2017-11-30 @ 12:00 pm	0.5 ± 0.4	2017-12-04
7976402	CAF	2017-11-27 @ 3:00 pr	m 2017-11-30 @ 12:00 pm	0.8 ± 0.3	2017-12-04
7977284	OB	2017-11-27 @ 2:00 pr	m 2017-11-30 @ 2:00 pm	< 0.3	2017-12-05
		-			

Radon test result report for: WESTLAND MS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7975747	135A	@	@		



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

Corporate Office: 936 Ridgebrook Road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase

Names of Schools:

- 1. Montgomery Knolls Elementary School
- 2. New Hampshire Estates Elementary School
- 3. Montgomery Blair High School
- 4. Silver Creek Middle School
- 5. Sligo Creek Elementary School
- 6. East Silver Spring Elementary School
- 7. Silver Spring International Middle School
- 8. Woodlin Elementary School
- 9. Northwood High School
- 10. Spring Mill Center
- 11. Westbrook Elementary School
- 12. Westland Middle School
- 13. Cloverly Elementary School

- 14. Flora Singer Elementary School
- 15. Sligo Middle School
- 16. Mario Loiederman Middle School
- 17. Roscoe Nix Elementary School
- 18. Sargent Shriver Elementary School
- 19.
- 20.
- 21.
- 22.
- 23.
- 24.
- 25.
- 26.

	Date	Initials
Radon Test Kits Deployed	11/27/17	IM
Radon Test Kits Collected	11/30/17	JM
Radon Test Kits Shipped to Lab*	11/30/17	M
Radon Test Kits Received by Lab*	12/04/17	JM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

Radon test result report for: TRANSIT 1 NONE

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7978062	TRANSIT 1	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975804	TRANSIT 10	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7977990	TRANSIT 11	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978201	TRANSIT 12	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978203	TRANSIT 13	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978206	TRANSIT 14	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978246	TRANSIT 15	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978239	TRANSIT 16	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978226	TRANSIT 17	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7975078	TRANSIT 18	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7975077	TRANSIT 19	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978074	TRANSIT 2	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975076	TRANSIT 20	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975684	TRANSIT 21	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975683	TRANSIT 22	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975601	TRANSIT 23	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978011	TRANSIT 24	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978012	TRANSIT 25	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978094	TRANSIT 26	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7975624	TRANSIT 27	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7834562	TRANSIT 28	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7977995	TRANSIT 29	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978098	TRANSIT 3	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7977992	TRANSIT 30	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978719	TRANSIT 4	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-05
7978732	TRANSIT 5	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7978731	TRANSIT 6	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975806	TRANSIT 7	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975815	TRANSIT 8	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04
7975805	TRANSIT 9	2017-11-27 @ 4:00 pm	2017-11-30 @ 4:00 pm	< 0.3	2017-12-04

Radon test result report for:

MCPS - Spike Sample Laboratory Results. Measured values are satisfactory, i.e. within ±25% of the chamber's reference value (27.7 pCi/L).

Kit #	Room Id	Started		Ended	pCi/L	Analyzed
7975075	S1	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	$1 25.6 \pm 0.7$	2017-12-07
7975064	S2	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	n 27.4 ± 0.8	2017-12-07
7975063	S 3	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	a 26.3 ± 0.7	2017-12-07
7975065	S4	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	a 23.0 ± 0.7	2017-12-07
7975069	S5	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	a 25.6 ± 0.7	2017-12-07
7975070	S6	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 an	a 23.0 ± 0.7	2017-12-07

EXPOSURE IN BOWSER- M	MORNER RA	DON CHAMBER	
CLIENT KCI Technolog	lies Inc.	Job Number 182393	3
NOMINAL Conditions: Radon Conc 27. 7	pCi/L Rel. Hum	49.1 % Temp. 70.1	F
Date Start: 12/11 Date Stop: 12/4/1-) Date Start:	Date Stop:	
Time Start: 1949 Time Stop: 1949	Time Start:	Time Stop:	
Device No.'s: (6) Chan. Bags.	Device No.'s:_		
7975075, 7975064, 7975063,			
1973065, 1975069, 1975070			
Fy Ront		-	
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:	~¢\$	
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:		

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Westland Middle School

Date of Test Report:	5/12/2016
Round of Testing:	Initial
	Follow-up
C	Post Remediation
# Rooms Tested:	69
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	1.9

Project Status: Post remediation testing completed; no further action at this time



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

May 12, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re:	Radon Testing Services		
	KCI Job # 12146341.36		
Location:	Westland Middle School		
	5511 Massachusetts Avenue		
	Bethesda, MD 20816		

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Westland Middle School, located at 5511 Massachusetts Avenue in Bethesda, Maryland 20816 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on April 11, 2016 and deployed eighty-three (83) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on April 14, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler

Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

School personnel informed KCI during the sample collection that numerous windows were opened for extended periods during the testing due to a problem with the facility's HVAC system.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachn	nent B

Notes:

D- Duplicate sample

The field blanks, office blank, and lab transit blank had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Mr. Richard Cox May 12, 2016 Page 4

Sincerely,

James Makler

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

- A- Floor Plan with Test Locations B- Table 1-Radon Test Summary Spreadsheet
- C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- **D-** Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank***
- PM- Project Manager
- QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 14 testing. Office blanks were not submitted under each school individually.

	Radon Testing Results					
	Westland Middle School					
Test Period: 04/11/16-04/14/16						
Kit Number	Room / Area	Result				
7752122	100G	< 0.3				
7752149	100H	< 0.3				
7752155	102	< 0.3				
7747578	105	< 0.3				
7747590	106	< 0.3				
7747577	107	0.6				
7747585	109	0.6				
7747537	110	< 0.3				
7747599	111	< 0.3				
7747600	112	< 0.3				
7747598	113	0.5				
7747593	114	0.6				
7747594	115	< 0.3				
7747595	116	< 0.3				
7747586	117	< 0.3				
7747592	118	< 0.3				
7747575	121	< 0.3				
7747538	122	< 0.3				
7752102	124	0.9				
7752114	125	1.1				
7752108	126	1.8				
7752137	128	< 0.3				
7747591	129	0.8				
7747596	130	0.6				
7752101	131	< 0.3				
7752106	132	< 0.3				
7752103	133	< 0.3				
7752127	134	0.6				
7752139	135	0.5				
7752148	136	0.7				
7752112	137	0.8				
7752132	139	0.9				
7752146	136A	< 0.3				
7752109	143	1.1				
7752104	143	1.0				
7752126	143	0.7				
7752118	143	0.5				
7752123	145	0.7				
//4/5/6	150	1.0				
//4/581	151	0.9				
//4/58/	152	1.6				
//52158	200	< 0.3				
//52156	203	< 0.3				
7752159	204	< 0.3				
//52136	209	< 0.3				
//52154	210	0.5				

Table Note: * Missing or Compromised Sample

	Radon Testing Results					
	Westland Middle School					
	Test Period: 04/11/16-04/14/16					
Kit Number	Room / Area	Result				
7752152	229	0.7				
7752113	125A	0.9				
7752107	125B	0.9				
7747580	125C	0.7				
7752117	126A	1.8				
7752111	126B	1.3				
7752116	126C	1.7				
7747589	127A	< 0.3				
7752119	127B	< 0.3				
7752128	127C	0.8				
7752105	131B	< 0.3				
7752145	100F	< 0.3				
7752144	100B	< 0.3				
7752147	100A	< 0.3				
7752134	100E	< 0.3				
7752160	CAFETERIA	< 0.3				
7752142	CONFERENCE RM	< 0.3				
7752143	136F	0.5				
7752120	136E	0.5				
7752131	136D	0.5				
7752135	136C	0.8				
7752130	136B	< 0.3				
7752138	136G	0.7				
7752150	100C	0.5				
7752124	NURSE OFF	< 0.3				
7752151	100D	0.7				

Radon Testing Results					
Westland Middle School					
	Test Period: 04/11/16-04/14/16				
Kit Number	QC Туре	Result			
7752141	D (100G)	< 0.3			
7747597	D (114)	< 0.3			
7752140	D (126A)	1.5			
7752110	D (139)	0.7			
7747588	D (152)	1.9			
7752133	D (100A)	< 0.3			
7752153	D (CAFETERIA)	< 0.3			
7752125	D (NURSE OFF)	0.6			
7752115	FB (125)	< 0.3			
7752129	FB (145)	< 0.3			
7752121	FB (100F)	< 0.3			

ATTACHMENT C

Laboratory Analytical Results

May ** LABORATORY ANALYSIS 10, 2016 REPORT **

Radon test result report for: WESTLAND MIDDLE SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7752122	100G	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752141	100G	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752149	100H	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752155	102	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747578	105	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747590	106	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747577	107	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	0.6 ± 0.3	2016-04-18
7747585	109	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	0.6 ± 0.3	2016-04-18
7747537	110	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747599	111	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747600	112	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747598	113	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	0.5 ± 0.3	2016-04-18
7747593	114	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	0.6 ± 0.3	2016-04-18
7747597	114	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747594	115	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747595	116	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747586	117	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747592	118	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747575	121	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747538	122	2016-04-11 @ 2:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752102	124	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.9 ± 0.3	2016-04-18
7752114	125	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.1 ± 0.3	2016-04-18
7752115	125	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752113	125A	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.9 ± 0.3	2016-04-18
7752107	125B	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.9 ± 0.3	2016-04-18
7747580	125C	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.7 ± 0.3	2016-04-18
7752108	126	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.8 ± 0.3	2016-04-18
7752117	126A	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.8 ± 0.3	2016-04-18
7752140	126A	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.5 ± 0.3	2016-04-18
7752111	126B	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.3 ± 0.3	2016-04-18
7752116	126C	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.7 ± 0.3	2016-04-18
7747589	127A	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752119	127B	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752128	127C	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.8 ± 0.3	2016-04-18
7752137	128	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747591	129	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.8 ± 0.3	2016-04-18
7747596	130	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.6 ± 0.3	2016-04-18

Radon test result report for: WESTLAND MIDDLE SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7752101	131	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752105	131B	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752106	132	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752103	133	2016-04-11 @ 1:00 pm	2016-04-14 @ 9:00 am	< 0.3	2016-04-18
7752139	135	2016-04-11 @ 12:00 pm	2016-04-14 @ 7:00 am	0.5 ± 0.3	2016-04-18
7752148	136	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	0.7 ± 0.3	2016-04-18
7752112	137	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	0.8 ± 0.3	2016-04-18
7752132	139	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.9 ± 0.3	2016-04-18
7752110	139	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.7 ± 0.3	2016-04-18
7752146	136A	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752118	143	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	0.5 ± 0.3	2016-04-18
7752126	143	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	0.7 ± 0.3	2016-04-18
7752127	143	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	0.6 ± 0.3	2016-04-18
7752104	143	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	1.0 ± 0.3	2016-04-18
7752109	143	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	1.1 ± 0.3	2016-04-18
7752123	145	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	0.7 ± 0.3	2016-04-18
7752129	145	2016-04-11 @ 12:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7747576	150	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.0 ± 0.3	2016-04-18
7747581	151	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	0.9 ± 0.3	2016-04-18
7747587	152	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.6 ± 0.3	2016-04-18
7747588	152	2016-04-11 @ 1:00 pm	2016-04-14 @ 8:00 am	1.9 ± 0.4	2016-04-18
7752158	200	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752156	203	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752159	204	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752136	209	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752154	210	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	0.5 ± 0.3	2016-04-18
7752152	229	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	0.7 ± 0.3	2016-04-18
7752121	100F	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752145	100F	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752144	100B	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752133	100A	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752147	100A	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752134	100E	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752160	CAFETERIA	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752153	CAFETERIA	2016-04-11 @ 3:00 pm	2016-04-14 @ 8:00 am	< 0.3	2016-04-18
7752142	CONFERENCE RM	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752143	136F	2016-04-11 @ 11:00 am	2016-04-14 @ 7:00 am	0.5 ± 0.3	2016-04-18

Radon test result report for: WESTLAND MIDDLE SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7752120	136E	2016-04-11 @ 11:00 an	n 2016-04-14 @ 7:00 am	0.5 ± 0.3	2016-04-18
7752131	136D	2016-04-11 @ 11:00 an	n 2016-04-14 @ 9:00 am	0.5 ± 0.3	2016-04-18
7752135	136C	2016-04-11 @ 11:00 an	n 2016-04-14 @ 7:00 am	0.8 ± 0.3	2016-04-18
7752130	136B	2016-04-11 @ 12:00 pm	n 2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752138	136G	2016-04-11 @ 12:00 pm	n 2016-04-14 @ 7:00 am	0.7 ± 0.3	2016-04-18
7752150	100C	2016-04-11 @ 11:00 an	n 2016-04-14 @ 7:00 am	0.5 ± 0.3	2016-04-18
7752124	NURSE OFF	2016-04-11 @ 12:00 pm	n 2016-04-14 @ 7:00 am	< 0.3	2016-04-18
7752125	NURSE OFF	2016-04-11 @ 12:00 pm	n 2016-04-14 @ 7:00 am	0.6 ± 0.3	2016-04-18
7752151	100D	2016-04-11 @ 11:00 an	n 2016-04-14 @ 7:00 am	0.7 ± 0.3	2016-04-18

Radon test result report for: OFFICE BLANK Phase 14

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7752157	0	2016-04-11 @ 4:00 pm	2016-04-14 @ 4:00 pm	< 0.3	2016-04-18
7752157	0	2016-04-11 @ 4:00 pm	2016-04-14 @ 4:00 pm	< 0.3	2016-04-

Radon test result report for: TRANSIT BLANK Phase 14

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7752162	1	2016-04-11 @ 4:00 pm	2016-04-14 @ 4:00 pm	< 0.3	2016-04-18

Radon test result report for: MCPS Spike Sample Results

7735295 1 7735289 2	2016-03-18	@ 1:00 pm	2016-03-21 @	1.00 nm	30.0 ± 2.0	2016 02 24
7735289 2	2016 02 10			1.00 pm	30.0 ± 2.0	2016-03-24
	2016-03-18	@ 1:00 pm	2016-03-21 @	1:00 pm	29.9 ± 2.0	2016-03-24
7735274 3	2016-03-18	@ 1:00 pm	2016-03-21 @	1:00 pm	25.6 ± 1.7	2016-03-24
7735278 4	2016-03-18	@ 1:00 pm	2016-03-21 @	1:00 pm	26.2 ± 1.8	2016-03-24
7735299 5	2016-03-18	@ 1:00 pm	2016-03-21 @	1:00 pm	28.3 ± 1.9	2016-03-24
7735293 6	2016-03-18	@ 1:00 pm	2016-03-21 @	1:00 pm	31.0 ± 2.0	2016-03-24

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-	MORNER RA	DON CHAMBER
CLIENT KCI Technolog:	es The.	Job Number 174430
NOMINAL Conditions: Radon Conc 26. (_pCi/L Rel. Hum	-18.8 % Temp. 70.1
Date Start: 3/18/16 Date Stop: 3/21/16	Date Start:	Date Stop:
Time Start: 1250 Time Stop: 1350	Time Start:	Time Stop:
Device No.'s: (6) Chan. Cana	- Device No.'s:_	
3029154 thru 3029157	8	
3029083, 3029086		· · ·
FS Right		
Date Start: 3/18/16 Date Stop: 3/21/16	Date Start:	Date Stop:
Time Start: 1250 Time Stop: 1250	Time Start:	Time Stop:
Device No.'s: (6) Chan. Bags.	Device No.'s:_	
7735299,7735293,7735295,		
7735274, 7735278, 7735289		
-s Right		
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	
· · · · · · · · · · · · · · · · · · ·	!	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 14

Name of Schools:

- 1. Westland MS
- 2. Whittier Woods Center

	Date	Initials
Radon Test Kits Deployed	4/11/16	JM
Radon Test Kits Collected	4/14/16	JM
Radon Test Kits Shipped to Lab*	4/14/16	JM
Radon Test Kits Received by Lab*	4/18/16	M

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

RADON SCREENING SURVEY – FOLLOW-UP WESTLAND MIDDLE SCHOOL

5511 Massachusetts Ave, Bethesda, Maryland 20816

Date of Test Report:	2/22/16	
Round of Testing:	Initial	
	Follow-up	
	Post Remediation	
# Rooms Tested	7	
# Rooms ≥ 4.0 pCi/L:	1	
Low Value:	<0.3	
High Value:	4.9	
Confirmed Rooms ≥ 4.0 pCi/L US EPA	2	
Action Level		

EXECUTIVE SUMMARY

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L) 1/6/16	Result (pCi/L) 2/22/16	Average Result (pCi/L)
137	6.2	1.3	3.8
229	1.3	1.3	1.3
100D	4.4	1.6	3.0
100E	2.9	1.3	2.1
136A	0.6	1.0	0.8
136B	3.9	4.9	4.4
136C	5.0	3.2	4.1



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS 936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Westland Middle School

Date of Test Report:	2/22/2016
Round of Testing:	Initial
•	Post Remediation
# Rooms Tested:	7
# Rooms \geq 4.0 pCi/L:	1
Low Value:	< 0.3
High Value:	4.9

Rooms with results \geq 4.0 pCi/L: Room 136B (4.9 pCi/L),

Project Status: Retesting completed; use the average of the initial and re-test results in a room to determine if remediation is necessary.

KCI TECHNOLOGIES, INC.

www.kci.com



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS 936 Ridgebrook Road • Sparks, MD 21152 • 410-316-7800 • (Fax) 410-316-7935

February 22, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re:	Radon Testing Services
	KCI Job # 12146341.25

Location: Westland Middle School 5511 Massachusetts Avenue Bethesda, MD 20816

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Westland Middle School, located at 5511 Massachusetts Avenue in Bethesda, Maryland 20816 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCl conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on January 19, 2016 and deployed eleven (11) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 22, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests to Accustar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis (certification # ARL0007) located at 929 Mount Zion Road,

KC1 TECHNOLOGIES, INC.

www.kei.com

Lebanon, Pennsylvania.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	136B	4.2, 4.9(D)
<4.0 piC/L	See Attachment B	
Notes		

D- Duplicate sample

The lab transit blanks had test results of less or equal to the laboratory detection limit of 0.4 pCi/L. The field blank had a low concentration of radon detected (0.6 piC/L), which suggests the field blank may have been incompletely sealed while deployed. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.
Mr. Richard Cox February 22, 2016 Page 4

Sincerely,

James Markler-

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test Locations B- Table 1-Radon Test Summary Spreadsheet C- Laboratory Analytical Results

KCI TECHNOLOGIES, INC.

www.kei.com

Employed Deard No.ce 1985

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

.

Radon Test Summary Spreadsheet

.

.

•

.

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

	Radon Testing Results				
Westland Middle School					
T	est Period: 01/19/16-01/22/16				
Kit Number	Room / Area	Result			
3028970	137	1.3			
3028980	229	1.3			
3028976	100D	1.6			
3028978	100E	1.3			
3028971	136A	1.0			
3028973	136B	4.2			
3028974	136C	3.2			

Table Note: * Missing or Compromised Sample

	Radon Testing Results			
	Westland Middle School			
	Test Period: 01/19/16-01/22/16			
Kit Number QC Type Result				
3028977	D (100D)	1.5		
3028975	D (136B)	4.9		
3028969	D (137)	0.5		
3028972	FB (136C)	0.6		

ATTACHMENT C

Laboratory Analytical Results



Radon in Air

EPA Melhod #402-R-92-004 Chercoal Canister NRPP Device Code 6048 NRSB Device Code 10317
Property Tested:
Westland Middle School
5511 Massachusetts Ave
Bethesda MD 20816

Log Number	Device Number	Test Exposu	re Duration:	Area Tested	Result (pCi/L)
3010592	3028970	01/19/2016 1:21 pm	01/22/2016 9:34	am 137 First Floor	1.3
3010593	3028969	01/19/2016 1:21 pm	01/22/2016 9:34	am 137 First Floor	0.5
3010594	3028974	01/19/2016 1:38 pm	01/22/2016 9:32	am 136C First Floor	3.2
3010595	3028972	01/19/2016 1:38 pm	01/22/2016 9:32	am 136C First Floor	0.6
3010596	3028976	01/19/2016 1:49 pm	01/22/2016 9:35 a	am 100D First Floor	1.6
3010597	3028977	01/19/2016 1:49 pm	01/22/2016 9:35 a	am 100D First Floor	1.5
3010598	3028980	01/19/2016 2:01 pm	01/22/2016 9:38 a	am 229 Second Floor	1.3
3010599	3028971	01/19/2016 1:35 pm	01/22/2016 9:28 a	am 136A First Floor	1.0
3010600	3028973	01/19/2016 1:43 pm	01/22/2016 9:30 a	am 136B First Floor	4.2
3010601	3028975	01/19/2016 1:43 pm	01/22/2016 9:30 a	am 136B First Floor	4.9

Comment: A copy of this report was emailed to james.moulsdale@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 01/27/2016 Date Logged:

01/27/2016

Date Analyzed: 01/28/2016

Date Reported: 01/28/2016

Report Reviewed By: CDGER Babys

Report Approved By:

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs The uncertainty of this radon measurement Is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY, Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

AccuStar

.

Radon in Air

NRPP 10511AL NRSB ARL0007			EPA Metho (NRPP E NRSB De	d #402-R-92-004 Charcoal Canisler Vevice Code 6048 Evice Code 10317
Laboratory Report for:		Property Tested:		
KCI Technologies 936 Ridgebrook Rd Sparks MD 21152		Westland Middle School 5511 Massachusetts Av Bethesda MD 20816	e	
Log Device Test Expo Number Number 01/19/2016 1:51 p	osure Duration: m 01/22/2016 9:36 am	Area Tested 100E First Floor		Result (pCi/L) 1.3
Comment: A copy of this report was ema	illed to james.moulsdale€	۵kci.com.		
Distributed by: KCI Technologies, Inc. Date Received: 01/27/2016 Date Logge	ed: 01/27/2016 D	ate Analyzed: 01/28/2016	Date Reported:	01/28/2016
Report Reviewed By: Disclaimer: The uncertainty of this radon measurement is ~+/- 10 concentrations, sample collection techniques and op This report may only be transferred to a third party in shown on this report represent levels of radon gas m Incorrect information will affect results. The results m structure at any other time. AccuStar Labs, its emplo results reported or any verbal or written interpretation	D %. Factors contributing to un eration of the dwelling. Interferent its entirety. Analytical results r easured between the dates sho hay not be construed as either hypees and agents are not respond of the results.	eport Approved By: Carolym certainty include statistical variation ence with test conditions may influe elate to the samples AS RECEIVE own in the room or area of the site predictive or supportive of measur nsible for the consequences of an	Date Hepotical D. Koke, President, Ac ons, daily and seasonal tence the test results. ED BY THE LABORATO identified above as "Pri- ements conducted in an y action taken or not tak	cuStar Labs variations in radon VRY. Results operty Tested*. y area of this ien based upon the
Rev 1402 PO B	OX 990 Jonestown PA	17038 717-274-8310	• ••	Page 2 of 2

Do not use this form in explain if NO explain if NO Certified Testers Provide # Raimy Y-N Were general operating Yes - No conditions maintained? Yes - No New Jersey or Florida ら conditions maintained? Call for correct forms. Were closed building PCi/L Multi-Page Report Y-N LAB USE ONLY Malion 5 |4/2015 # # Discrepancies will invalidate tests Name Tame Wgt. Gain Yes - No Yes - No 1/27/2016 3010592 3028970 ACPC2758 EXP12/31/2018 Instructions on back of form Read instructions carefully **(**`-! 0 9:50 Stop Time 9:34 9:35 Include Alt/PN 9.32 9.20 9.34 9:32 Both Placed by and Retrieved by/signatures are required 9:30 9.38 55 , 0 K Date KCI Technologies, Inc. ant a orier y Stop Date 4 112211 ļ May Sal 7046 INFORMATION FORM - Large Buildings Start Time Include AM/PM # 1:35 . 38 1:39 - - 4 7 7 ... Canisters retrieved by 2115 Owner waives confidentiality Canisters placed by $oldsymbol{ar{L}}$ Email: 1:43 <u>0</u> Attention: James . County \sim 6 Ĵ., Mailing: PO Box 990 Jonestown, PA 17. Shipping: 929 Mt Zion Road, Lebanon, PA • • 800-523-4964 fax 717-274-5662 NEHA 10511AL NRSB ARL 0007 Zip School by signing here _ Start Date 1/19/16 410599-2522 2000 1000 1000 <u>0</u> 5 Fax: Floor Zip State: M € Other Phone: ROOM NAME & NUMBER - LOCATION OF DETECTOR IN State MD Day Care in Public School - Public School 3010592 3010593 3010594 3010595 3010599 3010596 3010598 Other 3010600 3010597 3010601 ROOM (indicate duplicates and blanks) Real Estate -- Follow Up 'r est Name of Building/Project or Owner WCSH on J Private Day Care - Private School Neulsal Residential - Non Residential MO/ Dairs (circle one or more) Basement - Crawispace Massachus. Hs if a rocalculation is requested there is a \$10.00 recale too PER Canistor. Projects Contact Name: Jows Initial Screening AccuStar Labs 929 Mt. Zion Rd., Lebanon, PA 17046 800-523-4964 Post Mitigation rdachrod 7 661 Return canisters for analysis to: Phone: 4/10 -5-99-3826 1364 Make sure information is complete and corroct. 100 D 136A 300 0001 222 36 B Ц 136 $\tilde{\omega}$ SSII $\widetilde{\mathbb{C}}$ Dethes の中子 SParks Detector Serial# 7638 ති ප්රි EMAIL Results to: 897 845 Structure Type: Balla 8933 Company Name: 8944 (Circle all that apply) Building Type: Address: 236 Test Site Info Site Address; Test Purpose: 3028970 897/ Send Results To: Circle One) City: ž ক 292 2 1. \diamond -٠<u>-</u>

Return canisters for analy AccuStar Labs 929 Mt. Zion Rd., Lebanor 800-523-4964	sis to: AccuStar La INFORMATION F(RECEIVED JAN 2 7 206 Projects	abs – Lebanon, PA ORM - Large Buildings s - Apartments	Instructions on back Read instructions c Discrepancies will in	k of form arefully avalidate fests
Test Site Info Name of Building/Proje Site Address:	ct or Owner Westland Middle	School	Le La Contra Con	Do not use this form in New Jersey or Florida
City:	State Zip	County		Call for correct forms.
Projects Contact Name:	· Phone:	Email:		Multi-Page Report Y-N
Detector Serial拼	NAME & NUMBER - LOCATION OF DETECTOR IN ROOM (Indicate duplicates and blanks) Floor	r Start Date Include AM/PM	Stop Date helde AMPM	Wot Gain hCill
3-30289728 100	3010602	11/1/1/ 1:5/	1/22/1 9:36	Proce Site
3028979 OB		N 1:57	V 4:37	
				1/27/2016
		Ŷ	Cl Technologies, Inc.	
		ě.	010602 3028978 ACPCZ75B	EXP12/31/2018
Structure Type: (circle one or	more) Basement - Crawispace - Slab on Grade - Other	Both Placed by and Retriev	ed by signatures are required	Certified Testers Provide #
Test Purpose: Initi	al Screening - Follow Up Test -	Canisters placed by		#
(Circle all that apply) Po	st Mitigation - Real Estate - Other			
	idential - Non Kesidential	Canisters retrieved by "		#
(urde Une) Day	ate Day Care - Private School Care in Public School - Public School	Owner waives confidentiality by signing here	Date	Were general operating
Send Results To:	*		· · / · / · /.	conditions maintained? Ves - No - exulain if NO
Company Name: UC1	Tch	Attention: Jame S.	Man N Schald COVeria	Vere closed building
Address: 956 Kida.	brock			conditions maintained?
City: Sparks	State:	MU Zip ZISZ		Yes - No explain if NO
Phone: 4/0-5 99-38	24	Fax:		Normal Temp. Yes - No
EMAIL Results to:				Normal Humidity Yes - No
Make zuro Information iz complete and o	omet. Mailing: PO Box 5	990 Jonestown, PA 17038	b by . 	Windy Y-N Rainy Y-N
If a recalculation is requested there is a t	St 0.00 rocate foo PER Cantater.	on Road, Lebanon, PA 17046		
	94-07-0-00 NEHA 10	964 Tax / 1/-2/4-5662 1511al NRSB ARL 0007		Revision S 422015



Radon in Air

NRPP 10 NRSB AF	9511AL RL0007					EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317
Labora	tory Report	for:			Property Tested:	
k 9 5	(CI Technolo)36 Ridgebro Sparks MD	ogies lok Rd 21152			MCPS Transit Blanks	
Log Number	Device Number	Test Exposu	re Duration:	:	Area Tested	Result (pCi/L)
3010588	3028953	01/19/2016 1:00 pm	01/22/2016	9:30 am	1	< 0.4
3010589	3028955	01/19/2016 1:00 pm	01/22/2016	9:30 am	2	< 0.4
3010590	3028954	01/19/2016 1:00 pm	01/22/2016	9:30 am	3	< 0.4
3010591	3028997	01/19/2016 1:00 pm	01/22/2016	9:30 am	4	< 0.4

Comment: AMENDED REPORT for 3028953-8955, 3028997 on 2/22/16 to add all missing information from the blank datasheet. A copy of this report was emailed to james.moulsdale@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 01/27/2016 Date Logged: 0

01/27/2016

Date Analyzed: 01/28/2016 Date Re

Date Reported: 01/28/2016

Report Reviewed By: Course Bates

Report Approved By: Cause A. Koko Carolyn D. Koke, President, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

PO BOX 990 Jonestown PA 17038 717-274-8310

ļ	Return canisters fr AccuStar Labs 929 Mt. Zion Rd., L 800-523-4964	or analysis to: Lebanon, PA 17046	Accus Received Jan 2006008MAT	itar Lab ION FOI ojects -	s – Lebanc RM - Large Apartmen	on, PA Buildings - its	Instr Read Discr	uctions on bac l instructions (repancies will	ck of j carefi invali	form ully idate test	8	
	Test Site Info Name of Building	g/Project or Owner	r Transit &							o not use ew Jersev	this form in or Florida	
	Site Address: 7	rans. t							: 0	all for con	ect forms.	
	City:	n	State	Zip		County			1			1
	Projects Contact	Name: Je	Carle Phone:			Email:			≥∟ ,	fulti-Page R LAB USI	sport Y-N	1
	Detector Serial#	ROOM NAME & NUM ROOM (ind	IBER - LOCATION OF DETECTOR IN Sicate duplicates and blanks)	Floor	Start Date	Start Time Include AM/PM	Stop Date	Stop Time Include AM/PM		Vgt. Gain	pCi/L	1
5	3028953	Trans, F	3010588	<u> </u>	1/1 9/1	CO.Jacits	1/22/1	9120-	æ		<0>	<u> </u>
	8955	Traws, t	3010589		1/10/16	`			3 21-		207	
6	8954	traks:+	3010590	-	7176111			/			107	
ç D	6997	Trans, F	3010591		1112/11	€		\rightarrow	~~~		124	<u> </u>
•												ſ
												1
										1071	95	-
							KCI Technold	gies, Inc.		7177	0	1
							3010588 3	028953 ACP(C275B	EXP12/31/2	018 018	
	Structure Type: 🤞	circle ane or more) Baseme	ent - Crawispace - Slab on Grade - Ot	her	Both Placed b	y and Retrieved	by signatures	are required	ر	יהי האינ	#	
	Test Purpose:	Initial Screening	- Follow Up Test -		Canisters pla	aced by					#	1
	(Circle all that apply)	Post Mitigation	- Real Estate - Other								:	
	Building Type:	Residential -	Non Residential		Canisters re	trieved by					#	- II
	(Circle One)	Private Day Car Day Care in Pub	e - Private School blic School - Public School		Owner waives c by signing here	onfidentiality	0		2	Were gene	sral operating	
	Send Results To:			·		× 0				Conattions Yes - No	maintained / explain if NC	0
	Company Name: VL Address: Q 2/2	Li Tech			Attention:	Jons 1	Mapscal !!	J		Were clos	sed building	
	City: SP., 4	S		State: A	A D Zi	0 ZIZST	~				inaliticalitaus evolain iš Ni	Ċ
	Phone: 410 - 5-2	29-3826			Fax:		a da marta antes		*	Normal Tem	o. Yes - No	5
	EMAIL Results to:	A. Jam	15. Mouls Jale O &	2.20	5					Normal Humid	ty Yes - No	
	Make sure information is con	ablete and correct.	Mailind: F	o Box 99	0 Jonestown.	PA 17038		•••		Windy Y-P	A Rainy Y-h	7
	If a recalculation is requested	d there is a \$10.00 recalc teo Pt	ER Canistor. Shipping: 92	29 Mt Zion	Road, Lebanoi	n, PA 17046 662		₹.				-
			55	U-02-020-020-0	+ 124 1 1 1-21 7-0	200					Revision 5 4/2016	

ļ

,

CLIENT KCI Technologie	s Inc. Job Number 173618
NOMINAL Conditions: Radon Conc 25.2	pCi/L Rel. Hum <u>49.1</u> % Temp. <u>79.0</u> F
Date Start: 123/16 Date Stop: 1/25/16	Date Start: Date Stop:
Time Start: OF21 Time Stop: OF21	Time Start: Time Stop:
Device No.'s: (6) Char. Cans.	Device No.'s:
302,8985 than 302,8990	
Ealdt	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
·	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft



Radon in Air

NRPP 10511AL NRSB ARL0007

Laboratory Report for:

EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Property Tested:

KCI Technologies 936 Ridgebrook Rd Sparks MD 21152

MCPS Radon Spike Sample Laboratory Results

Log Number	Device Number	Test Exposu	re Duration:	Area Tested	Result (pCi/L)
3010551	3028985	01/23/2016 8:20 am	01/25/2016 8:20 am	1 First Floor	24.2
3010552	3028986	01/23/2016 8:20 am	01/25/2016 8:20 am	2 First Floor	25.7
3010553	3028987	01/23/2016 8:20 am	01/25/2016 8:20 am	3 First Floor	23.8
3010554	3028988	01/23/2016 8:20 am	01/25/2016 8:20 am	4 First Floor	23.3
3010555	3028989	01/23/2016 8:20 am	01/25/2016 8:20 am	5 First Floor	24.0
3010556	3028990	01/23/2016 8:20 am	01/25/2016 8:20 am	6 First Floor	24.4

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

Comment: A copy of this report was emailed to james.moulsdale@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 01/27/2016 Date Logged: 01/27/2016

Date Analyzed: 01/28/2016 Date Reported:

01/28/2016

Report Reviewed By: _______

Report Approved By:

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

PO BOX 990 Jonestown PA 17038 717-274-8310

Page 1 of 1

Return canisters AccuStar Labs 929 Mt. Zion Rd., 800-523-4964	for analysis to: Lebanon, PA 17046 RECEIVED JAN	AccuStal INFORMATION 2 7 2016 Proje	r Labs – Leband V FORM - Large ects - Apartmen	on, PA Buildings - its	Instr Read Discr	ictions on back instructions ca epancies will ii	t of form urefully rvalidate tests	
lest Site Info							Do not use this fam	
Site Address: Z.	19/ Project or Owner 1°10 PS						New Jersey or Flori	ida ida
City: Rucku	in ms	State MD Zi	05802 d	County Ment	10 Million	-	Call for correct forn	ms.
Projects Contact	I Name: Jomes Nouls No	Phone: 410	- 591-1842	Email: Jame	s. monts deler	Oker. can	Multi-Page Report Y-]	z
Detector Serial#	ROOM NAME & NUMBER - LOCATIO ROOM (indicate duplicates ar	N OF DETECTOR IN dianks) FI	oor Start Date	Start Time	Stop Date	Stop Time		
1 3028935	•	3010551	1/23/16	00:20	112511			
3028986	2	3010552	-	0222	9/10-1-	00.20	2	Ł
302 39 87	3	3010553			-			
3028988	4	3010554				-		
302 8989	5	3010555				_		
307 8990	ç	3010556	->					
								T
								7
Test Durnoror	arcte one or more) Basement - Crawlspace	- Slab on Grade - Other	Both Placed by	and Retrieved I	oy signatures∕a	re required	Certified Testers Provide	# •
Circle all that apply	Post Mitration Bool Environment) lest -	Canisters pla	bed by	mes lle	Z	#	
Building Type:	Residential - Non Residentia	ale - Uther	Canisters retr	ieved hv	here a			
(Circle One)	Private Day Care - Private Sc		Ourner weiting		- I VAT		++	
	Day Care in Public School -{	Public School	by signing here	an and the second s		Date	Were general operati	gui
Send Results To:	-						conditions maintained	ç;
Company Name: F Address: 926	CT Technologing Inc		Attention: Ja	Inell SM	دراه		Were closed building	2
City: Sparl	< MD ZIIST	Ctata	i				conditions maintained	d?
Phone: f'_{10} -	891-1842	0.04	Fax:			1/27/2016	TYes - No explain if	g
EMAIL Results to: _	vitimes mevisdule (~ icc)	, com	Š	l Technologies	, Inc.		Vormal Temp.	on So
Make sure information is com; If a receiculation is requested i	plote and corroct. there is a \$10.00 rocale foe PER Canister.	Mailing: PO Bo Shipping: 929 Mt	x 990 Jonesti 30 Zion Road, Let	10551 302 8	985 ACPCZ75	5 EXP12/31/2018	Windy Yen Rainy Y	<u></u>
		800-523- NEHA	4964 fax 717-2 10511al NRSB ARL 0007				Rovision 5 zeron 5	

ŧ

\$102/9



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS 936 Ridgebrook Road • Sparks, MD 21152 • 410-316-7800 • (Fax) 410-316-7935

MCPS RADON TESTING

Executive Summary: Westland Middle School

Date of Test Report:	1/6/2016 (Rev1)
Round of Testing:	Initia
	Follow-up
	Post Remediation
# Rooms Tested:	65
# Rooms \geq 4.0 pCi/L:	3
Low Value:	< 0.3
High Value:	6.2

Rooms with results \geq 4.0 pCi/L: Room 137 (6.2 pCi/L), Room 136C (5.0 pCi/L), Room 100D (4.7 pCi/L)

 $\label{eq:project Status:} Initial testing completed; re-test needed for results \geq 4.0 \ pCi/L. Initial testing completed; missing or compromised samples need re-test.$

KCI TECHNOLOGIES, INC.

www.kci.com

Imployee the ard Societ 1988

Mr. Richard Cox January 6, 2015 Page 3

is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room during the deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
	137	6.2	
≥4.0 piC/L	136C	5.0	
	100D	4.4, 4.7(D)	
<4.0 piC/L	See Attachment B		

Notes: D- Duplicate sample

All field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC.

Mr. Richard Cox January 6, 2015 Page 4

Sincerely,

٠,

James Makles-

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

	;	
Attachments:		A- Floor Plan with Test Locations B- Table 1-Radon Test Summary Spreadsheet
	:	C- Laboratory Analytical Results

M:\2014\12146341.19\Reports\Westland MS\MCPS radon letter report- Westland MS.doc

KCI TECHNOLOGIES, INC.

www.kci.com

ATTACHMENT A

.

Floor Plan With Test Locations

ATTACHMENT B

.

Radon Test Summary Spreadsheet

.

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Radon Testing Results				
	Westland MS			
Tes	t Period: 12/15/15-12/18/15			
Kit Number	Room/Area	Result		
7704047	102	0.7		
7704387	106	0.8		
7704378	107	1.3		
7704382	109	0.6		
7704392	110	< 0.3		
7704363	112	0.5		
7704100	113	< 0.3		
7704372	114	< 0.3		
7704089	115	< 0.3		
7704082	116	< 0.3		
7704090	117	1		
7704092	118	< 0.3		
7704096	121	0.7		
7704098	122	1		
7704080	124	0.9		
7704060	125	1.8		
7704099	125	1.9		
7704086	126	2.3		
7704065	128	0.8		
7704052	129	0.8		
7704066	130	0.7		
7704072	131	0.6		
7704068	132	< 0.3		
7704077	133	0.9		
7704058	134	1.4		
7704057	135	1.4		
7704074	137	6.2		
7704051	143	1.7		
7704067	143	1.4		
7704059	145	2.1		
7704095	150	1.5		
7704070	151	1.5		
7704087	152	2.1		
7704081	214	1.5		
7704043	222	< 0.3		
7704062	* 229 (Open Window)	1.3		
7704056	100A	1.2		
7704061	100B	1.5		
7704091	100C	1.5		
7704079	100D	4.4		
7704041	100E	2.9		
7704015	100F	1.6		
7704016	100G	1.1		
7704009	100H	1		

,

* Missing or Compromised Sample

	Radon Testing Results				
	Westland MS				
Test	t Period: 12/15/15-12/18/15				
Kit Number	Room/Area	Result			
7704379	105 OFFICE	0.8			
7704071	126A	2.1			
7704075	126B	2.2			
7704053	126C	2.3			
7704078	127A	< 0.3			
7704094	127B	< 0.3			
7704064	127C	< 0.3			
7704093	127D	0.7			
7704073	131B	0.9			
7704055	* 136A (Tampered)	0.6			
7704054	136B	3,9			
7704044	136C	5			
7704036	136D	2.1			
7704037	136E	2.7			
7704063	136F	2.2			
7704038	136G	2.3			
7704069	143B	1			
7704076	143B	1.1			
7704049	CAF	< 0.3			
7704050	CAF	0.6			
7704084	MED CENTER	1.3			
Kit Number	Room/Area	Result			
7704385	D (107)	1			
7704097	D (121)	0.9			
7704088	D (125)	1.6			
7704085	D (151)	1.4			
7704048	* D (229:Open Window)	0.9			
7704013	D (100D)	4.7			
7704017	D (100H)	0.8			
7704377	FB (112)	< 0.3			
7704083	FB (125)	< 0.3			
7704014	FB (100D)	< 0.3			
7708206	OB (OFFICE BLANK)	< 0.3			

•

ł

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

December LABORATORY ANALYSIS 30, REPORT **

Radon test result rep	<u>port for:</u>
WESTLAND N	I.S.
MAIN	:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7704056	100A	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.2 ± 0.4	2015-12-22
7704061	100B	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.5 ± 0.3	2015-12-22
7704091	100C	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.5 ± 0.4	2015-12-22
7704013	100D	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	4.7 ± 0.5	2015-12-22
7704079	100D	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	4.4 ± 0.5	2015-12-22
7704014	100D	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704041	100E	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	2.9 ± 0.4	2015-12-22
7704015	100F	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.6 ± 0.4	2015-12-22
7704016	100G	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.1 ± 0.4	2015-12-22
7704009	100H	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.0 ± 0.4	2015-12-22
7704017	100H	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.8 ± 0.4	2015-12-22
7704047	102	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	0.7 ± 0.3	2015-12-22
7704379	105 OFFICE	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	0.8 ± 0.3	2015-12-22
7704387	:106	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	0.8 ± 0.3	2015-12-22
7704378	107	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	1.3 ± 0.4	2015-12-22
7704385	107	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	1.0 ± 0.3	2015-12-22
7704382	109	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	0.6 ± 0.3	2015-12-22
7704392	110	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	< 0,3	2015-12-22
7704363	112	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	0.5 ± 0.3	2015-12-22
7704377	112	2015-12-15 @ 9:00 am	2015-12-18 @ 8:00 am	< 0.3	2015-12-22
7704100	113	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	< 0.3	2015-12-22
7704372	114	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	< 0.3	2015-12-22
7704089	115	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	< 0,3	2015-12-22
7704082	,116	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	< 0.3	2015-12-22
7704090	.117	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	1.0 ± 0.3	2015-12-22
7704092	118	2015-12-15 @ 10:00 am	2015-12-18 @ 8:00 am	< 0.3	2015-12-22
7704096	121	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	0.7 ± 0.3	2015-12-22
7704097	121	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7704098	122	2015-12-15 @ 10:00 am	2015-12-18 @ 10:00 am	1.0 ± 0.3	2015-12-22
7704080	124	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	0.9 ± 0.4	2015-12-22
7704083	125	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704088	125	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	1.6 ± 0.4	2015-12-22
7704099	125	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	1.9 ± 0.4	2015-12-22
7704060	125	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	1.8 ± 0.4	2015-12-22
7704086	126	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.3 ± 0.4	2015-12-22
7704071	126A	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.1 ± 0.4	2015-12-22
7704075	126B	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.2 ± 0.4	2015-12-22
. **		한 이상 이 나는 것이 가지 않는 것이 있었다.	비로 제작 전통 전 가격 관계가		승규는 것은 것이 같아요.

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Decensive LABORATORY ANALYSIS 30, REPORT ** 30, 2015

.

.

Radon test result report for: WESTLAND M.S. MAIN

Kit #	Room Id	Started	Ended	p Ci/L	Analyzed
7704053	126C	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.3 ± 0.4	2015-12-22
7704078	127A	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704094	127B	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704064	127C	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704093	127D	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.7 ± 0.3	2015-12-22
7704065	128	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.8 ± 0.3	2015-12-22
7704052	129	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.8 ± 0.3	2015-12-22
7704066	130	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.7 ± 0.3	2015-12-22
7704072	131	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.6 ± 0.3	2015-12-22
7704073	131B	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7704068	132	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704077	133	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7704058	134	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.4 ± 0.4	2015-12-22
7704057	135	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	1.4 ± 0.4	2015-12-22
7704055	136A	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	0.6 ± 0.3	2015-12-22
7704054	136B	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	3.9 ± 0.4	2015-12-22
7704044	136C	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	5.0 ± 0.5	2015-12-22
7704036	136D	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	2.1 ± 0.4	2015-12-22
7704037	136E	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	2.7 ± 0.4	2015-12-22
7704063	136F	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	2.2 ± 0.4	2015-12-22
7704038	136G	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	2.3 ± 0.4	2015-12-22
7704074	137	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	6.2 ± 0.5	2015-12-22
7704067	143	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	1.4 ± 0.4	2015-12-22
7704051	143	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	1.7 ± 0.4	2015-12-22
7704069	143B	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	1.0 ± 0.3	2015-12-22
7704076	143B	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	1.1 ± 0.3	2015-12-22
7704059	145	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.1 ± 0.4	2015-12-22
7704095	150	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	1.5 ± 0.4	2015-12-22
7704070	151	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	1.5 ± 0.4	2015-12-22
7704085	151	2015-12-15 @ 10:00 am	2015-12-18 @ 10:00 am	1.4 ± 0.3	2015-12-22
7704087	152	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	2.1 ± 0.4	2015-12-22
7704081	214	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	1.5 ± 0.4	2015-12-22
7704043	222	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704048	229	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7704062	229	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	1.3 ± 0.3	2015-12-22
7704049	CAF	2015-12-15 @ 1:00 pm	2015-12-18 @ 1:00 pm	< 0.3	2015-12-22
7704050	CAF	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.6 ± 0.3	2015-12-22
	te de Melle		이 집에 가장 아파는 것이 같은 것이 같아.	요즘 감독을 가야가 물었다.	그는 사람의 호흡 눈가 같아

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

.

December LABORATORY ANALYSIS 30, REPORT **

Radon test result report for: WESTLAND M.S. MAIN

.

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498	d Ended pCl/L Analyzed 15 @ 10:00 am 2015-12-18 @ 9:00 am 1.3 ± 0.3 2015-12-22	Kit # Room Id 7704084 MED CENTER
	e Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498	Air Chek, Inc. 1936
		· ·
		:
		· ·
		-
		<u>:</u>
		-
		:
		: ±
		· ·
		:
		:
		· ·

December LABORATORY ANALYSIS 30, REPORT **

Radon test result report for: WESTLAND M.S. OFFICE BLANK

, ,

Kit#_	Room Id	Started		Ended		pCi/L	Analyzed
7708206 OF	FICE BLANK	2015-12-15 (@ 3:00 pm	2015-12-18	3:00 pm	< 0.3	2015-12-22

Air Chek, Inc.	1936 Butler Bridge Rd,	Mills River,	NC 28759-3892	Phone: (828) 684-0893 Fax: (828) 684-8498
-				
•				
:				
:				
1				
:				
•				
:				
- - -				

Decensber 29, 2015 **REPORT ****

:

Radon test result report for: TRANSIT DEC 14 2015 NONE

Kit # Room	Id Started	Ended	pCi/L A	nalyzed
7704395 TRANSI	(T 1 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706508 TRANSI	T 10 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706510 TRANSI	T 11 2015-12-13 @ 10:00 a	um 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706511 TRANSI	T 12 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706505 TRANSI	T 13 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704371 TRANSI	T 14 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706506 TRANSI	Т 15 2015-12-13 @ 10:00 а	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704381 TRANSI	T 16 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704399 TRANSI	T 17 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704390 TRANSI	т 18 2015-12-13 @ 10:00 а	am — 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704396 TRANSI	T 2 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704364 TRANSI	T 3 2015-12-13 @ 10:00 a	um 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704370 TRANSI	IT 4 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7704368 TRANSI	IT 5 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706524 TRANSI	IT 6 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706526 TRANSI	IT 7 2015-12-13 @ 10:00 a	am 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706518 TRANSI	IT 8 2015-12-13 @ 10:00 a	um 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
7706516 TRANSI	IT 9 2015-12-13 @ 10:00 a	um 2015-12-15 @ 10:00 am	< 0.3 201	5-12-16
	n a san kapérék	terre interrettion		

Air Chek, Inc. 1936 Butter Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

.

Decembe	LABORATORY ANALYSIS
43,	DEDODT **
2015	KEPOKI **

ı

PS	-				
Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7706380	: 101	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	25.2	2015-12-23
7706381	102	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706208	103	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	27.7	2015-12-23
7705132	104	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	28.6	2015-12-23
7706366	105	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706211	106	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.1	2015-12-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER					
CLIENT KCI Technologies	the.	Job Number 173224	_		
NOMINAL Conditions: Radon Conc 26.9	pCi/L Rel. Hum	49.6 % Temp. 69.9	F		
Date Start: $12 18115$ Date Stop: $12 211(5)$	Date Start:	Date Stop:			
Time Start: <u>(1929</u> Time Stop: <u>(1929</u>	Time Start:	Time Stop:			
Device No.'s: <u>7705132</u> ,7706208	, Device No.'s:_				
7706211,7706366,					
7706380, 7706381					
F <u>3 (cf</u> +					
Date Start: Date Stop:	Date Start:	Date Stop:			
Time Start: Time Stop:	Time Start:	Time Stop:			
Device No.'s:	Device No.'s:_				
: 					
	r 				
Date Start: Date Stop:	Date Start:	Date Stop:			
Time Start: Time Stop:	Time Start:	Time Stop:			
Device No.'s:	Device No.'s:				
		·			

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft

1

M. A. CECIL & ASSOCIATES, INC. 4475 Shannon Way, Port Republic, Maryland 20676 (301) 855-7710 INDUSTRIAL HYGIENE AND ENVIRONMENTAL HEALTH

MCPS RADON TESTING

Executive Summary

Name of Facility	Westland Middle			
Date of Test report	December 24, 2015			
Round of Testing	Re-Test			
Number of rooms tested	2			
Number of room $>/= 4.0$	0			
Low value	1.1			
High value	1.2			

M. A. CECIL & ASSOCIATES, INC.

4475 Shannon Way, Port Republic, Maryland 20676 (301) 855-7710 INDUSTRIAL HYGIENE AND ENVIRONMENTAL HEALTH

December 24, 2015

е., r

Mr. Sean Yarup Montgomery County Public Schools 16651 Crabbs Branch Way Rockville, Maryland 20855

Re: Radon Evaluation - Westland Middle School

Dear Mr. Yarup:

Follow-up environmental radon testing has been completed at Westland Middle School.

Two charcoal canisters were placed in the Auxiliary Gym and Main Gym. The canisters were placed on December 9, 2015 and retrieved on December 11, 2015.

The detected radon concentrations were below the EPA recommended level of 4.0 pico curies per liter (pCi/l). Testing locations and results are summarized in the table below.

Location	Detected Radon
	Concentration (pCi/l)
Aux. Gym	1.1
Gym	1.2

Should you have any questions concerning this report please do not hesitate to contact us.

Sincerely,

Michael A. Cecil Michael A. Cecil, CIH

÷