

School / Facility Radon Testing Report Form

School Year: **24-25**

Facility:	Parkside Center		
Address:	9500 Brunett Avenue		
	Silver Spring, MD 20901		
Reason for Testing:	Scheduled Re-Testing - <input type="checkbox"/> 2-year or <input checked="" type="checkbox"/> 5-year schedule <input type="checkbox"/> Clearance Testing (Post-Mitigation) <input type="checkbox"/> Building Envelope or HVAC Upgrades <input type="checkbox"/> New Construction – Addition or Facility		
Current Radon Status:	<input type="checkbox"/> Active Mitigation (2-year regular schedule) <input checked="" type="checkbox"/> No Active Mitigation (5-year regular schedule) <input checked="" type="checkbox"/> Not Previously Tested (New Facility)		
Round of Testing:	<input checked="" type="checkbox"/> Initial Testing -or- <input type="checkbox"/> Follow-up Testing		
Testing Status:	<input checked="" type="checkbox"/> No Further Testing Needed -or- <input type="checkbox"/> Follow-Up Testing Required		

Conclusion (When Testing Status is - No Further Testing Needed)

Mitigation -	Facility Radon Status:		
<input type="checkbox"/> Not Required <input checked="" type="checkbox"/> Required (≥ 4.0 -pCi/L) Rooms: Entire Facility	<input type="checkbox"/> No Change in Status <input checked="" type="checkbox"/> Active Mitigation (2-year regular schedule) <input type="checkbox"/> No Active Mitigation (5-year regular schedule)		
Number of Rooms Tested	51	Lowest Value (pCi/L)	< 0.3
Number of Rooms (≥ 4.0 -pCi/L)	32	Highest Value (pCi/L)	7.8

Instructions: Submit one testing report form per-facility. Include the following as attachments:

Attachment 1- Summary Data Tables – containing the following: (see attached samples tables)

- Testing Results – lab/detector Identification, by room number/name (alpha-numeric order) as depicted on facility map/floor plan provided by the facility/school at the time of test device deployment;
- Summary Results – list of rooms by test result ≥ 2.0 -pCi/L; ≥ 2.7 -pCi/L; ≥ 4.0 -pCi/L; and ≥ 8.0 -pCi/L;
- QA/QC Results - (field blanks and duplicates) indicating location collected; trip and office blanks; and spike sample results;
- Invalid Measurement Locations – missed locations, missing and or damaged/compromised testing devices.

Attachment 2 – Laboratory Report(s)

Attachment 3 – Sampling Location Map(s) – indicating approximate location of samples, duplicates and blanks.

Detector and Deployment

Detector/Device Type:	<input checked="" type="checkbox"/> Passive	<input checked="" type="checkbox"/> Charcoal Absorption (CAD) <input type="checkbox"/> Alpha Track (ATD) <input type="checkbox"/> Other
	<input type="checkbox"/> Continuous	<input type="checkbox"/> Electret ion Chamber (EIC) <input type="checkbox"/> Electronic Integration (EID)
Other—Specify here:		
Detector/Device Name:	Air Chek – Radon Test Kits	
Manufacturer:	Radon Lab	
Person(s) Deploying or Retrieving Test Devices and certification number		Organization/Company
Brittany Maas		KCI Technologies, Inc.
If noncertified individuals, the qualified measurement professional providing oversight -		
Tyler McCleaf, CSP – Cert. #111004-RMP		KCI Technologies, Inc.

Testing

<input checked="" type="checkbox"/> Short-Term <input type="checkbox"/> Long-Term	Length of Test (days):	3	Date of Deployment and Retrieval (mm/dd/yy):	01/12/2025 01/16/2025
Does the test period include weekends, school breaks or holidays?				<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
If “Yes” please explain/detail in the space below:				
Was HVAC operating under occupied conditions?				<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
If “No” please explain/detail in the space below: Facility was newly acquired for MCPS use and was not occupied during testing; HVAC system was in use to ensure normal indoor temperature.				

Testing (continued)

Round of Testing	Detectors Deployed				
	Ground-Contact		Upper-Level(s)		Total
	Initial	Follow-Up	Initial	Follow-Up	
Test Locations ¹	51	0	0	0	51
Duplicates ²	5	0	0	0	5
Field Blanks ³	2	0	0	0	2
Grand Total					58

1 – include all detectors deployed (duplicates, field blanks); 1 detector per occupied (or intended to be occupied) ground-contact space ≤ 2,000-square feet; large spaces ≥ 2,000-square feet - 1 detector per 2,000-square feet or part thereof; and upper floors - 10% of all occupied or intended to be occupied rooms per floor (these are in addition to ground contact locations)

2 - 10% of all locations tested, per floor

3 – 5% of all locations tested, per floor

Quality Assurance / Quality Control (QA/QC)

A Quality Assurance plan that is consistent with ANSI/AARST MS-QA (Radon Measurement Systems Quality Assurance) was submitted under separate cover, and is available to review at the MCPS Radon Testing and Mitigation Program website. The following number of QA/QC samples are associated this facility.

Round of Testing	QA/QC Samples		Total
	Initial	Follow-Up	
Spikes ¹	Not applicable		3
Trip Blanks ²	1	0	1
Office Blanks ^{3, 4}	1	0	1
			5

1 - 3% of EIC detectors; and 3% from each LOT of CAD and ATD detectors; a maximum of 6-spiked measurements per month for both EIC detectors and each LOT of CAD and ATD detectors.

2 – One per shipping container from start of detector deployment

3 – One per facility tested as devices are removed/allocated from the storage location for deployment;

4 - One additional blank, analyzed prior to deployment, for storage locations that have not been evaluated or monitored, for detectors that have been stored for more than 30-day durations.

Quality Assurance / Quality Control (continued)

Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Quality Control measurements comply with QA/QC requirements in the submitted testing organization's/company's QA plan?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Round of Testing	Initial Follow-Up
All Field, Trip and Office Blanks are \leq (less than or equal to) to the Method Detection Limit?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No
For all Duplicate Samples ¹ , the higher value is $\leq 2x$ the lower value?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No
For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are less than the Warning Level ³ ?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No
For all Duplicate Samples ¹ , Relative Percent Difference(s) (RPD) ² are less than the Control Level ³ ?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No

1 – Duplicate Control – a “NO” response constitute a control failure and the space/location represented by the duplicate sample becomes an invalid measurement location and should be listed in the “Invalid Measurement Locations” Table attached to this report.

2 - The objective of duplicate tests is to assess the precision error of the measurement method or, how well two side-by-side measurements agree or disagree. Precision involving duplicates is calculated by using Relative Percent Difference (RPD). RPD is equal to the difference between the higher test result minus the lower value test result divided by the average of the two duplicate test results, multiplied by 100. The RPD result is then compared to the warning and control limits.

3 - The Warning Level is set at the deviation from ideal performance that would be expected to occur by chance only 5% of the time, and Control Limits are set at that deviation from ideal performance that would be expected to occur by chance only 1% of the time. The Warning Level indicates a potential problem, which should be investigated. The Control Level indicates that the measurement system should be subject to corrective action.

The control and warning levels for duplicates, based on the averaged duplicate test result, are -

Average concentration of the two duplicate test results	Warning Level	Control Level
< 2.0-pCi/L	1-pCi/L	Not applicable
Between 2.0 and 3.9-pCi/L	50% RPD	67% RPD
≥ 4.0 -pCi/L	28% RPD	36% RPD

Summary of Test Results¹ and Determination of Valid Measurements²

Round of Testing	Ground-Contact		Upper-Level(s)		Total
	Initial	Follow-Up	Initial	Follow-Up	
Number of test locations:	51	0	0	0	51
Number of locations ≥ 8.0 -pCi/L:	0	0	0	0	0
Number of locations ≥ 4.0 and ≤ 8 -pCi/L:	32	0	0	0	32
Number of locations ≥ 2.7 and < 4 -pCi/L:	17	0	0	0	17
Number of locations ≥ 2.0 and < 2.7 -pCi/L:	1	0	0	0	1
Number of missing required test locations ³ :	0	0	0	0	0
Number of failed duplicate control locations:	0	0	0	0	0
Percentage of missing test locations for the facility ^{4,5} :	0%	0%	0%	0%	0%

1 – for locations with multiple test results, report consistent with Section 7.2(When Two Test Results Disagree) and 8.1.2 (Averaging) of ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings;

2 - the allowance is to be calculated individually for Ground-Contact and Upper-Level(s) Test Locations;

3 – includes missed or inaccessible locations upon deployment or retrieval, damaged (not able to analyze) and missing detectors upon retrieval;

4 – if all valid measurements are < 4.0 -pCi/L and the total number of test locations are ≥ 18 , there is an allowance of $\leq 33\%$. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023;

5 – if any valid measurements are ≥ 4.0 -pCi/L and the total number of test locations are ≥ 20 , there is an allowance of $\leq 25\%$ of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023.

Summary of Test Results¹ and Determination of Valid Measurements² (continued)

Round of Testing	Initial	Follow-Up
Were test devices deployed in all occupied and intended to be occupied rooms in contact with the ground, and, if applicable, 10% of upper floor rooms?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Were valid measurements obtained in all occupied and intended to be occupied rooms in contact with the ground, and, if applicable, 10% of upper floor rooms?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
<i>If Yes to both above – then Testing Status – ‘No Further Testing Needed’ mark ‘NA’ below and complete Conclusions section</i>		
If No to either above, were all results obtained under 4.0-pCi/L and were sufficient valid measurements obtained?^{1,2} If Yes, then - ‘No Further Testing Needed’ complete Conclusion section on first page. If No, then - ‘Follow-up Testing Required’ continue below.	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA

1 – if all valid measurements are <4.0-pCi/L and the total number of test locations are ≥18, there is an allowance of ≤33%. If less than 18 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the allowance;
 2 – if any valid measurements are ≥4.0-pCi/L and the total number of test locations are ≥20, there is an allowance of ≤25% of the total locations tested. If less than 20 test locations please review section 6.2 of the ANSI/AARST MA-MFLB 2023 – Conducting Measurements of Radon in Multifamily, School, Commercial and Mix-Use Buildings to determine the number the allowance.

Follow-Up Testing

Required –

- If an insufficient number (greater than the allowance provided above) of valid measurements were obtained during the initial round of testing (the “missing required test locations” in the table above);
- Any location test results ≥ 4.0-pCi/L;
- Any location where duplicates fail QC checks; and or
- At the discretion of MCPS IAQ Staff

Reason for Follow-Up Testing	Testing Procedure	Follow-up Result	Conclusion
Insufficient Number of Measurements	Follow same procedures as Initial Testing	Not Applicable	Follow Initial Testing procedures
Results ≥ 4.0-pCi/L	Deploy two Short-term follow-up tests and required blanks and duplicates; Average the results of the two tests	≥4.0	Mitigation Required
Failed QC checks		≥2.0 and <4.0	Consider Mitigation
		<2.0	Mitigation Not Required

- **If follow-up testing identifies additional spaces requiring additional testing it will be performed as part of the ongoing follow-testing round.**

Attachment 1:

Summary Data Tables

Table 1- Radon Testing Results		
Parkside Center		
Test Period: 1/12/2025 - 1/16/2025		
Kit Number	Room / Area	Result
11906856	104	2.1
11892894	105	3.7
11906858	108	3.5
11892867	112	3.1
11892898	120	5.3
11903952	123	3.3
11906866	124	3.2
11906865	128	3.7
11906850	144	7.8
11906862	104 OFFICE	1.8
11906874	105A	4.3
11892886	105B	3.5
11892887	105C	5.2
11892888	105D	2.9
11892860	105D	3.2
11906864	105D	< 0.3
11892892	105E	3.4
11892880	105F	3.2
11892891	105G	3.5
11906863	105H	4.6
11906857	108A	3.8
11906805	108B	4.4
11906861	108B	5.0
11892895	108C	4.7
11906869	108D	5.3
11892893	108E	3.3
11892896	120 OFFICE	4.4
11906867	A100	5.4
11893089	A101	5.2
11893087	A102	4.9
11892876	A103	5.1
11893088	A104	5.3
11906870	A105	5.2
11892889	A106	4.3
11892890	A106	4.8
11906868	A106	< 0.3
11892859	A107	5.0

Table 1- Radon Testing Results		
Parkside Center		
Test Period: 1/12/2025 - 1/16/2025		
Kit Number	Room / Area	Result
11892884	A108	4.7
11892883	A109	4.3
11892881	A110	4.1
11906873	A111	4.4
11892875	A112	4.1
11892868	A113	4.0
11892866	A114	3.4
11892885	A124	3.7
11893095	B101	5.6
11893079	B101A	4.2
11903958	B101A	4.8
11903944	B102	5.1
11892874	B104	4.4
11893096	B105	4.5
11892879	B107	4.7
11893098	B108	6.1
11893097	B109	4.6
11893093	B110	5.0
11892897	B111	3.7
11892882	B111	3.8
11906849	LIBRARY	0.9

Table 2 - Summary Testing Results ≥ 2.0 pCi/L							
Parkside Center							
Test Period: 1/12/2025 - 1/16/2025							
≥ 2.0 and < 2.7 pCi/L		≥ 2.7 and < 4.0 pCi/L		≥ 4.0 and < 8.0 pCi/L		≥ 8.0 pCi/L	
Room / Area	Result	Room / Area	Result	Room / Area	Result	Room / Area	Result
104	2.1	105D	2.9	A113	4.0	N/A	N/A
		112	3.1	A110	4.1		
		124	3.2	A112	4.1		
		105D	3.2	B101A	4.2		
		105F	3.2	105A	4.3		
		123	3.3	A106	4.3		
		108E	3.3	A109	4.3		
		105E	3.4	108B	4.4		
		A114	3.4	120 OFFICE	4.4		
		108	3.5	A111	4.4		
		105B	3.5	B104	4.4		
		105G	3.5	B105	4.5		
		105	3.7	105H	4.6		
		128	3.7	B109	4.6		
		A124	3.7	108C	4.7		
		B111	3.7	A108	4.7		
		108A	3.8	B107	4.7		
		B111	3.8	A106	4.8		
				B101A	4.8		
				A102	4.9		
				108B	5.0		
				A107	5.0		
				B110	5.0		
				A103	5.1		
				B102	5.1		
				105C	5.2		
				A101	5.2		
				A105	5.2		
				120	5.3		
				108D	5.3		
				A104	5.3		
				A100	5.4		
				B101	5.6		
				B108	6.1		
				144	7.8		

Table 3 - QC Radon Testing Results			
Parkside Center			
Test Period: 1/12/2025 - 1/16/2025			
Kit Number	QC Type	Room / Area	Result
11892860	D	105D	3.2
11906864	FB	105D	< 0.3
11906805	D	108B	4.4
11892890	D	A106	4.8
11906868	FB	A106	< 0.3
11903958	D	B101A	4.8
11892882	D	B111	3.8
11906877	OB	OFFICE BLANK	< 0.3
11903993	TB	TRAVEL BLANK	< 0.3

Table 3a - Duplicate Worksheet / Data Validation										
Parkside Center										
Test Period: 1/12/2025 - 1/16/2025										
Sample ID			Duplicate Concentrations (pCi/L) and OC Checks							
Kit Numbers		Room / Area	Higher	Lower	Check #1 (Pass/Fail)	2x the Lower	Check #2 (Pass/Fail)	Average	Relative Percent Difference (RPD)	Check #3
11906861	11906805	108B	5.0	4.4	✓	8.8	PASS	4.7	12.8%	✓
11892888	11892860	105D	3.2	2.9	✓	5.8	PASS	3.1	9.8%	✓
11892897	11892882	B111	3.8	3.7	✓	7.4	PASS	3.8	2.7%	✓
11892889	11892890	A106	4.8	4.3	✓	8.6	PASS	4.6	11.0%	✓
11893079	11903958	B101A	4.8	4.2	✓	8.4	PASS	4.5	13.3%	✓
NOTES: QC Check #1 - Data Entry QC Check #2 - Higher duplicate concentration is < or = to 2x the Lower QC Check #3 - Meets RPD Limits, by average duplicate concentration - enter 2 if RPD is BELOW warning and control levels, AND passes QC Check 1 and 2 - enter 1 if RPD is ABOVE warning and BELOW control levels, AND passes QC Check 1 and 2 - enter 0 if RPD is ABOVE control level, or 'FAILS' QC Check 1 or 2							Average (pCi/L)		Warning Level	Control Level
							< 2.0		1-pCi/L	NA
							Between 2.0 and 3.9		50% RPD	67% RPD
							≥ 4.0		28% RPD	36% RPD

[illegible]

Attachment 2:

Laboratory Reports

Radon test result report for:
PARKSIDE CENTER
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11906856	104	2025-01-13 @ 11:00 am	2025-01-16 @ 10:00 am	2.1 ± 0.4	2025-01-20
11906862	104 OFFICE	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	1.8 ± 0.3	2025-01-20
11892894	105	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.7 ± 0.4	2025-01-20
11906874	105A	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.3 ± 0.4	2025-01-20
11892886	105B	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.5 ± 0.4	2025-01-20
11892887	105C	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.2 ± 0.4	2025-01-20
11906864	105D	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	< 0.3	2025-01-20
11892860	105D	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.2 ± 0.4	2025-01-20
11892888	105D	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	2.9 ± 0.4	2025-01-20
11892892	105E	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.4 ± 0.4	2025-01-20
11892880	105F	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.2 ± 0.4	2025-01-20
11892891	105G	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.5 ± 0.4	2025-01-20
11906863	105H	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.6 ± 0.4	2025-01-20
11906858	108	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.5 ± 0.4	2025-01-20
11906857	108A	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.8 ± 0.4	2025-01-20
11906805	108B	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.4 ± 0.4	2025-01-20
11906861	108B	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.0 ± 0.4	2025-01-20
11892895	108C	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.7 ± 0.4	2025-01-20
11906869	108D	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.3 ± 0.4	2025-01-20
11892893	108E	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.3 ± 0.4	2025-01-20
11892867	112	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.1 ± 0.4	2025-01-20
11892898	120	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.3 ± 0.4	2025-01-20
11892896	120 OFFICE	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.4 ± 0.4	2025-01-20
11903952	123	2025-01-13 @ 11:00 am	2025-01-16 @ 10:00 am	3.3 ± 0.4	2025-01-20
11906866	124	2025-01-13 @ 11:00 am	2025-01-16 @ 10:00 am	3.2 ± 0.4	2025-01-20
11906865	128	2025-01-13 @ 11:00 am	2025-01-16 @ 10:00 am	3.7 ± 0.4	2025-01-20
11906850	144	2025-01-13 @ 11:00 am	2025-01-16 @ 10:00 am	7.8 ± 0.6	2025-01-20
11906867	A100	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.4 ± 0.4	2025-01-20
11893089	A101	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.2 ± 0.4	2025-01-20
11893087	A102	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.9 ± 0.4	2025-01-20
11892876	A103	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.1 ± 0.4	2025-01-20
11893088	A104	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.3 ± 0.4	2025-01-20
11906870	A105	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.2 ± 0.4	2025-01-20
11892890	A106	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.8 ± 0.4	2025-01-20
11906868	A106	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	< 0.3	2025-01-20
11892889	A106	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.3 ± 0.4	2025-01-20
11892859	A107	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.0 ± 0.4	2025-01-20

January 20, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
**PARKSIDE CENTER
MAIN**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11892884	A108	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.7 ± 0.4	2025-01-20
11892883	A109	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.3 ± 0.4	2025-01-20
11892881	A110	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.1 ± 0.4	2025-01-20
11906873	A111	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.4 ± 0.4	2025-01-20
11892875	A112	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.1 ± 0.4	2025-01-20
11892868	A113	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.0 ± 0.4	2025-01-20
11892866	A114	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.4 ± 0.4	2025-01-20
11892885	A124	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.7 ± 0.4	2025-01-20
11893095	B101	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.6 ± 0.4	2025-01-20
11903958	B101A	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.8 ± 0.4	2025-01-20
11893079	B101A	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.2 ± 0.4	2025-01-20
11903944	B102	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.1 ± 0.4	2025-01-20
11892874	B104	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.4 ± 0.4	2025-01-20
11893096	B105	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.5 ± 0.4	2025-01-20
11892879	B107	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.7 ± 0.4	2025-01-20
11893098	B108	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	6.1 ± 0.5	2025-01-20
11893097	B109	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	4.6 ± 0.4	2025-01-20
11893093	B110	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	5.0 ± 0.4	2025-01-20
11892897	B111	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.7 ± 0.4	2025-01-20
11892882	B111	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	3.8 ± 0.4	2025-01-20
11906849	LIBRARY	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	0.9 ± 0.4	2025-01-20

January 20, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**OFFICE
MAIN**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11906876	O	2025-01-14 @ 11:00 am	2025-01-17 @ 11:00 am	< 0.3	2025-01-20
11906877	O	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	< 0.3	2025-01-20

January 20, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**TRAVEL
MAIN**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11903993	T	2025-01-13 @ 11:00 am	2025-01-16 @ 11:00 am	< 0.3	2025-01-20
11906878	T	2025-01-14 @ 11:00 am	2025-01-17 @ 11:00 am	< 0.3	2025-01-20

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGIES, INC Job Number 20001560

NOMINAL Conditions: Radon Conc 50.6 pCi/L Rel. Hum 50.6 % Temp. 70.8 F

Date Start: 12/14/24 Date Stop: 12/17/24 Date Start: _____ Date Stop: _____

Time Start: 0815 Time Stop: 0815 Time Start: _____ Time Stop: _____

Device No.'s: (3) CHAR BAGS Device No.'s: _____

11477880, 11477883, 11477896 _____

B4 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

December 23, 2024

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**SK
MAIN**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11477880	SK1	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	52.0 ± 4.2	2024-12-23
11477883	SK2	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	54.6 ± 4.4	2024-12-23
11477896	SK3	2024-12-14 @ 8:00 am	2024-12-17 @ 8:00 am	45.5 ± 3.6	2024-12-23



Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Testing January 13th – January 16th, 2024

Name of Schools:

1. Springbrook HS
2. Woodlin ES
3. Parkside Center
4. Bannockburn ES
5. Beall ES
6. Bells Mill ES
7. Bethesda ES

	Date	Initials
Radon Test Kits Deployed	01/13/2025	BWM
Radon Test Kits Collected	01/16/2025	BWM
Radon Test Kits Shipped to Lab*	01/17/2025	BWM
Radon Test Kits Received by Lab*	01/21/2025	BWM

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835