

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Facilities
	Maintenance Depot –
	Building B MCPS
Date of Test Report	2/16/2023
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	9
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	0.6 pCi/L

MCPS RADON TESTING – EXECUTIVE SUMMARY

Project Status:

1. 5-Year retesting completed.



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 16, 2023

Mr. Brian Croyle Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re:	Radon Testing Services
	KCI Job # 122210551
Location:	Facilities Maintenance Depot – Building B MCPS 8301 Turkey Thicket Drive Gaithersburg, MD 20879

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Facilities Maintenance Depot – Building B MCPS, located at 8301 Turkey Thicket Dr. Gaithersburg, MD 20879 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on January 9, 2023 and deployed eleven (11) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 12, 2023 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs - MA for analysis by gamma-ray spectroscopy.

Mr. Brian Croyle February 16, 2023 Page 3

Accustar Labs - MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

Evaluation of Testing Conditions:

These tests represent:

- Follow up to initial testing.
- These tests were conducted to:
- Evaluate radon concentration levels at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate temperatures ranged from the 26°F to the mid 56°F. Maximum sustained winds ranged from 0-21 miles per hour. Average humidity was around 68% with .09 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachn	nent B

Quality Control Samples		
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of	
	less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
	adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is	
	operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler McCleaf

Tyler P. McCleaf Radon Measurement Provider #111004 RT KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test LocationsB- Table 1-3, Radon Test Summary SpreadsheetsC- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal ACI- Air Check, Inc. D- Duplicate FB- Field Blank KCI- KCI Technologies, Inc. OB- Office Blank PM- Project Manager OC- Quality Control

	es Maintenance Depot - Build	
Test	Period: 01/09/2023 - 01/12/20	023
		•
Kit Number	Room / Area	Result
11132198	B151	< 0.3
11132136	B153	< 0.3
11132199	B161	< 0.3
11132145	B172	0.6
11132158	B172A	< 0.3
11633285	B179	< 0.3
11633288	B179	< 0.3
11633281	MAIN WORK AREA	< 0.3
11633291	MAIN WORK AREA	< 0.3
11633293	MAIN WORK AREA	< 0.3
11132157	SHOP AREA	< 0.3

Table 2- Radon Testing Results					
	Facilities Mainte	nance Depot - Building B			
	Test Period: 01/09/23 - 01/12/23				
Kit Number QC Type Room / Area Resul					
11633288 D B179		B179	< 0.3		
11633293 FB Main Work Area					
11285160	OFFICE BLANK	< 0.3			
11285167	TRAVEL BLANK	< 0.3			

Summary of Missed Locations			
Facilities Maintenance Depot - Building B			
Test Period: 01/09/23 - 01/12/23			
Kit Number	Room/Area	Result	
	N/A		

Summary of Missing, Compromised and >/= 4 piC/L Tests				
Facilities Maintenance Depot - Building B				
Test Period: 01/09/23 - 01/12/23				
Kit Number	Room/Area	Result		
	N/A			

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

January 16, 2023

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11633285	B179	2023-01-09 @ 11:00 ar	n 2023-01-12 @ 11:00 am	< 0.3	2023-01-16
11633288	B179	2023-01-09 @ 11:00 ar	n 2023-01-12 @ 11:00 am	< 0.3	2023-01-16
11633281	MAIN WORK AREA	2023-01-09 @ 11:00 ar	n 2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11633291	MAIN WORK AREA	2023-01-09 @ 11:00 ar	n 2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11633293	MAIN WORK AREA	2023-01-09 @ 11:00 ar	n 2023-01-12 @ 10:00 am	< 0.3	2023-01-16

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

CLIENT KCI TECHNOLOGIES	Job Number 208343
NOMINAL Conditions: Radon Conc 34.7	_pCi/L Rel. Hum <u>49.4</u> % Temp. <u>69.6</u> F
Date Start: 12/24/22 Date Stop: 12/27/2	Date Start: Date Stop:
Time Start: <u>O810</u> Time Stop: <u>O810</u>	Time Start: Time Stop:
Device No.'s: (5) CHAR BAGS -	Device No.'s:
11285109 11285110, 11285101	÷
THRU 11285103	
Byceff	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
-	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft

~

December 29, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: OFFICE MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285110	SK1	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	31.7 ± 2.5	2022-12-29
11285101	SK2	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.1 ± 2.4	2022-12-29
11285103	SK3	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	34.0 ± 2.7	2022-12-29
11285102	SK4	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.9 ± 2.5	2022-12-29
11285109	SK5	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	32.0 ± 2.6	2022-12-29

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Week 1 January Schools

Name of Schools:

- 1. Diamond ES
- 2. Lakelands Park MS
- 3. Quince Orchard HS
- 4. Facilities Maintenance Depot Building A MCPS
- 5. Facilities Maintenance Depot Building B MCPS
- 6. Food and Nutrition Services
- 7. Hadley Farms
- 8. Goshen ES
- 9. Forest Knolls ES

	Date	Initials
Radon Test Kits Deployed	01/09/2023	BMM
Radon Test Kits Collected	01/12/2023	13MM
Radon Test Kits Shipped to Lab*	01/12/2023	BMM
Radon Test Kits Received by Lab*	01/17/2023	BMM

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Facilities Maintenance Depot - Shop
Date of Report	February 2, 2018
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
\langle	New Facility
# of Rooms Tested	4
# Rooms \geq 4.0 pCi/L	0
Lowest Value	< 0.3 pCi/L
Highest Value	0.7 pCi/L

MCPS RADON TESTING - EXECUTIVE SUMMARY

Current Project Status at this time: Testing Completed; no further action at this time.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 2, 2018

Mr. Richard Cox, MS Team Leader Montgomery County Public Schools Division of Maintenance Rockville, Maryland 20855

Re: Radon Testing Services

KCI Job #1214694182

Location: Facilities Maintenance Depot - Shop 8301 Turkey Thicket Drive Gaithersburg, Maryland 20879

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Facilities Maintenance Depot - Shop, located at 8301 Turkey Thicket Drive in Gaithersburg, Maryland 20879 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on December 5, 2017 and deployed seven (7) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Appendix A of this report. KCI conducted radon testing only in the MCPS occupied portion of the building.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to

Mr. Richard Cox, MS February 2, 2018 Page 3

Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on December 8, 2017 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Initial Testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the low-30s to mid-40s and high temperatures ranged from the upper-30s to mid-50s. Maximum sustained winds ranged from 4-17 miles per hour. Average humidity was around 60%. 0.16 Inches of precipitation was recorded during the testing period.

<u>RESULTS</u>

The sampling locations, field observations, and analytical results are listed on Table 1 (Appendix B). The laboratory analytical results are also attached (Appendix C). Laboratory results and exposure data for the spike samples are also included in Appendix C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples			
Results of Blank Canisters:	The field blank, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that		
	adequate laboratory measurement precision was achieved.		
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is		
	operating within statistical control limits.		

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

James Makle

James Moulsdale, CHMM Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

C- Laboratory Analytical Results

B- Table 1-Radon Test Summary Spreadsheet

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank**
- PM- Project Manager
- QC- Quality Control

Radon Testing Results				
Test Period: 12/05/17-12/08/17				
Kit Number	Room / Area	Result		
7975801	B151	< 0.3		
7975836	B153	< 0.3		
7975837	B161	0.7		
7975838	B172A	0.6		

Radon Testing Results				
F	Facility Maintenance Depot Shop - Building B			
	Test Period: 12/05/17-12/08/17			
Kit Number	QC Type	Result		
7975839	D (B151)	< 0.3		
7986200	FB (B151)	< 0.3		
7986192	OB (OFFICE BLANK)	< 0.3		

Summary of Missed Locations						
Facility Maintenance Depot Shop - Building B						
	Test Period: 12/05/17-12/08/17					
Kit Number	Room / Area	Result				
	(none)					

Summ	ary of Missing, Compromised and ≥4 piC/	L Tests
F	acility Maintenance Depot Shop - Building	уB
	Test Period: 12/05/17-12/08/17	
Kit Number	Room / Area	Result
	(none)	
	(none)	
		-
		1
		1
		1
		+
	ļ	
		1

ATTACHMENT C

Laboratory Analytical Results

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: FMD SHOP MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7975801	B151	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	< 0.3	2017-12-13
7986200	B151	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	< 0.3	2017-12-13
7975839	B151	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	< 0.3	2017-12-13
7975836	B153	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	< 0.3	2017-12-13
7975837	B161	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	0.7 ± 0.4	2017-12-13
7975838	B172A	2017-12-05 @ 3:00 pm	2017-12-08 @ 12:00 pm	0.6 ± 0.4	2017-12-13
7986192	OFFICE BLANK	2017-12-05 @ 1:00 pm	2017-12-08 @ 1:00 pm	< 0.3	2017-12-13

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook Road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase

Names of Schools:

- 1. John T. Baker Middle School
- 2. Cedar Grove Elementary School
- 3. Clarksburg Elementary School
- 4. Clarksburg Elementary School Annex
- 5. Clarksburg High School
- 6. Clearspring Elementary School
- 7. Damascus Elementary School
- 8. Damascus High School
- 9. Dr. Charles R. Drew Elementary School
- 10. Facilities Maintenance Depot Shop
- 11. Lake Seneca Elementary School
- 12. Laytonsville Elementary School
- 13. Watkins Mill Elementary School
- 14. Watkins Mill High School

	Date	Initials
Radon Test Kits Deployed	12/05/17	IM
Radon Test Kits Collected	12/08/17	IM
Radon Test Kits Shipped to Lab*	12/08/17	VM
Radon Test Kits Received by Lab*	12/13/17	VM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

15. Whetstone Elementary School

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: TRANSIT 2 MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7193838	TRANSIT 1	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979384	TRANSIT 10	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979385	TRANSIT 11	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7984056	TRANSIT 12	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983834	TRANSIT 13	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7194097	TRANSIT 14	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7194092	TRANSIT 15	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7193840	TRANSIT 16	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979072	TRANSIT 17	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979071	TRANSIT 18	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979065	TRANSIT 19	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.6 ± 0.4	2017-12-13
7978194	TRANSIT 2	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7985660	TRANSIT 20	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7985661	TRANSIT 21	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.7 ± 0.4	2017-12-13
7193843	TRANSIT 22	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7984055	TRANSIT 23	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983813	TRANSIT 24	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983827	TRANSIT 25	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7978193	TRANSIT 3	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7978189	TRANSIT 4	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.5 ± 0.4	2017-12-13
7986187	TRANSIT 5	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7986188	TRANSIT 6	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7986177	TRANSIT 7	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979077	TRANSIT 8	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979386	TRANSIT 9	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Radon test result report for:

MCPS - Spike Sample Laboratory Results. Measured values are satisfactory, i.e. within ±25% of the chamber's reference value (27.7 pCi/L).

Kit # Koom Id Started Ended 7975075 S1 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	pCI/L Analyzed
7975075 S1 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	
7775075 51 2017 12 01 @ 11.00 uni 2017 12 04 @ 11.00 u	am 25.6 ± 0.7 2017-12-07
7975064 S2 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	am 27.4 ± 0.8 2017-12-07
7975063 S3 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	am 26.3 ± 0.7 2017-12-07
7975065 S4 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	am 23.0 ± 0.7 2017-12-07
7975069 S5 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	am 25.6 ± 0.7 2017-12-07
7975070 S6 2017-12-01 @ 11:00 am 2017-12-04 @ 11:00 a	am 23.0 ± 0.7 2017-12-07

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

EXPOSURE IN BOWSER-MORNER RADON CHAMBER					
CLIENT KCI Technolog	lies Inc.	Job Number 182393	3		
NOMINAL Conditions: Radon Conc 27. 7	pCi/L Rel. Hum	49.1 % Temp. 70.1	F		
Date Start: 12/11 Date Stop: 12/4/1-) Date Start:	Date Stop:			
Time Start: 1949 Time Stop: 1949	Time Start:	Time Stop:			
Device No.'s: (6) Chan. Bags.	Device No.'s:_				
7975075, 7975064, 7975063,					
1973065, 1975069, 1975070					
Fy Ront		-			
Date Start: Date Stop:	Date Start:	Date Stop:			
Time Start: Time Stop:	Time Start:	Time Stop:			
Device No.'s:	Device No.'s:	~¢\$			
Date Start: Date Stop:	Date Start:	Date Stop:			
Time Start: Time Stop:	Time Start:	Time Stop:			
Device No.'s:	Device No.'s:				

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft