

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

Site Name	Longview School
Date of Test Report	1/25/2023
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	26
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.5 pCi/L

MCPS RADON TESTING – EXECUTIVE SUMMARY

Project Status: 1. 5-Year Re-Testing Completed.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

January 25, 2023

Mr. Brian Croyle Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re:	Radon Testing Services		
	KCI Job # 122210551		
Location:	Longview School		

13900 Bromfield Road Germantown, MD 20874

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Longview School located at 13900 Bromfield Rd. Germantown, MD 20874 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on December 19, 2022 and deployed twenty-nine (29) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 22, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs - MA for analysis by gamma-ray spectroscopy.

Accustar Labs - MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

Evaluation of Testing Conditions:

These tests represent:

• Follow up to initial testing.

These tests were conducted to:

• Evaluate radon concentration levels at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate temperatures ranged from 23°F to 55°F. Maximum sustained winds ranged from 0-18 miles per hour. Average humidity was around 75% with 0.0 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples		
Results of Blank Canisters: The office blanks, and lab transit blanks had test resul		
less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
adequate laboratory measurement precision was achieved.		
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is	
operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler McCleaf

Tyler P. McCleaf Radon Measurement Provider #111004 RT KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test LocationsB- Table 1-3, Radon Test Summary SpreadsheetsC- Laboratory Analytical Results

KCI TECHNOLOGIES, INC.

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal ACI- Air Check, Inc. D- Duplicate FB- Field Blank KCI- KCI Technologies, Inc. OB- Office Blank PM- Project Manager OC- Quality Control

Table 1- Radon Testing Results				
	Longview School			
Tes	Test Period: 12/19/2022 - 12/22/2022			
Kit Number	Room / Area	Result		
11287044	134	< 0.3		
11287013	136	< 0.3		
11287043	137	< 0.3		
11287006	138	1.5		
11287028	140	< 0.3		
11287037	141	< 0.3		
11287036	143	< 0.3		
11287026	144	< 0.3		
11287014	145	< 0.3		
11633396	147	< 0.3		
11287005	149	< 0.3		
11633395	151	< 0.3		
11287007	152	< 0.3		
11287021	153	< 0.3		
11287027	153	< 0.3		
11287045	154	< 0.3		
11287004	100F	< 0.3		
11287003	100G	< 0.3		
11287030	141C	< 0.3		
11287022	145C	< 0.3		
11287029	145C	< 0.3		
11287035	145C	< 0.3		
11633397	147C	< 0.3		
11287012	GYM	< 0.3		
11287018	GYM	< 0.3		
11287019	GYM OFFICE	< 0.3		
11287011	MAIN OFFICE	< 0.3		
11287010	POOL	< 0.3		
11287020	POOL OFFICE	< 0.3		

Table 2- Radon Testing Results				
	Longview School			
	Test Period: 12/19/22 - 12/22/22			
Kit Number QC Type Room / Area Result				
11287027 D 153 < 0.3				
11287022 D 145C < 0.3				
11287029 FB 145C < 0.3				
11288518 OB OFFICE BLANK < 0.3				
11287685 TB TRAVEL BLANK < 0.3				

Summary of Missed Locations				
Longview School				
Т	Test Period: 12/19/22 - 12/22/22			
Kit Number	Room/Area	Result		
	N/A			

Summary of Missing, Compromised and >/= 4 piC/L Tests				
Longview School				
	Test Period: 12/19/22 - 12/22/22			
Kit Number	Room/Area	Result		
	N/A			

Table Note:

* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11287004	100F	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287003	100G	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287044	134	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287013	136	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287043	137	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287006	138	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	1.5 ± 0.6	2022-12-28
11287028	140	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287037	141	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287030	141C	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287036	143	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287026	144	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287014	145	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287022	145C	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287035	145C	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287029	145C	2022-12-19 @ 3:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11633396	147	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11633397	147C	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287005	149	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11633395	151	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287007	152	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287021	153	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287027	153	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287045	154	2022-12-19 @ 3:00 pm	2022-12-22 @ 12:00 pm	< 0.3	2022-12-28
11287018	GYM	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287012	GYM	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287019	GYM OFFICE	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287011	MAIN OFFICE	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287010	POOL	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28
11287020	POOL OFFICE	2022-12-19 @ 2:00 pm	2022-12-22 @ 11:00 am	< 0.3	2022-12-28

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

CLIENT KCI TECHNOLOGIES	Job Number 208343
	_pCi/L Rel. Hum <u>49.4</u> % Temp. <u>69.6</u> F
Date Start: 12/24/22 Date Stop: 12/27/2	Date Start: Date Stop:
Time Start: <u>O810</u> Time Stop: <u>O810</u>	Time Start: Time Stop:
	Device No.'s:
	÷
THRU 11285103	1
Byceff	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft

~

December 29, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for: OFFICE MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285110	SK1	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	31.7 ± 2.5	2022-12-29
11285101	SK2	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.1 ± 2.4	2022-12-29
11285103	SK3	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	34.0 ± 2.7	2022-12-29
11285102	SK4	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.9 ± 2.5	2022-12-29
11285109	SK5	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	32.0 ± 2.6	2022-12-29

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Week 3 December Schools

Name of Schools:

- 1. Clopper Mill ES
- 2. Cold Spring ES
- 3. Fox Chapel ES
- 4. Gaithersburg HS
- 5. Longview School
- 6. North Lake Center
- 7. Ronald McNair ES
- 8. Rosemont ES
- 9. S. Christa McAuliffe ES
- 10.Spark M. Matsunaga ES
- 11.William B. Gibbs, JR. ES

	Date	Initials
Radon Test Kits Deployed	12/19/2022	BMM
Radon Test Kits Collected	12/22/2022	BMM
Radon Test Kits Shipped to Lab*	12/22/2022	BMU
Radon Test Kits Received by Lab*	12/28/2022	BMM

*All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835



MONTGOMERY COUNTY PUBLIC SCHOOLS RADON TESTING

Executive Summary: Longview School 13900 Bromfield Rd,

Germantown, MD 20874

Date of Test Report:	2/3/2019
Round of Testing:	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested:	24
# of Rooms ≥ 4.0 pCi/L:	0
Low Value:	< 0.4
High Value:	0.6

Project Status

Initial testing complete: No further action at this time.



February 3, 2019

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

Location: Longview School 13900 Bromfield Road, Germantown, MD 20874

Dear Mr. Cox:

Intertek-PSI (PSI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of a "short-term" 3-day radon test for Rock Terrance High School, located at 13900 Bromfield Road, Germantown, MD 20874 (subject site).

Scope of Services:

PSI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. PSI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS007) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

PSI visited the site on December 04, 2018 and deployed thirty (32) activated charcoal (AC) radon test kits. PSI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. PSI returned to the site on December 07, 2018 to retrieve the radon sampling test kits. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, PSI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, PSI submitted ten (10) test kits to Bowser-Morner Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner Inc. prior to being returned to the laboratory for analysis.

PSI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis located at 929 Mount Zion Road, Lebanon, Pennsylvania (certification # ARL0007) and 2 Saber Way, Haverhill, Massachusetts (certification # ARL0017).



The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

PSI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

PSI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. PSI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥ 4.0 pCi/L	None	NA
≤ 4.0 pCi/L	See Attack	iment B
Notes:		

D -Duplicate Sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C).

Laboratory results and exposure data for the spike samples are also included in Attachment C. Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (703) 698-9300.



Respectfully Submitted,

INTERTEK-PSI

Non-Ame Jewlih

Nand Kaushik, P.E. Department Manager, Environmental Services Nand.Kaushik@intertek.com

Attachments:

A – Floor Plan with Test Locations
 B – Table 1 – Radon Test Summary Spreadsheet
 C – Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Radon Testing Results			
Longview School			
Tes	ting period: 12/04/18 - 12/07	/18	
Kit Number	Room / Area	Result (pCi/L)	
3928461	100	< 0.4	
3923469	134	0.5	
3924468	134	0.4	
3926929	136	< 0.4	
3928464	137	< 0.4	
3926930	138	< 0.4	
3926814	140	0.6	
3925467	141	< 0.4	
3926812	143	< 0.4	
3926820	144	< 0.4	
3926926	145	< 0.4	
3926927	147	< 0.4	
3926815	149	< 0.4	
3926816	151	< 0.4	
3926813	152	< 0.4	
3926818	153	< 0.4	
3926819	153	< 0.4	
3928431	154	< 0.4	
3929463	157	< 0.4	
3926466	137A	< 0.4	
3926925	143A	0.5	
3926928	147A	< 0.4	
3926817	151A	< 0.4	
3926995	157A	0.4	
3926696	Pool	0.5	
3926881	Pool Office	< 0.4	

Radon Testing Results			
	Longview School		
Testing period: 12/04/18 - 12/07/18			
Kit Number	QC Type	Result (pCi/L)	
3922470	134 (D)	< 0.4	
3927465	137 (D)	< 0.4	
3928595	Field Blank	< 0.4	
3928596	Field Blank	< 0.4	
3928593	Office Blank	< 0.4	
3928594	Transit Blank	< 0.4	

Table Notes:

- D Duplicate
- FB Field Blank
- OB Office Blank
- TB Transit Blank
- QC Quality Control

ATTACHMENT C

Laboratory Analytical Results



NELAC NY 11769 NRPP 103216 AL NRSB ARL0017 EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)	MCPS Radon Survey
2930 Eskridge Road	Longview School
Fairfax VA 22031	Germantown MD 20874

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
2405395 3928465 12/04/2018	3 9:26 am 12/07/2018 8:18 am	Room 137	< 0.4
2405396 3926996 12/04/2018	3 10:14 am 12/07/2018 8:39 am	Pool	0.5
2405397 3928463 12/04/2018	3 9:22 am 12/07/2018 8:16 am	Room 157	< 0.4
2405398 3928467 12/04/2018	3 9:30 am 12/07/2018 8:20 am	Room 141	< 0.4
2405399 3928468 12/04/2018	3 9:32 am 12/07/2018 8:21 am	Room 134	0.4
2405400 3928466 12/04/2018	3 9:28 am 12/07/2018 8:19 am	Room 137A	< 0.4
2405401 3928470 12/04/2018	3 9:36 am 12/07/2018 8:23 am	Room 134	< 0.4
2405402 3928469 12/04/2018	3 9:36 am 12/07/2018 8:23 am	Room 134	0.5
2405403 3928461 12/04/2018	3 9:20 am 12/07/2018 8:15 am	Floor First Room 100	< 0.4
2405404 3928464 12/04/2018	3 9:26 am 12/07/2018 8:18 am	Floor First Room 137	< 0.4
2405405 3926812 12/04/2018	3 9:38 am 12/07/2018 8:24 am	Floor First Room 143	< 0.4

Comment: AMENDED REPORT on 1/31/2019 to add the beginning & ending dates & times for devices 3928465, 3926996, 3928463, 3928467, 3928468, 3928466, 3928470 and 3928469. A copy of this report was emailed to Intertek-PSI (VA).



Date Analyzed: 12/11/2018 Date Reported: 01/15/2019

Report Reviewed By: ______

Report Approved By: Shawn Price, Director of Laboratory Operations, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



NELAC NY 11769 NRPP 103216 AL NRSB ARL0017

EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)	MCPS Radon Survey
2930 Eskridge Road	Longview School
Fairfax VA 22031	Germantown MD 20874

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
2405406 3926925 12/04/2018	8 9:40 am 12/07/2018 8:25 am	Floor First Room 143A	0.5
2405407 3926926 12/04/2018	8 9:42 am 12/07/2018 8:26 am	Floor First Room 145	< 0.4
2405408 3926927 12/04/2018	8 9:44 am 12/07/2018 8:27 am	Floor First Room 147	< 0.4
2405409 3926928 12/04/2018	8 9:46 am 12/07/2018 8:28 am	Floor First Room 147A	< 0.4
2405410 3926929 12/04/2018	8 9:48 am 12/07/2018 8:29 am	Floor First Room 136	< 0.4
2405411 3926930 12/04/2018	8 9:50 am 12/07/2018 8:30 am	Floor First Room 138	< 0.4
2405412 3926814 12/04/2018	8 9:52 am 12/07/2018 8:31 am	Floor First Room 140	0.6
2405413 3926815 12/04/2018	8 9:54 am 12/07/2018 8:32 am	Floor First Room 149	< 0.4
2405414 3926816 12/04/2018	8 9:56 am 12/07/2018 8:33 am	Floor First Room 151	< 0.4
2405415 3926817 12/04/2018	8 9:58 am 12/07/2018 8:34 am	Floor First Room 151A	< 0.4
2405416 3926818 12/04/2018	8 10:02 am 12/07/2018 8:36 am	Floor First Room 153	< 0.4

Comment: AMENDED REPORT on 1/31/2019 to add the beginning & ending dates & times for devices 3928465, 3926996, 3928463, 3928467, 3928468, 3928466, 3928470 and 3928469. A copy of this report was emailed to Intertek-PSI (VA).



12/10/2018

Date Analyzed: 12/11/2018 Date Reported: 01/15/2019

Report Reviewed By: ______

Report Approved By: Shawn Price, Director of Laboratory Operations, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

NELAC NY 11769 NRPP 103216 AL NRSB ARL0017

EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Property Tested: Project # 04481387-1

Intertek-PSI (VA)	MCPS Radon Survey
2930 Eskridge Road	Longview School
Fairfax VA 22031	Germantown MD 20874

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
2405417 3926819 12/04/2018	3 10:02 am 12/07/2018 8:36 am	Floor First Room 153	< 0.4
2405418 3926820 12/04/2018	3 10:04 am 12/07/2018 8:37 am	Floor First Room 144	< 0.4
2405419 3926995 12/04/2018	3 10:06 am 12/07/2018 8:38 am	Floor First Room 157A	0.4
2405420 3926881 12/04/2018	3 10:15 am 12/07/2018 8:40 am	Floor First Room Pool Office	< 0.4
2405421 3926813 12/04/2018	3 10:18 am 12/07/2018 8:41 am	Floor First Room 152	< 0.4
2405422 3928431 12/04/2018	3 10:20 am 12/07/2018 8:42 am	Floor First Room 154	< 0.4
2405423 3928593 12/04/2018	8 6:00 am 12/07/2018 6:00 pm	Office Blank	< 0.4
2405424 3928594 12/04/2018	8 6:00 am 12/07/2018 6:00 pm	Transit Blank	< 0.4
2405425 3928595 12/04/2018	3 9:20 am 12/07/2018 8:42 am	Field Blank	< 0.4
2405426 3928596 12/04/2018	3 9:20 am 12/07/2018 8:42 am	Field Blank	< 0.4

Comment: AMENDED REPORT on 1/31/2019 to add the beginning & ending dates & times for devices 3928465, 3926996, 3928463, 3928467, 3928468, 3928466, 3928470 and 3928469. A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 12/08/2018 Date Logged: 12/10/2018

Date Analyzed: 12/11/2018 Date Reported: 01/15/2019

Report Reviewed By: ______

Report Approved By:

Disclaimer:

Shawn Price, Director of Laboratory Operations, AccuStar Labs The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Radon in Air

EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

NRPP 105011 AL NRSB ARL0007 Ohio RL41

Laboratory Report for:

Property Tested:

Intertek-PSI (VA)	MCPS Radon Survey
2930 Eskridge Road	4514 Taylorsville Road
Fairfax VA 22031	Dayton OH 45424

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
3204125 3926831 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	36.1
3204126 3926832 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.8
3204127 3926833 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.7
3204128 3926834 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.8
3204129 3926835 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.0
3204130 3926836 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.5
3204131 3926837 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.6
3204132 3926838 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.3
3204133 3926839 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.2
3204134 3926840 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.0

Comment: A copy of this report was e-mailed to Intertek-PSI (VA)

Test Performed By: Unknow	n				
Distributed by: Intertek-PSI (VA)				
Date Received: 12/12/2018	Date Logged:	12/12/2018	Date Analyzed: 12/12/2018	Date Reported:	12/13/2018
				\sim	
Report Review	ed By:	they Kartin	Report Approved By:	XX2	
Disclaimer:	\subset	\sum	Shawn Price, Dire	ctor of Laboratory Oper	ations, AccuStar Labs
		•	uncertainty include statistical variations, d erence with test conditions may influence		ions in radon
This report may only be transferred to	a third party in its optir	oty Applytical regulte	relate to the samples AS RECEIVED B		Posulte shown on

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT Intertal - PS	I	Job Number 187732	
NOMINAL Conditions: Radon Conc 33.6	pCi/L Rel. Hum	49.1 % Temp. 20.1	F
Date Start: 12/7/18 Date Stop: 12/10/18	P Date Start:	Date Stop:	
Time Start: <u>0947</u> Time Stop: <u>0947</u>	_ Time Start:	Time Stop:	
Device No.'s: (10) Char. Cans-	Device No.'s:_		
3926831 thro 3926840			
		6	
G2 Laft			
Date Start: Date Stop:		Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:_	24	
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:		

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft



Chain of Custody

Project Name: MCPS Radon Survey 2018

Name of Schools:

- 1. Grosvenor Center (Luxmanor ES)
- 2. Montrose Center
- 3. Gibbs ES
- 4. Westbrook ES
- 5. Hadley Farms (Resnik ES)
- 6. Kingsview MS
- 7. Longview School
- 8. Lynnbrook Center
- 9. Magruder HS
- 10. McAuliffe ES
- 11. McNair ES

- 12. Mill Creek Towne ES
- 13. Martin Luther King MS
- 14. Montgomery Village MS
- 15. Great Seneca Creek ES
- 16. Quince Orchard HS
- 17. Redland MS
- 18. North Bethesda MS
- 19. Spark Matsunaga ES
- 20. Whetstone ES
- 21. Wood Acres ES

	Date	Initials
Radon Test Kits Deployed	12/04/2018	NL
Radon Test Kits Sampled	12/07/2018	ML
Radon Test Kits Shipped to Lab*	12/07/2018	NL
Radon Test Kits Received by Lab*	12/08/2018;	111
	12/09/2018	NL

*All samples sent to AccuStar Laboratories, 929 Mount Zion Road, Lebanon, PA 17046 and 2 Saber Way, Haverhill, MA 01835



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Longview School

Date of Test Report:	10/19/2016	
Round of Testing:	Initial	
	Follow-up	
	Post Remediation	
# Rooms Tested:	9	
# Rooms \geq 4.0 pCi/L:	0	
Low Value:	< 0.3	
High Value:	0.7	

Project Status:

Follow-up testing after HVAC update completed; no further action at this time.




ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

October 19, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850



Location: Longview School 13900 Bromfield Road Germantown, MD 20874

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Longview School, located at 13900 Bromfield Road in Germantown, Maryland 20874 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on September 27, 2016 and deployed thirteen (13) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on September 30, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

• Follow-up sampling of a school that had HVAC modifications over the summer.

To expedite the testing, tests were conducted in September as soon as students and staff returned to:

• Determine if the HVAC project changed previously detected radon levels

Future periodic testing should be conducted during the heating season in ideal conditions as described below. According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in cooling mode; therefore, KCI concludes that this test was not conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 50s and high temperatures in the mid-60s to mid-70s. Maximum sustained winds ranged from 3-15 miles per hour. Average humidity ranged from 71 to 89 percent. Rain (1.83 inches in Gaithersburg, MD) was recorded on 9/29/16. The weather conditions during the testing period may have resulted in atypical radon test results for this facility.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

The lab transit blanks and office blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

```
KCI TECHNOLOGIES, INC.
```

Mr. Richard Cox October 19, 2016 Page 4

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Sincerely,

James Makler

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test LocationsB- Table 1-Radon Test Summary SpreadsheetC- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

	Longview School			
	Test Period: 09/27/16-09/30/16			
Kit Number	Room / Area	Result		
7714264	102	0.6		
7714267	102	0.7		
7714256	144	< 0.3		
7714300	102G	< 0.3		
7714259	102H	< 0.3		
7714260	1021	< 0.3		
7714266	1021	< 0.3		
7714294	157A	< 0.3		
7714296	* 159 (Tampered)	< 0.3		
7714249	GYM	< 0.3		
7714293	* GYM (Missing)	-		
7714297	MAIN	< 0.3		

	Radon Testing Results	
	Longview School	
Test Period: 09/27/16-09/30/16		
Kit Number	QC Type	Result
7714284	D (144)	< 0.3

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: LONGVIEW SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714267	102	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	0.7 ± 0.3	2016-10-03
7714264	102	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	0.6 ± 0.3	2016-10-03
7714300	102G	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714259	102H	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714266	102I	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714260	102I	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714256	144	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714284	144	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714294	157A	2016-09-27 @ 3:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714296	159	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714293	GYM	@	@		
7714249	GYM	2016-09-27 @ 3:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03
7714297	MAIN	2016-09-27 @ 4:00 pm	2016-09-30 @ 1:00 pm	< 0.3	2016-10-03

Radon test result report for: MCPS Radon Phase 18 Office Blanks

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7802697	1	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7801899	10	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802932	11	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802935	12	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802915	13	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802941	2	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802942	3	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802919	4	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802918	5	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802917	6	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802916	7	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802952	8	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03
7802928	9	2016-09-26 @ 11:00 am	2016-09-29 @ 11:00 am	< 0.3	2016-10-03

Radon test result report for: MCPS Radon Phase 18 Transit Blanks

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714274	1	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802962	10	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714295	11	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714299	12	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714273	13	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714270	14	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802965	2	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802696	3	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802690	4	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714275	5	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7714298	6	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802990	7	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802974	8	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03
7802694	9	2016-09-26 @ 10:00 am	2016-09-29 @ 10:00 am	< 0.3	2016-10-03

Radon test result report for: MCPS Radon Spike Sample Results

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7769880	101	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	22.9 ± 1.0	2016-09-28
7769884	102	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	22.4 ± 1.0	2016-09-28
7769885	103	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	23.0 ± 1.0	2016-09-28
7769890	104	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	22.3 ± 1.0	2016-09-28
7769891	105	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	26.8 ± 1.2	2016-09-28
7769899	106	2016-09-24 @ 8:00 am	2016-09-26 @ 8:00 am	24.1 ± 1.1	2016-09-28

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

s Inc. Job Number 176788
pCi/L Rel. Hum <u>49.6</u> % Temp. <u>70.0</u> F
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
۶
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 18

Name of Schools:

- 1. Wood Acres Elementary School
- 2. Walt Whitman High School
- 3. Burning Tree Elementary School
- 4. Ashburton Elementary School
- 5. Bethesda Maintenance
- 6. Bethesda Transportation
- 7. Herbert Hoover Middle School
- 8. Cold Spring Elementary School
- 9. Garret Park Elementary School
- 10. Rock View Elementary School
- 11. Francis Scott Key Middle School
- 12. Montgomery Blair High School
- 13. Stephen Knolls School

- 14. Lourie Center
- 15. Shriver Elementary School
- 16. Viers Mill Elementary School
- 17. Highland Elementary School
- 18. Newport Middle School
- 19. Albert Einstein High School
- 20. Sligo Middle School
- 21. East Silver Spring Elementary School
- 22. Oak View Elementary School
- 23. Roscoe Nix Elementary School
- 24. Northwood High School
- 25. Springbrook High School
- 26. John F. Kennedy High School

	Date	Initials
Radon Test Kits Deployed	9/26/16	M
Radon Test Kits Collected	9/29/16	IM
Radon Test Kits Shipped to Lab*	9/30/16	JM
Radon Test Kits Received by Lab*	10/03/16	JM.

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 18

Name of Schools:

- 1. Damascus High School
- 2. Cedar Grove Elementary School
- 3. Hallie Wells Middle School
- 4. Clarksburg Elementary School
- 5. Clarksburg High School
- 6. Woodlin Elementary School
- 7. Flora Singer Elementary School
- 8. Spring Mill Center
- 9. Dr. Charles Drew Elementary School
- 10. William Farquah Middle School
- 11. Rosa Parks Middle School
- 12. Blair Ewing Center
- 13. Lathrop Smith Environmental Center
- 14. Sequoyah Elementary School
- 15. Shady Grove Middle School
- 16. Captain James Daly Elementary School

- 17. Watkins Mills High School
- 18. Forest Oak Middle School
- 19. Gaithersburg Middle School
- 20. Emory Grove
- 21. Fields Road Elementary School
- 22. Beall Elementary School
- 23. Julius West Middle School
- 24. Thomas Wootton High School
- 25. Robert Frost High School
- 26. Travilah Elementary School
- 27. Jones Lane Elementary School
- 28. Longview School
- 29. Rock Terrace High School
- 30. Germantown Elementary School
- 31. Lake Seneca Elementary School

	Date	Initials
Radon Test Kits Deployed	9/27/16	U.M
Radon Test Kits Collected	9/30/16	JM
Radon Test Kits Shipped to Lab*	9/30/16	JM
Radon Test Kits Received by Lab*	10/03/16	JM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

RADON SCREENING SURVEY – FOLLOW-UP LONGVIEW SCHOOL

13900 Bromfield Road, Germantown, Maryland 20874

Date of Test Report:	4/13/16 Follow-Up
Round of Testing:	Initial
<	Follow-up
	Post Remediation
# Rooms Tested	1
# Rooms <u>></u> 4.0 pCi/L:	0
Low Value:	<0.4
High Value:	<0.4
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0
Action Level	

EXECUTIVE SUMMARY

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L) 2/17/16 Initial	Result (pCi/L) 4/13/16 Follow-Up	Average Result (pCi/L)
145	Missing	<0.4	<0.4



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Longview School

Date of Test Report:	4/13/2016
Round of Testing:	Initial
(Follow-up
	Post Remediation
# Rooms Tested:	1
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.4
High Value:	< 0.4

Project Status: Retesting completed; no further action at this time.




ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

April 13, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850



Location: Longview School 13900 Bromfield Road Germantown, MD 20874

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Longview School, located at 13900 Bromfield Road in Germantown, Maryland 20874 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on March 8, 2016 and deployed one (1) activated charcoal (AC) radon test kit. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 11, 2016 to retrieve the radon sampling test kit. KCI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis (certification # ARL0007) located at 929 Mount

Zion Road, Lebanon, Pennsylvania.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachn	nent B

Notes: D- Duplicate sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling location, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Mr. Richard Cox April 13, 2016 Page 4

Sincerely,

James Makler

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

- A- Floor Plan with Test Locations B- Table 1-Radon Test Summary Spreadsheet
- C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB- Office Blank***
- PM- Project Manager
- QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 11 testing. Office blanks were not submitted under each school individually.

	Radon Testing Results						
Radon Testing Results Longview School Test Period: 03/08/16-03/11/16 Kit Number Room / Area 3028806 145							
Kit Number	Room / Area	Result					
		<0.4					

ATTACHMENT C

Laboratory Analytical Results



Sparks MD 21152

Radon in Air

NRPP 10511AL NRSB ARL0007	EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317
Laboratory Report for:	Property Tested: Project # 12146341
KCI Technologies 936 Ridgebrook Rd	Longview School 13900 Bromfield Rd

Log Number	Device Number	Test Exposu	re Duration:	Area Tested	Result (pCi/L)
3016770	3028806	03/08/2016 4:33 pm	03/11/2016 12:46 pr	m Unit 145 First Floor	<0.4

Comment: A copy of this report was emailed to tehsin@kci.com.

Distributed by: KCI Technologies, Inc.

Date Received: 03/15/2016 Date Logged:

03/15/2016

Date Analyzed: 03/16/2016

Germantown MD 20874

Date Reported: 03/16/2016

Disclaimer:

Report Reviewed By: ______ Report Approved By: ______ Report Approved By: ______ Carolyn D. Koke, President, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

PO BOX 990 Jonestown PA 17038 717-274-8310

AccuSta 11 Awl S	Medway
AccuStar	Professional Radon Laboratory Services Since 1984

Radon Device Type Open Face Canister 888-480-8812 www.accustarlabs.com

ar Labs Street y MA 02053 Send Written Report To:

Send Written Report To:	Report To:	Site Tested:	
Name	KCI Technologies, Inc	Site Name	Lovenieu Schi
Address	936 Ridgebrook Road	Address	13900 Brank
Address		Address	
City / Town	Sparks	City / Town	Giermantown
State/Province	State/Province Postal Code MD 21152	State/Province	State/Province Postal Code MD
Report Country	Report Country Baltimore County	Test Country	Test Country Montgomery County
Email Address	Email Address tehsin@kci.com	Project Number 12146341	r 12146341

Contact Information:

Contact	Tehsin Aurangabadwala
Telephone	410-891-1726
Technician	
Cert. Number	1. A second sec second second sec
Signature	

20874

13900 Bromfield Rd

Longview School

Lab Use Only						
Stop Time	94°C)					
Stop Date	03/11/2016					
Start Time	16:33					
Start Date	03/08/2016					
Name of Room	730					
Floor						
Unit Number	145					
Building Number						
Device Number	3020806					
Lab Use Only	~					

Test must start before the expiration date shown on your device or test results will be invalid

Rev E1512



Laboratory Report for:

NRPP 10511AL

NRSB ARL0007

Radon in Air

EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Property Tested: Project # 12146341

MCPS Radon Phase 11 Office Blank

KCI Technologies 936 Ridgebrook Rd Sparks MD 21152

Log Number	Device Number	Test Exposur	e Duration:		Area Tested	Result (pCi/L)
3016739	3029191	03/08/2016 10:00 am	03/11/2016 10	0:00 am	Office Blank	<0.4

Comment: A copy of this report was emailed to tehsin@kci.com.

Distributed by: KCI Technologies, Inc. Date Received: 03/15/2016 Date Logged: 03/15/2016 Date Analyzed: 03/15/2016 Date Reported: 03/16/2016

Report Reviewed By: ___ Disclaimer:

Anten Canton

Report Approved By: ______ Report Approved By: ______ Carolyn D. Koke, President, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

									Lab Use Only						
		Tehsin Aurangabadwala	I-1726				ine Mundal	- m	Stop Time hh:mm am / pm	10:00 am					
	Contact Information:	KU LINNA			ian	Imber 7	re A AA		Stop Date mm/dd/yyy	03/11/2016					
	Contac	Contact	Telephone		Technician	Cert. Number	Signature		Start Time hh:mm am / pm	10:00 am					
ce Canister		ie Blank	Ridge brove Ad			2/152	ty		Start Date ^{mm/dd/yyyy}	03/08/2016					
Radon Device Type Open Face Canister	Site Tested:	Site Name MLPS UR	Address 936 R_{35}		City/Town Sparks	State/Province Postal Code MD	Test Country Montgomery County	Project Number 12146341	Name of Room	Office Blank					
labs.com	S	<i></i>	•	4		S			Floor	۲					
		p	q			21152			Unit Number	۲					
AccuStar Labs AccuStar Labs 11 Awl Street Medway MA 02053		KCI Technologies, Inc	936 Ridgebrook Road			MD	e County	kci.com	Building Number	-					
Account Radon Laboratory Services Since 1884	n Report Tc	KCI Tec	936 Ridç		Sparks	ce Postal Cc	try Baltimor	ss tehsin@	Device Number	3029191					
Professional Radon Labo	Send Written Report To:	Name	Address	Address	City / Town	State/Province Postal Code	Report Country Baltimore County	Email Address tehsin@kci.com	Lab Use Only						

Test must start before the expiration date shown on your device or test results will be invalid

Rev E1512

1 of 1



Radon in Air

	IRPP 10 IRSB AF					EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317
L	abora	tory Report	for:		Property Tested:	
	9	(CI Technolo 936 Ridgebro Sparks MD	•		MCPS Transit Blanks	
	g mber 10588	Device Number 3028953	Test Exposu 01/19/2016 1:00 pm	re Duration: 01/22/2016 9:30 am	Area Tested	Result (pCi/L) < 0.4

Number	Number					
3010588	3028953	01/19/2016 1:00 pm	01/22/2016	9:30 am	1	< 0.4
3010589	3028955	01/19/2016 1:00 pm	01/22/2016	9:30 am	2	< 0.4
3010590	3028954	01/19/2016 1:00 pm	01/22/2016	9:30 am	3	< 0.4
3010591	3028997	01/19/2016 1:00 pm	01/22/2016	9:30 am	4	< 0.4

Comment: AMENDED REPORT for 3028953-8955, 3028997 on 2/22/16 to add all missing information from the blank datasheet. A copy of this report was emailed to james.moulsdale@kci.com.

Distributed by: KCI Technologies, Inc. Date Received: 01/27/2016 Date Logged: 01/27/2016 Date Analyzed: 01/28/2016 Date Reported: 01/28/2016 Report Reviewed By: Cruese Bates Report Approved By: Curly D. Koke

Disclaimer:

Carolyn D. Koke, President, AccuStar Labs The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

Return canisters for analysis to: AccuStar Labs 929 Mt. Zion Rd., Lebanon, PA 1 800-523-4964	Return canisters for analysis to: AccuStar Labs 929 Mt. Zion Rd., Lebanon, PA 17046 RECEIVED JAN 2NFORMATION FORM - Large Buildings 800-523-4964 Projects - Apartments	ED JAN 2NFORMAT	uStar Labs ATION FOF Projects -	AccuStar Labs – Lebanon, PA RMATION FORM - Large Build Projects - Apartments	ın, PA Buildings - İts		Instructions on back of form Read instructions carefully Discrepancies will invalidate tests	ck of fo careful invalid	rm ly ate tests	
Test Site Info Name of Buildir	Test Site Info Name of Building/Project or Owner \overline{n}	ranset &						0 Q N	Do not use this form in New Jersev or Florida	orm in
Site Address:		and the set is set of the set			Contraction of the second second	THE LEASE PROPERTY.	ad produces	Ca Ca	Call for correct forms.	orms.
City:	and a strength of the strength	State	Zip		County			3		
Projects Contact Name:	t Name: Ser Con	Phone:			Email:	CONTRACTOR AND A	AND BUT FERRE	Mu	Multi-Page Report Y-N LAB USE ONLY	N-Y
Detector Serial#	ROOM NAME & NUMBER - LOCATION OF DETECTOR ROOM (indicate duplicates and blanks)	CATION OF DETECTOR IN cates and blanks)	Floor	Start Date	Start Time	Stop Date	Stop Time Include AM/PM	Wgt.	Gain	pCi/L
3028953	Trans	3010588	/	1/19/1	CO. Jacits	1/22/1/	9130an	Statistics of the local division of the		40:
8955	Traw, t	3010589	-	1/10/16				55}-	V	30.
- 8954	trans, t	3010590	1	1110111				0		202
E99 C	Transit	3010591	-	1112111	>	2		2	V	54
	appoint avdeal habercostic wellog	and management eventstations -	· Apurat		01 000 (million				310012011	
		a operation of the second of t	- Enter		Closeda, gan	KCI Technologies, Inc.	gies, Inc.		9107/17/1	~
		Margan darataria kanada				3010588 3028953		ACPC275B E	EXP12/31/2018	
Sector Sector	gree the fight fitter of the fitter	the state of the s								
Structure Type:	(circle one or more) Basement - Crawlspace - Slab on Grade - Other	Ispace - Slab on Grade - Oi	ther	Both Placed b	Both Placed by and Retrieved by signatures are required	I by signatures	are required	Cer	רפנווומת ובמיהיה	# e
Test Purpose:	Initial Screening - Foll	Follow Up Test -		Canisters placed by	aced by				#	101.101
(Circle all that apply)	Post Mitigation - Re	Real Estate - Other								
Building Type:	Residential - Non Residential Private Dav Care - Private Sch	Residential Private School		Canisters retrieved by	irieved by	\langle		-	#	
		ol - Public School		Owner waives confidentiality by signing here	onfidentiality	0	Date Weell	19	Were general operating	erating
Send Results To:			4		~	1 11			conalitons maintained ? Yes - No explain if No	explain if NO
Company Name: V	lei Tech	20x	Þ	Attention:	James. 1	Mapcolal			OSe	ilding
Address: 936	Ridgebrock	-121.	£20-0148		Star The root & s	and to show he	ally made with we		conditions maintained?	ained?
1	2	ARGE DERIG ALLER TO S	State:	MD Zip	21250	~		-	Yes - No expla	explain if NO
Phone: 110 - 5	79-3826			Fax:				2	Normal Temp. Y	Yes - No
EMAIL Results to:	to James. M	1 ouls dale () k	£. Co	Lon.				2	Normal Humidity Y	Yes - No
Make sure information is complete and correct. If a recolutioniation is connected there is a \$10.00	Make sure information is complete and correct. If a recolution is required there is a \$10.00 recolution is requireded	Mailing: I Shipping: 9	Mailing: PO Box 990 inning: 929 Mt Zion Re	Mailing: PO Box 990 Jonestown, PA 17038 Shinping: 929 Mt Zion Road, Lebanon, PA 17046	PA 17038 1. PA 17046		**: *		12	
וו מ וקטמוטווניוטו וט ורקאיייי		80	0-523-496	800-523-4964 fax 717-274-5662 NEHA 10511AL NRSB ARL 0007	362				Revision 5 4/2015	<u>ى</u> ى

6-42

TCS INDUSTRIES, INC.

(717) 657-7032

RADON GAS DETECTION

www.radondetek.com

4326 Crestview Road, Harrisburg, PA 17112

James Moulsdale KCI 936 Ridgebrook Rd. Sparks, MD 21152 April 04, 2016

Dear Mr. Moulsdale:

The spike exposure data were:

Start 04/04/16 @ 1110 hrs EDT End 04/06/16 @ 1113 hrs EDT

AC 3029218, 3029219, 3029220, 3029217, 3029214, 3029217, and 3029166

Average radon concentration was 10.6 pCi/L +/- 5%

Avg, Temp. was 71FAvg. RHwas 51%Elevationwas 490 feet above sea level

Sincerely,

Cut

Carl H. Distenfeld, CHP



NRPP 10511AL NRSB ARL0007

Laboratory Report for:

KCI Technologies

936 Ridgebrook Rd Sparks MD 21152 EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Property Tested:

MCPS Radon Spike Sample Laboratory Results

Log Number	Device Number	Test Exposur	e Duration:	Area Tested	Result (pCi/L)
3020102	3029166	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	11.9
3020103	3029214	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	11.5
3020104	3029217	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	10.7
3020105	3029218	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	11.3
3020106	3029219	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	11.0
3020107	3029220	04/04/2016 11:10 am	04/06/2016 11:13 a	m Not Indicated	10.5

Comment: A copy of this report was emailed to james.moulsdale@kci.com.

Distributed by: KCI Technolo	gies, Inc.					
Date Received: 04/07/2016	Date Logged:	04/07/2016	Date Analyzed: 04/07/2016	Date Reported:	04/08/2016	
Note: Spike samples are test canisters t They provide a quality control measur tested.	· · ·					
The uncertainty of this radon measu		Factors contributing	Report Approved By: Carolyr to uncertainty include statistical variati erference with test conditions may influ	n D. Koke, President, Ao ons, daily and seasona	ccuStar Labs	۱

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

PO BOX 990 Jonestown PA 17038 717-274-8310

	[-)	٦				7	r	<u>т</u>	1		- <u></u>	1	1	T	· · · · ·	T
					The second s			Lab Use Only									
	Tehsin Aurangabadwala	1-1726				1 Na		Stop Time hh:mm am / pm	11:15an)			
Contact Information:	<u></u>			tian	umber	Le		Stop Date	4/6/16					>			
Contac	Contact	Telephone		Technician				Start Time	11:10an	_				\uparrow			
		nd Dr			20850			Start Date	4/4/16					>			
Site Tested:	Site Name MC PS	Address 852 Hurverd	Address	City / Town Pockulle	State/Province Postal Code MD	Test Country Montgomery County	Project Number 12146341	Name of Room Temp		2	M	J	Ь	9			
labs.com	S	▼	A		S			Floor	1	-		1	-	-			
	JC L	p			21152			Unit Number									
Medway MA 02053	KCI Technologies, Inc	936 Ridgebrook Road			MD	e County	kci.com	Building Number	1		-		.				-
n Report To	KCI Tec	936 Rid(Sparks	ce Postal Co	try Baltimor	ss tehsin@kci.com	Device Number	3029166	3029214	3029217	3029218	3029219	3029220			
Professional Redon Laboratory Services Since 1984 Send Written Report To:	Name	Address	Address	City / Town	State/Province Postal Code	Report Country Baltimore County	Email Address	Lab Use Only			., .			• - 1			

Test must start before the expiration date shown on your device or test results will be invalid

1 of 1

Rev E1512



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Longview School

Date of Test Report:	2/17/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	21
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	0.7

Project Status: Initial testing completed; missing or compromised samples need re-test.




ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 17, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850



Location: Longview School 13900 Bromfield Road Germantown, MD 20874

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Longview School, located at 13900 Bromfield Road in Germantown, Maryland 20874 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on January 19, 2016 and deployed twenty-five (25) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 22, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachn	nent B

Notes:

D- Duplicate sample

The field blank, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Mr. Richard Cox February 17, 2016 Page 4

Sincerely,

James Makler

James M. Moulsdale Radon Measurement Specialist KCI Technologies, Inc.

Attachments:

- A- Floor Plan with Test Locations B- Table 1-Radon Test Summary Spreadsheet
- C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

- AC- Activated Charcoal
- ACI- Air Chek, Inc.
- D- Duplicate
- FB- Field Blank
- KCI- KCI Technologies, Inc.
- **OB-** Office Blank
- PM- Project Manager
- QC- Quality Control

	Radon Testing Results Longview Elementary School	
	Test Period: 01/19/16-01/22/16	
Kit Number	Room / Area	Result
7721625	100	0.6
7721627	134	< 0.3
7721648	136	0.6
7721619	137	< 0.3
7721622	138	< 0.3
7721638	140	< 0.3
7721634	141	< 0.3
7717814	142	< 0.3
7721636	143	< 0.3
7721639	144	< 0.3
7717845	147	< 0.3
7717877	149	< 0.3
7721642	151	< 0.3
7721663	153	< 0.3
7717812	157	< 0.3
7717813	157	< 0.3
7721629	137C	0.7
7721640	143C	< 0.3
7721637 *	145 (missing)	0
7721626	147C	< 0.3
7721641	151C	< 0.3
7721646	157A	0.6

	Radon Testing Results	
	Longview Elementary School	
	Test Period: 01/19/16-01/22/16	
Kit Number	QC Type	Result
7721644	D (136)	< 0.3
7721623	FB (137)	< 0.3
7721454	OB (0)	< 0.3

ATTACHMENT C

Laboratory Analytical Results

February LABORATORY ANALYSIS 11, REPORT **

Radon test result report for: LONGVIEW ELEMENTARY SCHOOL MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7721625	100	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	0.6 ± 0.3	2016-01-26
7721627	134	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721644	136	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-27
7721648	136	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	0.6 ± 0.3	2016-01-27
7721619	137	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721623	137	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721629	137C	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	0.7 ± 0.3	2016-01-26
7721622	138	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721638	140	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721634	141	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7717814	142	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721636	143	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-27
7721640	143C	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721639	144	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721637	145	@	@		
7717845	147	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-27
7721626	147C	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7717877	149	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-27
7721642	151	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721641	151C	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7721663	153	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7717812	157	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-26
7717813	157	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	< 0.3	2016-01-27
7721646	157A	2016-01-19 @ 1:00 pm	2016-01-22 @ 10:00 am	0.6 ± 0.3	2016-01-26

February LABORATORY ANALYSIS 11, REPORT **

Radon test result report for: LONGVIEW ELEMENTARY SCHOOL OFFICE BLANK

Started E	Ended p	Ci/L	Analyzed
6-01-19 @ 3:00 pm 2016	6-01-22 @ 1:00 pm < 0	0.3 20	16-01-26
		1	•

February LABORATORY ANALYSIS 2, REPORT **

Radon test result report for: MCPS PHASE 5 & 6 TRANSIT BLANKS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7722194	1	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718494	10	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718475	11	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718495	12	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718496	13	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718497	14	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718498	15	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718499	16	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718500	17	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718296	18	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718295	19	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7722195	2	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7716789	20	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7716785	21	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-26
7716791	22	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7716786	23	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7716793	24	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718274	25	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7716792	26	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718294	27	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718293	28	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718292	29	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7722197	3	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718290	30	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7722198	4	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7722199	5	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7722211	6	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718491	7	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27
7718476	8	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-26
7718479	9	2016-01-19 @ 12:00 pm	2016-01-22 @ 12:00 pm	< 0.3	2016-01-27

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

	Kit #	Room Id	Started	Ended	pCi/L	Analyzed
,	7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
,	7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
,	7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
,	7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
,	7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
	7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
	//102/1	1001	2010 01 50 C 9.00 um	2010 02 01 @ 9.00 um	0.5 ± 0.0	2010 02 0

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCF Technologie	5 Inc. Job Number 173704	
NOMINAL Conditions: Radon Conc 5.9	pCi/L Rel. Hum <u>45.9</u> % Temp. <u>79.0</u>	
Date Start: 1/30/16 Date Stop: 2/1/16	Date Start: Date Stop:	
Time Start: <u>9926</u> Time Stop: <u>996</u>	Time Start: Time Stop:	
Device No.'s: (6) Char. Bago-	Device No.'s:	
, ופבצורר, בוצבצורר אוצבצורר		
7718288, 7718289, 7718273		
E3 Left		
Date Start: Date Stop:	Date Start: Date Stop:	
Time Start: Time Stop:	Time Start: Time Stop:	
Device No.'s:	Device No.'s:	
Date Start: Date Stop:	Date Start: Date Stop:	
Time Start: Time Stop:	Time Start: Time Stop:	
Device No.'s:	Device No.'s:	
	· · · · · · · · · · · · · · · · · · ·	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μR/h Elevation = 820 ft



ENGINEERS · PLANNERS · SCIENTISTS · CONSTRUCTION MANAGERS

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Chain of Custody

Project Name: MCPS Radon Phase VI

Name of Schools:

- 1. Francis Scott Key MS
- 2. Gaithersburg ES
- 3. Gaithersburg MS
- 4. Galway ES
- 5. Great Seneca Creek ES
- 6. Harmony Hills ES
- 7. John Poole MS
- 8. Judith A. Resnik ES
- 9. Kemp Mill ES
- 10. Kingsview MS
- 11. Lakelands Park MS

13. Loiderman MS

12. Little Bennett ES

- 14. Longview ES
- 15. Meadow Hall ES
- 16. Neelsville MS
- 17. New Hampshire Estates ES
- 18. North Bethesda MS
- 19. Northwest HS
- 20. Pine Crest ES
- 21. Radnor Center
- 22. Ritchie Park ES

- 23. Rolling Terrace ES
- 24. Roscoe Nix ES
- 25. Sally K. Ride ES
- 26. Spark Matsunaga ES
- 27. Tacoma Park ES
- 28. Thomas Pyle MS
- 29. Wayside ES
- 30. Westbrook ES (retest)
- 31. Westland MS (retest)
- 32. William B. Gibbs ES
- 33. William Tyler Page ES

	Date	Initials
Radon Test Kits Deployed	1/19/16	JM
Radon Test Kits Sampled	1/22/16	JM
Radon Test Kits Shipped to Lab*	1/22/16	JM
Radon Test Kits Received by Lab*	1/26/16	JM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Road, Mills River, NC 28758