



Montgomery County Public Schools Lead in Drinking Water Testing 2018

Executive Summary:

Wheaton HS

12401 Dalewood Drive

Silver Spring, Maryland 20906

Date of Test Report:	3/23/2018
Round of Testing:	Initial
# of Outlets Tested:	36
# of Outlets ≥ 20 ppb:	0
Low Value (ppb):	<1.0
High Value (ppb):	<1.0

Project Status:

Initial testing complete: All results less than 20 ppb.



3/23/2018

Mr. Brian Mullikin, MS
Environmental Team Leader
Montgomery County Public Schools
Division of Maintenance
Gaithersburg, Maryland 20879

Re: Drinking Water Testing

KCI Job #1214634186

Location: Wheaton HS
12401 Dalewood Drive
Silver Spring, Maryland 20906

Dear Mr. Mullikin:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of Initial lead in water testing at Wheaton HS, located at 12401 Dalewood Drive in Silver Spring, Maryland 20906.

SCOPE OF SERVICES

KCI conducted lead in water testing at Wheaton HS in accordance with the Environmental Protection Agency (EPA) and Maryland House Bill (HB) 270. State regulation established an action level of 20 parts per billion (ppb) to evaluate lead levels in school buildings, a concentration EPA recommends that schools take action to reduce lead below this action level. Maryland requires periodic testing for the presence of lead in drinking water in occupied public and nonpublic school buildings. EPA developed the 3T's (Training, Testing, and Telling) to assist schools in reducing the lead concentrations in their drinking water. More information about 3T's can be found on the EPA website.

KCI visited the site on 1/31/2018 and 2/1/2018 to collect samples from 36 drinking water outlets in accordance with current criteria described by the Maryland Department of the Environment (MDE) Draft Lead in Drinking Water - Public and Nonpublic Schools, Title 26, Subtitle 16 Lead, Chapter 07.

Samples were submitted to a laboratory for lead in water analysis using current US EPA methodology. The laboratory has been certified by the Maryland Department of the Environment to analyze drinking water for lead.

RESULTS

There are no results of the lead in water analysis at or above 20 parts per billion (ppb). The lead in water sample results for sample collection date 2/1/2018 are shown in Attachment A.

DISCUSSION

Lead is a naturally occurring element that can be harmful to humans when ingested or inhaled, particularly to children under the age of six. Lead can adversely affect the development of children's brain potentially leading to detrimental alterations in intelligence and behavior. Lead has been historically used in plumbing, paint and other building materials. Lead is released into the environment from industrial sources and fuel combustion. Lead may also be found in consumer products (imported candy, medicines, toys, dishes, etc.).

Most lead leaches into drinking water from contact with plumbing components such as faucets and valves made of brass or lead-containing solder. The physical and chemical interaction that occurs between the plumbing and water directly contributes to the amount of lead that is released into the water. Although plumbing components installed prior to the 1990's could contain more lead than newer materials, the amount of lead in the drinking water cannot be predicted by the age of building. The purpose of this regulation is to establish a program to minimize the risk of exposure to lead in drinking water outlets at schools.

Simple steps like keeping your home clean and well-maintained will go a long way in preventing lead exposure. These steps include inspecting and maintaining all painted surfaces to prevent paint deterioration, using only cold water to prepare food and drinks, flushing water outlets used for drinking or food preparation, and cleaning around painted areas where friction can generate dust, such as doors, windows, and drawers. Wipe these areas with a wet sponge or rag to remove paint chips or dust, and wash children's hands, bottles, pacifiers and toys often.

Respectfully Submitted,
KCI Technologies, Inc.



Kamau McAbee
MDE Certified Water Sampler #8281KM

Attachment:

A- Lead in Water Test Summary Table

ATTACHMENT A

Lead in Water Test Summary Table

ATTACHMENT A

Lead in Water Test Summary Table

Contractor: KCI Technologies, Inc.

Certified Laboratory: Microbac Laboratories, Inc.

Sample Results for Wheaton High School

Barcode ID	Room #	Location	Location Notes	Equipment Type	Results (PPB)*	Pass/Fail	Status
LW02602		Hallway	Next To 1400	Cooler	<1.0	Pass	Testing Complete
LW02785	3200	Hallway	Across From	Cooler	<1.0	Pass	Testing Complete
M33112		Hallway	Across From 1605	Cooler	<1.0	Pass	Testing Complete
M33120	1712	Hallway	Outside Of	Cooler	<1.0	Pass	Testing Complete
M33121	1712	Hallway	Outside Of	Cooler	<1.0	Pass	Testing Complete
M33126	1716	Child Development		Cooler	<1.0	Pass	Testing Complete
M33131	1000G	Work Room Administration		Faucet	<1.0	Pass	Testing Complete
M33141	1110	Hallway	outside	Cooler	<1.0	Pass	Testing Complete
M33142	1110	Hallway	outside	Cooler	<1.0	Pass	Testing Complete
M33145	1115	Health Room		Faucet	<1.0	Pass	Testing Complete
M33168	1400	Hallway	Next To	Cooler	<1.0	Pass	Testing Complete
M33179	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33180	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33181	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33182	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33183	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33184	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33186	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33187	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33188	1504	Kitchen Cafeteria		Faucet	<1.0	Pass	Testing Complete
M33189	1504	Kitchen Cafeteria	Across From 1504a	Icemaker	<1.0	Pass	Testing Complete
M33190	1500	Cafeteria	Outside Of 1600	Cooler	<1.0	Pass	Testing Complete
M33191	1500	Cafeteria	Outside Of 1600	Cooler	<1.0	Pass	Testing Complete
M33192	1009	Break Room		Faucet	<1.0	Pass	Testing Complete

Barcode ID	Room #	Location	Location Notes	Equipment Type	Results (PPB)*	Pass/Fail	Status
M33197	1315	Hallway	Across From	Cooler	<1.0	Pass	Testing Complete
M33198	1315	Hallway	Across From	Cooler	<1.0	Pass	Testing Complete
M33201	2702	Hallway	Next To	Cooler	<1.0	Pass	Testing Complete
M33202	2702	Hallway	Next To	Cooler	<1.0	Pass	Testing Complete
M33214		Hallway	Outside	Cooler	<1.0	Pass	Testing Complete
M33215	2026	Hallway	Outside	Cooler	<1.0	Pass	Testing Complete
M33226	2200	Hallway	Left Of	Cooler	<1.0	Pass	Testing Complete
M33227	2200	Hallway	Left Of	Cooler	<1.0	Pass	Testing Complete
M33239	3019	Hallway	Outside	Cooler	<1.0	Pass	Testing Complete
M33251	3200	Hallway	Across From	Cooler	<1.0	Pass	Testing Complete
M33267	2709	Hallway	Next To	Cooler	<1.0	Pass	Testing Complete
M33268	2709	Hallway	Next To	Cooler	<1.0	Pass	Testing Complete

*PPB = parts per billion