



**MCPS RADON TESTING – EXECUTIVE SUMMARY**

Site Name	Forest Oak Middle School
Date of Test Report	4/7/2022
Round of Testing	Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility
# Rooms Tested	79
# Rooms $\geq$ 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.2 pCi/L

Project Status:  
Initial testing completed; no further action needed.



April 7, 2022

Brian T. Croyle, PG, CHMM  
Environmental Specialist  
Montgomery County Public Schools  
Gaithersburg, MD 20879

Re: **Radon Testing Services**  
KCI Job # 122108316

Location: Forest Oak MS  
651 Saybrooke Oaks Blvd.  
Gaithersburg, MD 20877

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Forest Oak MS, located at 651 Saybrooke Oaks Blvd. Gaithersburg, MD 20877 (subject site).

**Scope of Services:**

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <https://www.montgomeryschoolsmd.org> or [www.epa.gov/radon](http://www.epa.gov/radon).

KCI visited the site on February 22, 2022 and deployed eighty nine (89) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 25, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc.

is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

**Evaluation of Testing Conditions:**

These tests represent:

- Follow-up to post-mitigation biennial testing.

These tests were conducted to:

- Confirm the success of the mitigation system(s).

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility’s HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 20s and high temperatures ranged from the high 30s to the high 40s Fahrenheit. Maximum sustained winds ranged from 5-18 miles per hour. Average humidity was around 15% with 1.5 inches of precipitation (rain) was recorded during testing period.

**Results:**

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

<b>Radon Concentration</b>	<b>Room</b>	<b>Result</b>
≥4.0 pCi/L	NA	NA
<4.0 pCi/L	See Attachment B	

Quality Control Samples	
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is operating within statistical control limits.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,



Tyler P. McCleaf  
Radon Measurement Provider  
#111004 RT  
KCI Technologies, Inc.

Attachments:     A- Floor Plan with Test Locations  
                      B- Table 1-3, Radon Test Summary Spreadsheets  
                      C- Laboratory Analytical Results

# ATTACHMENT A

## Floor Plan With Test Locations

# ATTACHMENT B

## Radon Test Summary Spreadsheet

**Table Notes:**

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results		
Forest Oak MS		
Test Period: 02/22/2022 - 02/25/2022		
Kit Number	Room / Area	Result
11123469	A105	< 0.3
11123460	A108	0.9
11123464	A108	< 0.3
11123459	A118	< 0.3
11123461	A124	< 0.3
11123463	A126	< 0.3
11123465	A127	< 0.3
11123453	A130 GYM	< 0.3
11123466	A130 GYM	< 0.3
11115152	B101 CAFETERIA	< 0.3
11115156	B101 CAFETERIA	< 0.3
11123476	B103 STAGE	< 0.3
11115160	B110	< 0.3
11115164	B114	< 0.3
11115150	B115	< 0.3
11115153	B120	< 0.3
11115154	B121	< 0.3
11115163	B124	< 0.3
11115157	B125	0.9
11115162	B130	< 0.3
11115166	C106	< 0.3
11115171	C107	< 0.3
11115169	C109	< 0.3
11115178	C110	< 0.3
11115167	C111	< 0.3
11115168	C112	0.7
11115180	C114	0.8
11115175	C115	< 0.3
11115179	C116	< 0.3
11115174	C117	< 0.3
11115176	C118	< 0.3
11115181	C121	< 0.3
11115182	C121	< 0.3
11115183	C122	< 0.3
11115159	C131	< 0.3
11115170	C131	< 0.3
11115177	C131	0.8
11115173	C132	< 0.3
11115151	C133	< 0.3
11115155	C133	< 0.3
11115165	C135	< 0.3
11115161	C136	< 0.3
11115172	C137	< 0.3
11115187	C145	< 0.3
11115188	C145	< 0.3



Table 1- Radon Testing Results		
Forest Oak MS		
Test Period: 02/22/2022 - 02/25/2022		
Kit Number	Room / Area	Result
11115184	C146	1.1
11115192	C147	< 0.3
11115185	C157	< 0.3
11123450	D102	< 0.3
11123451	D103	< 0.3
11123452	D108	< 0.3
11123445	D109	< 0.3
11123446	D109	< 0.3
11123447	D109	< 0.3
11123440	D110	< 0.3
11123457	D113	< 0.3
11123449	D114A	< 0.3
11123458	D114B	< 0.3
11123442	D116	< 0.3
11123441	D119	< 0.3
11123444	D124	< 0.3
11123468	D127	< 0.3
11123481	D207	< 0.3
11123470	D219	< 0.3
11123472	D227	< 0.3
11123475	D230	< 0.3
11123456	E104	< 0.3
11123443	E105	< 0.3
11123455	E106	< 0.3
11123454	E107	< 0.3
11115198	E108	0.6
11123448	E109	< 0.3
11115199	E115	1.2
11115200	E115	< 0.3
11115190	E118	< 0.3
11115186	E119	< 0.3
11115189	E119	< 0.3
11115191	E119	< 0.3
11115197	E123	< 0.3
11115194	E124	< 0.3
11115193	E125	0.5
11115196	E126	< 0.3
11115195	E127	< 0.3
11123474	E208	< 0.3
11123462	E224	< 0.3
11123471	E224	< 0.3
11123473	E224	< 0.3
11123467	E228	< 0.3
11115158	MAIN OFFICE	< 0.3

Table 2- Radon Testing Results			
Forest Oak MS			
Test Period: 02/22/2022 - 02/25/2022			
Kit Number	QC Type	Room / Area	Result
11115151	D	C133	< 0.3
11115170	D	C131	< 0.3
11115182	D	C121	< 0.3
11115189	D	E119	< 0.3
11115199	D	E115	1.2
11123447	D	D109	< 0.3
11123446	FB	D109	< 0.3
11123460	D	A108	0.9
11123473	D	E224	< 0.3
11123471	FB	E224	< 0.3
11139384	OB	OFFICE BLANK	< 0.3
11131222	TB	TRAVEL BLANK	< 0.3

Summary of Missed Locations		
Forest Oak MS		
Test Period: 02/22/22 - 02/25/22		
Kit Number	Room/Area	Result
	NA	

Summary of Missing, Compromised and >= 4 piC/L Tests		
Forest Oak MS		
Test Period: 02/22/22 - 02/25/22		
Kit Number	Room/Area	Result
	NA	

Table Note:  
\* Missing or Compromised Sample

# ATTACHMENT C

## Laboratory Analytical Results

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11123469	A105	2022-02-22 @ 1:00 pm	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11123460	A108	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	0.9 ± 0.5	2022-03-03
11123464	A108	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123459	A118	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123461	A124	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123463	A126	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123465	A127	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123466	A130 GYM	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123453	A130 GYM	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115152	B101 CAFETERIA	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115156	B101 CAFETERIA	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11123476	B103 STAGE	2022-02-22 @ 2:00 pm	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115160	B110	2022-02-22 @ 9:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115164	B114	2022-02-22 @ 9:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115150	B115	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115153	B120	2022-02-22 @ 9:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115154	B121	2022-02-22 @ 9:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115163	B124	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115157	B125	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	0.9 ± 0.5	2022-03-03
11115162	B130	2022-02-22 @ 10:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11115166	C106	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115171	C107	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115169	C109	2022-02-22 @ 11:00 am	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11115178	C110	2022-02-22 @ 11:00 am	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11115167	C111	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115168	C112	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	0.7 ± 0.4	2022-03-03
11115180	C114	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	0.8 ± 0.5	2022-03-03
11115175	C115	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115179	C116	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115174	C117	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115176	C118	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115182	C121	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115181	C121	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115183	C122	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115170	C131	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115177	C131	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	0.8 ± 0.5	2022-03-03
11115159	C131	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03

Radon test result report for:

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11115173	C132	2022-02-22 @ 11:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115155	C133	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115151	C133	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115165	C135	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115161	C136	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115172	C137	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11115188	C145	2022-02-22 @ 11:00 am	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115187	C145	2022-02-22 @ 11:00 am	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115184	C146	2022-02-22 @ 11:00 am	2022-02-25 @ 11:00 am	1.1 ± 0.5	2022-03-03
11115192	C147	2022-02-22 @ 11:00 am	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115185	C157	2022-02-22 @ 11:00 am	2022-02-25 @ 9:00 am	< 0.3	2022-03-03
11123450	D102	2022-02-22 @ 12:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123451	D103	2022-02-22 @ 12:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123452	D108	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123445	D109	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123447	D109	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123446	D109	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123440	D110	2022-02-22 @ 1:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123457	D113	2022-02-22 @ 1:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123449	D114A	2022-02-22 @ 1:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123458	D114B	2022-02-22 @ 1:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123442	D116	2022-02-22 @ 1:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123441	D119	2022-02-22 @ 1:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123444	D124	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123468	D127	2022-02-22 @ 2:00 pm	2022-02-25 @ 10:00 am	< 0.3	2022-03-03
11123481	D207	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123470	D219	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123472	D227	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123475	D230	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123456	E104	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123443	E105	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123455	E106	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123454	E107	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115198	E108	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	0.6 ± 0.5	2022-03-03
11123448	E109	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115199	E115	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	1.2 ± 0.5	2022-03-03
11115200	E115	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03

March 3, 2022

**\*\* LABORATORY ANALYSIS REPORT \*\***

Radon test result report for:

<b>Kit #</b>	<b>Room Id</b>	<b>Started</b>	<b>Ended</b>	<b>pCi/L</b>	<b>Analyzed</b>
11115190	E118	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115186	E119	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115189	E119	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115191	E119	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115197	E123	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115194	E124	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115193	E125	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	0.5 ± 0.4	2022-03-03
11115196	E126	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11115195	E127	2022-02-22 @ 12:00 pm	2022-02-25 @ 11:00 am	< 0.3	2022-03-03
11123474	E208	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123462	E224	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123473	E224	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123471	E224	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11123467	E228	2022-02-22 @ 2:00 pm	2022-02-25 @ 12:00 pm	< 0.3	2022-03-03
11115158	MAIN OFFICE	2022-02-22 @ 10:00 am	2022-02-25 @ 10:00 am	< 0.3	2022-03-03

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, Inc. Job Number 204186

NOMINAL Conditions: Radon Conc 25.8 pCi/L Rel. Hum 50.1 % Temp. 70.9 F

Date Start: 2/18/22 Date Stop: 2/21/22 Date Start: \_\_\_\_\_ Date Stop: \_\_\_\_\_

Time Start: 0911 Time Stop: 0911 Time Start: \_\_\_\_\_ Time Stop: \_\_\_\_\_

Device No.'s: (3) Char Bags -  
11113484, 1112998, 20107126 Device No.'s: \_\_\_\_\_

23 Right

Date Start: \_\_\_\_\_ Date Stop: \_\_\_\_\_ Date Start: \_\_\_\_\_ Date Stop: \_\_\_\_\_

Time Start: \_\_\_\_\_ Time Stop: \_\_\_\_\_ Time Start: \_\_\_\_\_ Time Stop: \_\_\_\_\_

Device No.'s: \_\_\_\_\_ Device No.'s: \_\_\_\_\_

Date Start: \_\_\_\_\_ Date Stop: \_\_\_\_\_ Date Start: \_\_\_\_\_ Date Stop: \_\_\_\_\_

Time Start: \_\_\_\_\_ Time Stop: \_\_\_\_\_ Time Start: \_\_\_\_\_ Time Stop: \_\_\_\_\_

Device No.'s: \_\_\_\_\_ Device No.'s: \_\_\_\_\_

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)  
Background = 7 µR/h Elevation = 820 ft



MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within  $\pm 25\%$  of the chamber's reference value (25.7 pCi/L).

---

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
11113484	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK1		1	27.9
11122998	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK2		1	26.0
20107126	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK3		1	27.6

---



## Radon Test Kit Chain of Custody

Project Name: MCPS Radon – February 2022 Schools

Name of Schools:

1. Dufief ES
2. Emory Grove Center
3. Fields Road ES
4. Forest Oak MS
5. Gaithersburg ES
6. Gaithersburg MS
7. Jones Lane ES
8. Rachel Carson ES
9. Rosemont ES
10. Shady Grove MS
11. Summit Hall ES
12. Washington Grove ES

---

	Date	Initials
Radon Test Kits Deployed	02/22/2022	PM
Radon Test Kits Collected	02/25/2022	PM
Radon Test Kits Shipped to Lab*	02/25/2022	JM
Radon Test Kits Received by Lab*	02/28/2022	PM

\*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759